



EXTERNAL FINISHES

2

External Finish 001
INTEGRAL COLOUR OF RENDER
RAL 7035 'Light Grey'
LRV: 58.34

1

External Finish 001
PAINTED FINISH TO RENDER, TO CREATE SUBTLE PATTERN
RAL Design 000 80 00 'Foggy Grey'
LRV: 58.95

4

External Finish 004 – Shop Window Frame & External Door Colour
POLYESTER POWDER COATED FINISH
RAL 7026 'Signal Grey'
LRV: 8.27

9 10

External Finish 003 – Window Frame & Balustrade Colour
POWDER COATED FINISH
RAL Design 040 70 40 'Apricot Red'
LRV: 41.53

6

External Finish 005 – Shop Front Colour
PAINTED FINISH
RAL Design 150 40 20 'Firm Green'
LRV: 14.64

EXTERNAL TILED FINISHES – REFER ALSO TO DR-A-340 DETAILED ELEVATIONS DRAWING SERIES FOR TILE SETTING OUT

3

External Finish 003 – Wall Tile
TILED FINISH – TO FORM 'YMCA' USING WALL TILE
Domus 1 Color Matt, DCORM01, Matt Finish
LRV: TBC

3

External Finish 003 – Wall Tile
TILED FINISH – HIGHLIGHT/ FEATURE COLOUR
Domus 1 Color Matt, DCORM28, Matt Finish
LRV: TBC

3

External Finish 003 – Wall Tile
TILED FINISH – TO SPACE BETWEEN WINDOWS AT GROUND FLOOR LEVEL
Domus 1 Color Matt, DCORM08, Matt Finish
LRV: TBC

3

External Finish 003 – Wall Tile
TILED FINISH – PRINCIPAL COLOUR 01
Domus 1 Color Matt, DCORM35, Matt Finish
LRV: TBC

3

External Finish 003 – Wall Tile
TILED FINISH – TO SPACE BETWEEN WINDOWS AT GROUND FLOOR LEVEL
Domus 1 Color Matt, DCORM21, Matt Finish
LRV: TBC

3

External Finish 003 – Wall Tile
TILED FINISH – PRINCIPAL COLOUR 02
Domus 1 Color Matt, DCORM36, Matt Finish
LRV: TBC

3

External Finish 003 – Wall Tile
TILED FINISH – HIGHLIGHT/ FEATURE COLOUR
Domus 1 Color Matt, DCORM22, Matt Finish
LRV: TBC

3

External Finish 003 – Wall Tile
TILED FINISH – BASE COLOUR
Domus 1 Color Matt, DCORM29, Matt Finish
LRV: TBC

This document is © Bond Bryan Architects Ltd
If in doubt ASK. Drawing measurements shall not be obtained by scaling. Verify all dimensions prior to construction.
Immediately report any discrepancies on this document to the Originator. This document shall be used in conjunction with associated models, specifications and related consultant documents.

Key plan	North
----------	-------

- PROPOSED ELEVATIONS KEY**
- 1** EXTERNAL WALL INSULATION SYSTEM WITH SILICATE RENDER FINISH, PAINTED WITH STENCIL PATTERN DESIGN
NBS M21/ 210D
 - 2** EXTERNAL WALL INSULATION SYSTEM WITH SILICATE RENDER FINISH, PLAIN COLOUR, NO PATTERN
NBS M21/ 210D
 - 3** EXTERNAL WALL INSULATION SYSTEM WITH TILED FINISH
NBS M21/ 210E & NBS M40/ 110C-K
 - 4** CURTAIN WALL SYSTEM
NBS H11/ 150A
 - 5** NEW STALL RISER WITH TILED FINISH
NBS M40/ 110H
 - 6** TIMBER BOXING TO PROVIDE SIGNAGE AREA & RETAIL UNIT DIVIDERS; TO INCLUDE PATTERNSING; REFER TO DETAIL DRAWINGS, PAINTED FINISH
NBS M60/ 150B
 - 7** NEW TILED FINISH TO ACCESS RAMP & STAIR
NBS M40/ 110H
 - 8** NEW METAL CHANNEL AT FIRST FLOOR & GROUND FLOOR JUNCTION WITH INTEGRATED LED LIGHTING STRIP
 - 9** DESIGNATED SHOP SIGNAGE AREA
 - 10** NEW PAINTED FINISH TO EXTERNAL METALWORK (RAILINGS)
NBS M60/ 150C
 - 10** NEW DOUBLE-GLAZED, ALUMINIUM FRAMED EXTERNAL WINDOWS
NBS L10/ 330A

P02 Exterior Finishes Board Updated for Planning Conditions Discharge JW 04/12/2024

P01 Exterior Finishes Board Submitted for Planning Conditions Discharge JM/ JW 07/10/2024

Rev.	Description	Drawn	Checked	Date

B
BOND BRYAN
info@bondbryan.co.uk
www.bondbryan.co.uk

Barnsley Metropolitan Borough Council
Barnsley Levelling Up Fund
Barnsley YMCA/Chilypop

Exterior Finishes Board

Originator project ref 2304B	Purpose of Issue Planning
Scale(s) 1:50	Revision description Preliminary
Paper size A0	

project	originator	volume	level	type	rate	number	revision
BALU-BBA-YM-XX-DR-A-8310	BOND BRYAN						P02