

Reference	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m)	Scaled Tree Diagram (m)	Notes	Recommendations			Vigour		Amenity Value		
								(Independent of any development proposals)			Physiological Condition	Structural Condition		Life Expectancy (yrs)	Retention Category
								Priority	Inspect Freq (yrs)						
T1	Mature Poplar Populus sp.	10	2	74	0 12 6		Position: Adjacent canal. Form: Single stemmed with a major lean and an unbalanced crown. History: No evidence of previous pruning. Defects: Very poor specimen, partially collapsed.	Remove.	Moderate	Low	Moderate	10-20	U		
								Moderate	N/A	Very Poor					
T2	Mature Poplar Populus sp.	21	10	77	2 7 8		Position: Adjacent canal. Form: Single stemmed and leaning with an unbalanced crown. History: No evidence of previous pruning. Defects: Major limb failure has left major tear wound at 6m.	Remove.	Moderate	Low	Moderate	10-20	U		
								Moderate	N/A	Very Poor					
T3	Mature Poplar Populus sp.	22	10	72	5 10 5		Position: Adjacent canal. Form: Multi-stemmed at 6m with a balanced crown. History: No evidence of previous pruning. Defects: Significant deadwood and broken branch to lower crown.	Crown clean.	Moderate	Moderate	Moderate	40+	B		
								Moderate	1	Good	Fair				
T4	Mature Poplar Populus sp.	22	5	84	10 8 0		Position: Adjacent canal. Form: Single stemmed and leaning with an unbalanced crown. History: No evidence of previous pruning. Defects: Major cavity at base.	Crown clean, decay detection required.	Moderate	Moderate	Moderate	20-40	B -		
								Moderate	1	Fair	Poor				
T5	Mature Wild Cherry Prunus avium.	10	6	46	5 3 1 5		Position: Adjacent boundary with number 73. Form: Twin-stemmed at 4m with a sparse crown. History: Half of crown is dead. Defects: Major bark wound at ground level to 1.5m, x40% of girth.	Remove limb overhanging boundary at main fork. Monitor.	Low	Low	Fair	<10	C -		
								High	1	Very Poor					
T6	Mature Wild Cherry Prunus avium.	17	4	69	8 6 6 10		Position: Adjacent boundary with number 73. Form: Twin-stemmed at ground level with a balanced crown. History: No evidence of significant pruning. Defects: Minor deadwood to lower crown. Other: Actual stem diameter = 61 & 33cm.	Deadwood.	High	Moderate	Good	40+	B		
								Low	3	Fair					
T7	Early-Mature Wild Cherry Prunus avium.	17	6	49	4 5 1 6		Position: Adjacent boundary with number 73. Form: Twin-stemmed at 0.5m with a full crown. History: No evidence of significant pruning. Defects: Minor deadwood to lower crown. Other: Actual stem diameter = 35 & 34cm.	Deadwood.	Low - Moderate	Moderate	Good	40+	B-		
								Low	3	Fair					

Reference	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m)	Scaled Tree Diagram (m)	Notes	Recommendations (Independent of any development proposals)			Vigour	Amenity Value	Life Expectancy (yrs)	Retention Category
								Priority	Inspect Freq (yrs)	Physiological Condition				
T15	Semi-Mature Red Horse Chestnut Aesculus x carnea.	10	3	35	4 4 4		Position: Situated on third party land. Form: Twin-stemmed at 3m with a full crown. History: No evidence of significant pruning. Defects: No significant defects. Other: Limited inspection.	No action required.			High	Moderate	40+	B
								n/a	3	Good				
T16	Semi-Mature Elm Ulmus sp.	15	2	40	4.5 4.5 4.5		Position: Situated on third party land. Form: Single stemmed and vertical with a well-formed crown. History: No evidence of significant pruning. Defects: No significant defects. Other: Attractive specimen.	No action required.			High	High	40+	A
								n/a	3	Good				