* ALL NEW LEVELS ARE CHANNEL LEVELS (BOK)

BRADBERRY BA

FENCE TO BE RE-ALIGNED

NEW GULLY IN MIN 150 C15/20 CONCRETE SURROUND

NEW GULLY DRAIN INTO NEW SPUR.

TREE AND BUSH NOT PRESENT (PREVIOUSLY REMOVED)

NEW RODDING EYE SPUR

REMOVE EXISTING GULLY AND MAKE GOOD

EXISTING DRAIN.

NEW RETAINING WALL — SEE SKETCH SK2

TREE NOT PRESENT (PREVIOUSLY REMOVED)

SURFACE EXTENT

SPEED BUMP

TIMBER P+R FENCE

TARMAC SURFACE

FOOTWAY

GRASS

PAVED

GATE

PARKING BAYS

KERB

SB

SP

KEY

30 MM SMA 10 SURFACE COURSE PD6691 ANNEX D 40/60 OR PMB BINDER GRADE

ON 60 MM AC 20 DENSE BINDER COURSE PD6691 ANNEX B 100/150 BINDER GRADE

ON 150 MM NOT TYPE 1 GRADED STONE BASE

ON 210 MM MAX OF 2 SUB-BASE DEPENDANT ON SUB-GRADE. TO BE AGREED ON SITE

* KERBS TO BE HB2 TYPE GENERALLY. (STRAIGHT, CURVED OR QUADRANT AS NECESSARY)

Rev. A: Re-scaled and notes re trees added.

CAR PARK EXTENSION - SETTING OUT

(1:150)

BSL - SK 1 A.