

# VIKING STAR IV Roller Shutter Door

## **SPECIFICATION:-**

The shutter curtain is constructed from suitable interlocking galvanised steel laths and galvanised "T" section bottom rail, running in galvanised steel side channels, mounted on mild steel / galvanised steel support angles / boxes, which are bolted to the structure.

The curtain is supported from a suitable steel tube barrel assembly at high level, running on steel bearings. The barrel assembly is supported between mild steel endplates.

All mild steel components are finished in one coat of primer.



## **APPLICATION:-**

Each door is purpose-made to suit dimensions and requirements and is suitable for all types of industrial use where insulation is not important.

## **OPERATION:-**

Electrical operation is by means of high quality single-phase tubular motor and

gearbox fitted within the barrel assembly. An emergency manual hand crank over-ride is provided as standard to allow operation of the door in case of power failure.



A SAFETY BRAKE is fitted to the non-drive end of the barrel assembly to prevent uncontrolled dropping of shutter curtain.

## **BS 13241 compliant & CE Marked**

## **OPTIONAL EXTRAS:-**

- Plastisol coated laths
- Galvanised steel coil casings
- Rubber bottom seals
- Wicket Gates
- Polyester powder coat finish
- Special electrical automation and safety devices.

**ADVANCED DOORS LTD**  
PARK MILL WAY, CLAYTON WEST,  
HUDDERSFIELD, WEST YORKSHIRE, HD8 9XJ.

TEL: (01484) 861112 FAX: (01484) 866700  
[www.advanceddoors.co.uk](http://www.advanceddoors.co.uk)



**ADVANCED DOORS LTD**  
31 TOLL PARK PLACE, WARD PARK EAST,  
CUMBERNAULD, G68 0LN.

TEL: (01236) 766229 FAX: (01236) 763876  
[www.advanceddoors.co.uk](http://www.advanceddoors.co.uk)