

Proven WT6000 Wind Turbine Mounted on TM1500 15m self supporting tower Noise Emission Report

GENERAL

The dB (A) scale is the most common measure used to quantify noise. It covers sound intensity over the entire audible scale *and* takes account of the sensitivity of the human ear to give an overall measure of "loudness".

TYPICAL dB(A) LEVELS

Sound Level	dB (A)
Threshold of hearing	0
Whisper	30
Talking	60
City Traffic	90
Rock Concert	120
Jet Engine (10m away)	150

CURRENT BEST PRACTICE

In assessing the noise from a proposed wind turbine installation we are often interested in what noise levels will be at various distances from the wind turbine. It is accepted practice to *calculate* noise contributions from the wind turbine. This is because it is only practical to *measure* the wind turbine contribution accurately when it is 10 dBA above background noise. For example, background noise in a "quiet" environment is typically 30-40 dBA making it impossible to *measure* contributions less than 40-50 dB(A).

PROVEN WT6000 WIND TURBINE NOISE CALCULATIONS

Figure 1 shows how the noise emitted by a Proven WT6000 wind turbine on a 15m mast will disperse over the local environment. Maximum noise output at the base of the machine was recorded at 60dB(A) at a wind speed of 20 m/s. The noise output at the base of the mast in light winds 5m/s was 40 dB(A). The sound meter was held at a height of 1.5m from the ground. Background noise is louder than the turbine when more than 25m from the mast in both cases.

Figure 2 shows how the combined noise of wind turbine plus background; this is what will be detected by the human ear.

Figure 3 graphs the dBA difference between wind turbine and background plus common complaint classifications. *It can be generally taken that there will be no noise complaints where the turbine specific noise is 10dBA less than background.* This happens at a distance of 40-75m depending on wind speed.

Details of the calculations used in these graphs are given in Appendices B & C.




Figure 1




Figure 2




Figure 3

NOTE ON MEASUREMENTS USED IN THIS REPORT

All measurements were taken on a portable SL-25 dBA sound meter at our demonstration wind turbine site in Kilmarnock. Proven Wind Turbines emit a swishing noise only - we do not believe full tonal analysis is needed for our small wind turbines (see also Appendix A).

COMMENT ON THE CALCULATIONS AND ASSUMPTIONS USED IN THIS REPORT

The above method does not take account of wind "streaming" noise to the downwind side of the turbine. In practice, turbine dBA levels will be shifted downwind by a variable amount depending on the individual site.

In both cases the dB(A) readings taken as coming from the wind turbine **certainly also included a contribution from background noise in a nearby tree**. Secondly, in the graphs shown, the typical background dBA readings have been chosen very conservatively (low).

Proven Energy Ltd
 Wardhead Park, Stewarton, Ayrshire, KA3 5LH, Scotland, UK
 Tel: +44 (0)1560 485 570
 Fax: +44 (0)1560 485 580
 email: info@provenenergy.com
 web: www.provenenergy.com

Appendix A - Noise Reduction Features in Proven Wind Turbines

Feature	Benefit
Proven rotors are specially designed to operate at low rpm (typical max Tip Speed Ratio 6)	Blades and bearings rotate slowly keeping air noise to a minimum.
Direct Drive Permanent Magnet Generator	There is no gearbox as the rotor is coupled direct to the generator. This eliminates the gearbox hum which is the main source of noise in turbines with gearboxes. There are no touching parts.
Specially shaped blade tips	The rounded tips on Proven Wind Turbine blades are designed to reduce the vortices present at the end of any aerofoil. This keeps wind noise to a minimum.

Appendix B - Calculating Sound Pressure Levels

DEFINITIONS

1. Sound Pressure Level in dB(A) = $10 \times \log_{10}$ (sound power in W/m²)

2. Sound Power in Watts/m² = $10^{0.1 \times (\text{dB}-120)}$

Given a sound power P_1 at distance d_1 from a noise source the sound power P_2 at distance d_2 may be calculated by the formula

$$3. P_2 = P_1 \left(\frac{d_1}{d_2} \right)^2$$

ADDING dBA SOUND PRESSURE LEVELS FROM DIFFERENT SOURCES AT POINT X

First convert the dBA ratings at their initial distances to sound powers using equation 2.


Use the equation 3 to work out the sound powers at point X where you are interested in the total sound pressure level

Add all the sound powers together to find P_{total}

Convert back using equation 1 to find $\text{dB(A)}_{\text{total}}$

Appendix C - Calculations used in this report

height to hub	15		dBA high	60								
height meter	1.5		dBA low	40								
initial height	13.5											
initial dist	0											
db=10log(power in w/m2)+120												
sound power=10^(0.1(db-120))												
horizontal distance (m)	actual distance	sound high (w/m2)	sound low (W/m2)	high wind WT2500 sound pressure level (dBA)	low wind WT2500 sound pressure level (dBA)	typical high wind background sound pressure level (dBA)	typical low wind background sound pressure level (dBA)	combined WT6000 plus background sound high	combined WT6000 plus background sound low	high wind combined WT6000 and background sound pressure level (dBA)	low wind combined WT6000 and background sound pressure level (dBA)	
0	13.5	0.000001	1E-08	60	40	60	35	0.000002	1.32E-08	63	41	
10	16.8	6.46E-07	6.46E-09	58	38	60	35	1.65E-06	9.62E-09	62	40	
20	24.1	3.13E-07	3.13E-09	55	35	60	35	1.31E-06	6.29E-09	61	38	
30	32.9	1.68E-07	1.68E-09	52	32	60	35	1.17E-06	4.85E-09	61	37	
40	42.2	1.02E-07	1.02E-09	50	30	60	35	1.1E-06	4.18E-09	60	36	
50	51.8	6.79E-08	6.79E-10	48	28	60	35	1.07E-06	3.84E-09	60	36	
60	61.5	4.82E-08	4.82E-10	47	27	60	35	1.05E-06	3.64E-09	60	36	
70	71.3	3.59E-08	3.59E-10	46	26	60	35	1.04E-06	3.52E-09	60	35	
80	81.1	2.77E-08	2.77E-10	44	24	60	35	1.03E-06	3.44E-09	60	35	
90	91.0	2.2E-08	2.2E-10	43	23	60	35	1.02E-06	3.38E-09	60	35	
100	100.9	1.79E-08	1.79E-10	43	23	60	35	1.02E-06	3.34E-09	60	35	
						sound w/m	sound w/m2					
						0.000001	3.16E-09					



NOISE REPORT STATEMENT - July 07

This measurement has been taken using a handheld noise meter at our wind turbine test facility located at Proven Energy Ltd, Stewarton, Scotland. The results are merely an indication of the level of noise produced by our wind turbines and it may be inconsistent when measuring a similar wind turbine at a different location.

Proven Energy is committed to providing high quality products, and is in the process of commissioning and collating further noise reports on its range of wind turbines.

Proven Energy Ltd
Wardhead Park
Stewarton
KA3 5LH
Scotland
info@provenenergy.com