


REPLACE ROOF WITH APPROPRIATE
SLATE COVERING IN ORDER THAT IT
IS IN KEEPING WITH OTHER COTTAGES
ON 'REFORM ROW'.




CHIMNEY TO BE REPOINTED
WITH APPROPRIATE MORTAR
SOME HEAVILY ERODED STONEWORK
TO BE REPLACED AND
ALL STONEWORK TO BE REPOINTED
WITH LIME BASED NHL




SOME HEAVILY ERODED STONEWORK
TO BE REPLACED AND ALL STONEWORK
TO BE REPOINTED WITH LIME BASED NHL