



410050N

410000N

409950N

409900N

- GENERAL SAFETY NOTES**
- WHERE THE BASE (ROAD BASE) HAS BEEN USED AS A TEMPORARY RUNNING SURFACE DURING THE CONTRACT IT SHALL BE THOROUGHLY CLEANED AND POWER WASHED AS NECESSARY AFTER DRIVING AND IMMEDIATELY BEFORE THE BRIDGE COURSE IS Laid A JACK COAT OF BITUMEN EMULSION CLASS 40-45 @ 4-5 LITRE TO TON SHALL BE APPLIED AT A RATE OF 2.5-3.0 LITRE TO SQ METER
 - ALL RADIIUS KERBS WITH A RADIIUS OF 12m OR LESS SHALL BE FORMED WITH PROPRIETARY RADIIUS KERBS
- HEALTH & SAFETY**
- CONTRACTOR SHOULD BE AWARE OF GENERAL CONSTRUCTION RISKS TO PREVENT SLIPS, TRIPS AND FALLS AND TAKE NECESSARY PRECAUTIONS WITHOUT SPREAD INSTRUCTION
- ROADS & DRAINAGE**
- CONTRACTOR TO PROVIDE TRENCH SUPPORTS AS APPROPRIATE AND ENSURE THAT PLANT REMAINS A SAFE DISTANCE FROM TRENCHES PRIOR TO INSTALLING DRAINAGE
 - THE TIME THAT EXCAVATIONS ARE OPEN ON SITE SHOULD BE KEPT TO A MINIMUM AND ALL TRENCHES SHOULD BE COVERED BY A BOARD
 - CONNECTIONS TO EXISTING SEWERS TO BE MADE BY APPROVED CONTRACTOR ONLY
 - CONTRACTOR TO HAVE OPERATING AWARE OF ASSOCIATED DANGERS TO HEALTH SUCH AS LEPTOSPIROSIS (WELLS DISEASE) AND RECOMMENDED PRECAUTIONS, ADEQUATE WELFARE FACILITIES AND PROTECTIVE CLOTHING TO BE PROVIDED AS REQUIRED
 - UNFINISHED MANHOLES MUST BE COVERED WITH LOAD BEARING MATERIALS AND SURROUNDED WITH RAILINGS
- TRIPS & CABLES**
- CONTRACTOR TO OBTAIN ALL SERVICE RECORDS PRIOR TO WORKS COMMENCING
 - SERVICE RECORDS TO BE REFERRED TO PRIOR TO WORK COMMENCING. CONTRACTOR TO PROCEED WITH CAUTION AND SERVICES TO BE LOCATED BY HAND AND PROTECTED ACCORDINGLY
- CONTAMINATION**
- CONTRACTOR TO ENSURE RELEVANT MEASURES ARE TAKEN TO KEEP PLANT AND PEOPLE A SAFE DISTANCE FROM STEEP SLOPES DURING THE WORKS
 - CONTRACTOR TO ENSURE THAT PROCEDURES ARE IN PLACE TO KEEP PEOPLE A SAFE DISTANCE FROM WORKING PLANT WHERE NECESSARY
 - CONTRACTOR TO REFER TO GROUND INVESTIGATION REPORT FOR CONTAMINATION TESTS AND TO PROVIDE ADEQUATE WELFARE FACILITIES AND PROTECTIVE CLOTHING AS REQUIRED

- DESIGN NOTES**
- PROPOSED LAYOUTS HAVE BEEN BASED ON THE EXISTING TOPOGRAHICAL SURVEY BY SURVEY OPERATIONS DATED: DRAWING REF: 23057 (DATED NOVEMBER 2022)
 - ALL WORKS TO COMPLY WITH CURRENT VERSIONS OF THE FOLLOWING DOCUMENTS
 - ROAD MARKING FOR ROADS AND SPACES (MARS)
 - SPECIFICATION FOR HIGHWAY WORKS (SHW)
 - LOCAL AUTHORITY DESIGN CODE AND SPECIFICATION
 - PRIOR TO COMMENCING WORKS THE CONTRACTOR SHOULD INVESTIGATE AND LOCATE ANY NECESSARY ANY STATUTORY UNDERTAKERS EQUIPMENT WITHIN THE NEW ACCESS AND DISCUSS REQUIREMENTS FOR LIFTING/CONVERSION AND PROTECTION WITH THE RELEVANT UNDERTAKER
 - ALL WORKS WITHIN THE PUBLIC HIGHWAY TO MEET LOCAL AUTHORITY REQUIREMENTS. CONTRACTOR TO APPLY FOR ROAD OPENING NOTICES ETC AS REQUIRED
 - ROAD CONSTRUCTION DETAIL SUBJECT TO CORROBORATION OF ORN VALUES. CONTRACTOR TO ALLOW FOR LIA TESTS TO BE UNDERTAKEN IN ACCORDANCE WITH LOCAL AUTHORITY HIGHWAY SPECIFICATIONS PRIOR TO WORKS COMMENCING
 - WORKS WITHIN THE CONSTRUCTION ACCORDANCE WITH THE RELEVANT STANDARDS. BRIDGE SPECIFICATIONS AND GUARANTEE ANY RELIES IDENTIFIED ON SITE ARE TO BE ADDRESSED TO THE SATISFACTION OF BRIDGES UK THROUGH THE DEVELOPMENT MANAGEMENT TEAM

SUBJECT TO LOCAL AUTHORITY
APPROVAL

KEY

- VEGETATION TO BE REMOVED/CUT BACK
- EXISTING KERBS TO BE REMOVED
- EXISTING CARRIAGEWAY SURFACING TO BE PLANNED OFF (REFER TO DRAWING T11 FOR DETAILS)
- EXISTING FOOTWAY SURFACING TO BE PLANNED OFF (REFER TO DRAWING T11 FOR DETAILS)
- EXISTING GULLY TO BE ABANDONED

23050208	AMENDED FOLLOWING STAGE 10 RMA	JF	AE	3
23070208	REV AMENDED: SECTION LABELS ADDED	SR	AE	2
11060208	ISSUED FOR APPROVAL	NA	AE	1
DATE	DESCRIPTION	DR	CHK	REV

INFORMATION



CLIENT: VISTRY GROUP

PROJECT: SHAW LANE
CARLTON

TITLE: S278 SITE CLEARANCE - OFFSITE WORKS
SHEET 2 OF 2

PROJECT No:	DISCIPLINE:	SCALE:
24307	CIVIL	@:A0 1:250
DRAWING No:		REV:

D523

3