

Tree No	Species	Height (m)	Clear Stem Height	DBH 1 (m)	DBH 2 (m)	DBH 3 (m)	DBH 4 (m)	DBH 5 (m)	DBH Calc (m)	Crown Spread N	Crown Spread E	Crown Spread S	Crown Spread W	Age Class	Crown	Stem	Basal	Physiological Condition	Comment	Recommendations	Retention Category	Life Expectancy	RPA radius (m)	RPA (m ²)	
1	Fagus sylvatica 'Purpurea' (Copper Beech)	15	3	0.620					0.620	6	7	5	7	Mature	Good	Good	Good	Good			B	1/2	>40 yrs	7.4	174
3	Prunus avium (Cherry)	8	3	0.310					0.310	4	3	5	3	Mature	Fair	Fair	Fair	Fair			C	1/2	20 to 40 yrs	3.7	43
4	Prunus avium (Cherry)	12	5	0.020	0.023				0.030	1	3	7	3	Mature	Fair	Fair	Fair	Fair			C	1/2	20 to 40 yrs	0.4	0
5	Acer pseudoplatanus (Sycamore)	15	5	0.390	0.270				0.660	6	3	4	5	Semi-mature	Fair	Fair	Fair	Fair			B	2	>40 yrs	7.9	197
6	Acer pseudoplatanus (Sycamore)	15	3	0.250	0.240	0.120			0.367	6	5	4	3	Semi-mature	Fair	Fair	Fair	Fair			B	2	>40 yrs	4.4	61
7	Crataegus monogyna (Hawthorn)	6	2	0.360					0.360	3	3	3	3	Mature	Fair	Fair	Fair	Fair			C	1	20 to 40 yrs	4.3	59
8	Abies nordmanniana (Nordman Spruce)	14	4	0.350					0.350	2	2	4	3	Semi-mature	Fair	Fair	Fair	Fair			C	1/2	>40 yrs	4.2	55
9	Fraxinus excelsior (Ash)	16	6	0.300					0.300	4	4	4	4	Semi-mature	Fair	Fair	Fair	Fair			B	1/2	>40 yrs	3.6	41
10	Fraxinus excelsior (Ash)	15	6	0.330					0.330	6	2	2	4	Semi-mature	Fair	Fair	Fair	Fair			C	1/2	20 to 40 yrs	4.0	49
11	Quercus robur (Oak)	16	4	0.520					0.520	8	5	4	4	Mature	Fair	Ivy	Fair	Fair	Ivy	Sever Ivy	B	1/2	>40 yrs	6.2	122
12	Fraxinus excelsior (Ash)	18	8	0.450					0.450	5	4	7	3	Semi-mature	Fair	Ivy	Fair	Fair	Ivy	Sever Ivy	B	2	>40 yrs	5.4	92
13	Fraxinus excelsior (Ash)	18	5	0.520					0.520	3	6	6	5	Mature	Fair	Ivy	Fair	Fair	Ivy	Sever Ivy	B	2	>40 yrs	6.2	122
14	Abies nordmanniana (Nordman Spruce)	12	4	0.280					0.280	2	1	2	5	Semi-mature	Fair	Ivy	Fair	Fair	Ivy	Sever Ivy	C	1/2	20 to 40 yrs	3.4	35
15	Fraxinus excelsior (Ash)	18	6	0.670					0.670	5	5	5	5	Mature	Fair	Ivy	Fair	Fair	Ivy	Sever/remove ivy	B	1/2	>40 yrs	8.0	203
G2	Prunus avium (Cherry)	9	4	0.340					0.340	1	2	4	2	Semi-mature	Fair	Ivy	Fair	Fair	Start of group of 5. The other 4 stems are located within 4m to the north and west of this tree.	Sever Ivy	C	1	20 to 40 yrs	4.1	52
G2	Prunus avium (Cherry)	9		0.250	0.320	0.270	0.300	0.360	0.676	4	4	4	4		Fair	Ivy	Fair	Fair	End of group of 5. The other 4 stems are located within 4m to the south and east of this tree.	Sever Ivy	C	2	20 to 40 yrs	8.1	207
G16	Acer pseudoplatanus (Sycamore)	17	3	0.450	0.180				0.485	4	6	4	5	Semi-mature	Fair	Ivy	Fair	Fair	Start of linear group of 8 similar trees including sycamore ash and hawthorn. Ivy infested	Sever Ivy	B	2		5.8	106
G16a	Fraxinus excelsior (Ash)	17	2	0.750					0.750	6	6	6	6	Mature	Fair	Ivy	Fair	Fair	End of linear group 16	Sever Ivy	B	2	>40 yrs	9.0	255
G19	Malus sylvestris (Apple)	6	2	0.230					0.230	2	2	2	2	Over Mature	Fair	Fair	Fair	Decline	One of 13 similar trees within 10m of here. Group is rectangular and extends 20m along the south east boundary and 10m along the north east boundary.		B	3	20 to 40 yrs	2.8	24
G17	X Cupressocyparis leylandii (Leyland Cypress)	10	1	0.280					0.280	2	2	2	2	Mature	Fair	Fair	Fair	Fair	Start of linear group of 22 similar stems		C	1		3.4	35

Tree No	Species	Height (m)	Clear Stem Height	DBH 1 (m)	DBH 2 (m)	DBH 3 (m)	DBH 4 (m)	DBH 5 (m)	DBH Calc (m)	Crown Spread N	Crown Spread E	Crown Spread S	Crown Spread W	Age Class	Crown	Stem	Basal	Physiological Condition	Comment	Recommendations	Retention Category	Life Expectancy	RPA radius (m)	RPA (m ²)
G21	Ilex aquifolium (Holly)	8	0	0.190	0.100				0.215	2	2	2	2	Semi-mature	Fair	Fair	Fair	Fair	Within group of approximately 20 stems extending north east to group 19 and south east to the site boundary. trees to 17m in height and dbh to 300mm. species present are sycamore, downy birch and wild cherry.		B 2	20 to 40 yrs	2.6	21
G30	Quercus robur (Oak)	14	5	0.600					0.600	5	5	5	2	Semi-mature	Fair	Fair	Fair	Fair	Group G30 consists of sycamore, ash and beech to 20m in height. The trees are on adjacent 3rd party land and flank the south western boundary of the site. The group extends 7m away from boundary and all the way to the road.		B 1	>40 yrs	7.2	163
31	Acer pseudoplatanus (Sycamore)	20	2	0.400	0.400				0.566	5	5	5	5	Mature	Fair	Fair	Fair	Fair	Measurements estimated as tree on adjacent land.		B 1	>40 yrs	6.8	145
32	Acer pseudoplatanus (Sycamore)	18	2	0.800					0.800	4	8	5	5	Mature	Fair	Fair	Fair	Fair	Measurements estimated as tree on adjacent land.		B 2	>40 yrs	9.6	290
33	Acer pseudoplatanus (Sycamore)	20	4	0.700					0.700	3	7	6	5	Mature	Fair	Fair	Fair	Fair	Measurements estimated as tree on adjacent land.		B 1	>40 yrs	8.4	222
34	Acer pseudoplatanus (Sycamore)	20	5	0.750					0.750	4	8	4	5	Mature	Fair	Fair	Fair	Fair	Measurements estimated as tree on adjacent land.		B 1	>40 yrs	9.0	255
35	Acer pseudoplatanus (Sycamore)	20	5	0.800					0.800	6	8	4	7	Mature	Fair	Fair	Fair	Fair	Measurements estimated as tree on adjacent land.		B 1	>40 yrs	9.6	290
36	Acer pseudoplatanus (Sycamore)	20	7	0.650					0.650	4	9	3	5	Mature	Fair	Fair	Fair	Fair	Measurements estimated as tree on adjacent land.		B 2	>40 yrs	7.8	191
37	Acer pseudoplatanus (Sycamore)	17	4	0.450					0.450	7	5	4	5	Mature	Fair	Fair	Fair	Fair	Measurements estimated as tree on adjacent land.		C 1	>40 yrs	5.4	92