Rev	Date	Description
XX	XX:XX:XX	XXXX

The external play area for the foundation classrooms is to have new covered areas to provide shade and shelter.

Remove rainwater pipes, seal off redundant drains

Grub up foul and SW drains and 2 No gullies in area of extension

Lay new Foul and SW drains complete with gullies and connections for new RWPs

Form new extension to classrooms providing new entrance area with lockers

Lift and relay playground area to revised falls to new surface water drainage

Contractor's temporary mains electricity and water supplied from the boiler house

Contractor's site compound and access to the works areas

Temporary access road formed up to playground area

Excavate and extend the grassed embankment to accommodate the new extension to Classrooms 48 and 53

GROUND FLOOR PLAN

ARCUS CONSULTING

Arcus Consulting LLP
Leeds 0113 281 5350 Manchester 0161 905 3222 Sheffield 0114 227 0002
Liverpool 0151 708 1080 Newcastle 0191 272 5781 info@arcus.uk.com
www.arcus.uk.com

Client
BARNSLEY MBC

Project
BRIERLEY CE PRIMARY SCHOOL
BRIERLEY BARNSLEY

Title
PROPOSED FLOOR PLAN OPTION 3

Scale	Date	Stage
1:100	06:04:09	PL
Job No	Drawing No	Rev
1428	005	XX
Drawn	Approved	
AW	XX	

This drawing is the copyright of Arcus. Contractors must check all dimensions on site. Do not scale the drawings.Only figured dimensions are to be worked to.