



Planting Schedule

Proposed Trees				
Nr	Code	Tree Name	Specification	Girth Height
5 -	Ac	Acer campestre	Selected Standard :Clear Stem 175-200 :RB 10-12cm 300-350cm	
7 -	Bp	Betula pendula	Selected Standard :Clear Stem 175-200 :RB 12-14cm 300-350cm	
2 -	Cbe	Carpinus betulus	Heavy Standard :Clear Stem 175-200 :RB 12-14cm 350-400cm	
6 -	Pp	Prunus padus	Selected Standard :Clear Stem 175-200 :RB 10-12cm 300-350cm	
1 -	Qr	Quercus robur	Heavy Standard :Clear Stem 175-200 :RB 12-14cm 350-400cm	
7 -	Sau	Sorbus aucuparia	Selected Standard :Clear Stem 175-200 :RB 10-12cm 300-350cm	
2 -	Tc	Tilia cordata	Heavy Standard :Clear Stem 175-200 :RB 12-14cm 350-400cm	
Total :29 No.				

Hedges				
Nr	Code	Tree Name	Specification	Girth Height
752 -	PIR	Prunus laurocerasus 'Rotundifolia'		60-80cm
Total :752 No.				

Proposed Shrubs				
Nr	Code	Plant Name	Height	Cntr (l) Nr/m2
39 -	CBM	Ceanothus 'Blue Mound'	30-40cm 5L	4/m²
27 -	Ct	Choisya ternata	30-40cm 5L	3/m²
38 -	HRE	Hebe albicans 'Red Edge'	20-30cm 2L	4/m²
28 -	LaH	Lavandula angustifolia 'Hidcote'	20-30cm 2L	4/m²
26 -	PIRR	Photinia fraseri 'Red Robin'	40-60cm 5L	4/m²
74 -	PIOL	Prunus laurocerasus 'Otto Luyken'	40-60cm 5L	4/m²
17 -	PSR	Pyracantha saphyr 'Red'	40-60cm 5L	4/m²
36 -	Vmi	Vinca minor	20-30cm 2L	4/m²
17 -	Vi	Viburnum tinus	40-60cm 5L	3/m²
Total :302 No.				

Native Hedge Mix (5/m)		
Nr	Code	Plant Name
181 -	Ac	Acer campestre
106 -	Cav	Corylus avellana
358 -	Cm	Crataegus monogyna
106 -	la	Ilex aquifolium
211 -	Psp	Prunus spinosa
106 -	Rca	Rosa canina
106 -	Vo	Viburnum opulus
Total :1174 No.		

This drawing is the copyright of Rosetta Landscape Design and cannot be reproduced in any form without the express consent of the company. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. If in doubt please ask.

This drawing has been prepared for the purpose of planning approval.

Planting Notes
Topsoil shall be a minimum of 400mm depth over planting beds and graded to fall. Imported topsoil must be take place in wet/ waterlogged conditions.
Herbicide and cultivation: Topsoil to be treated with two applications of herbicide prior to planting, where necessary, strictly in accordance with the Control of Pesticides Regulations 1986 (as amended 1997, or, otherwise, updated/superseded legislation) and following manufacturer's instructions by qualified staff. The topsoil shall than be cultivated to 150mm depth.
Planting: All planting and turfing shall conform to BS: 3938: 1992 and BS:4428: 1989.
Trees: Standard trees to be planted in pits 800x800x450mm or dimensions of rootball, whichever is greater. Heavy and Extra Heavy Standard trees to be planted in pits 1000x1000x600mm or dimensions of rootball, whichever is greater.

shall be strong enough not to split when driven into the ground and when ties are nailed to them (both initially and when adjusted). For Feathered trees use 2Nr stakes (1.4m by 75mm) to be driven into ground 800mm, leaving 600mm above ground. For Selected Standard Trees 2Nr stakes (1.7m by 100mm) and cross bar are required, stakes to be driven a 400x100x15mm cross bar. Stakes to be driven into ground 1m leaving 1.2m above ground.

spacer, hollowed on both sides and twice slotted of such a width that the tree is held away from the stake and/or cross bar, and such that it does not rub against the stake and/or cross bar in any location and fixed so that nails do not scar with 10mm diameter heads.

Container grown shrubs, transplants and whips: Shrubs and transplants shall be planted in pits 300x300x400mm depth), and the backfill shall include 3 litres of peat-free tree and shrub compost. Where two or more shrub species are indicated within a single bed each species shall be randomly mixed throughout the bed in groups of 3/5.
Herbicide: Spot treat with herbicide throughout the maintenance period in accordance with the manufacturer's instructions.
Mulch: Planting beds to receive 75mm depth pulverized ornamental bark mulch. Native woodland/edge plants to be planted with 800g flax fibre mulch mat pinned to soil. Native hedgerow to be planted through 800g flax fibre mulch roll, prevent spillage.

Plant position: Final position of trees and shrubs subject to confirmation of service location and approval of statutory undertakers.
Protection to planting: Native hedgerow plants to be protected by spiral shelters. Native trees and shrubs within mixes to be protected by shelter guards as supplied by Acorn Planting Products Ltd (01508 528763), or equivalent.
Ornamental hedging: Hedges to comprise a single row of plants. 400mm wide trench excavated to take plants and topsoil cultivated to 400mm depth prior to application of fertiliser.

Grass: All turf/seeded areas to be cultivated and levelled as required removing any stones, rubble, subsoil, general construction waste.
Planting Season: Bare-root shrubs to be planted between mid-November and mid-March dependant upon the planting season.

LEGEND

Existing vegetation to be retained

Existing vegetation to be removed

Proposed tree Standard (Heavy)

Proposed tree Standard (Selected)

Proposed shrub bed

Proposed hedge

Proposed native hedge mix

Proposed grass

Rev G: Oak and Lime trees removed from POS as requested by Parish Council.

Rev G: Trees removed from behind war memorial. Planning request.

Rev E: Further hedge and tree planting to meet planning approval

Rev D: Additional hedge planting required for planning condition approval.

Rev C: Revised to Pearce Bottomley 'Proposed Housing layout' 5148-90 01-C09-GA - 05Oct20 (BP)

Rev B: Revised to client comments - 10Mar20 (BP)

Rev A: Revised to client comments - 06Mar20 (BP)

Base: Pearce Bottomley 'Proposed Housing layout' 5148-90 02-C09-GA received 04Mar20

PROJECT Halifax Road, Thurgoland

TITLE Detailed Landscape Proposals

CLIENT Arncliffe Homes Ltd

DATE XX Mar 20 SCALE 1 : 200 SHEET A0

DRAWN BP DRAWING NO 3619/1

CHECKEDBP REVISION H