



SURFACE FINISHES

- DBM CARRIAGEWAY
30mm AC10 DENSE SURF 100/150
- BLOCK PAVED SHARED SURFACE
60mm PCC BLOCKS
BRINDLE COLOUR - SHARED SURFACE
CHARCOAL COLOUR - HARD MARGIN
- BLOCK PAVED RAMP
60mm PCC BLOCKS
- DBM FOOTWAY / DRIVE CROSSING
25mm AC6 DENSE SURF 160/220
- EXTENT OF CARRIAGEWAY
REINSTATEMENT / RESURFACING
- PCC TACTILE PAVING FLAGS
400 x 400 x 65mm (BUFF)

KERB TYPE DETAILS

- 125 x 255mm PRECAST CONCRETE
HALF BATTERED KERB WITH 100mm FACE
- 125 x 175mm PRECAST CONCRETE CHAMFERED
KERB WITH 25mm FACE
- 125 x 150mm PRECAST CONCRETE SQUARE EDGE
CHANNEL BLOCK LAID FLUSH
- 125 x 175mm PRECAST CONCRETE PLASMOBILITY
KERB 89 WITH 30mm FACE (SHARED SURFACE)
- TRANSITION KERB - HALF BATTERED TO
BULLNOSED
- 50 x 150mm PRECAST CONCRETE EDGING KERB
- 150 x 150mm PRECAST CONCRETE CHANNEL
BLOCK (WHERE ROAD GRADIENTS DICTATE)

- KERB NOTES:**
1. MINIMUM 4 DROP KERBS PER SINGLE DRIVE
 2. MINIMUM 6 DROP KERBS PER DOUBLE DRIVE
 3. MINIMUM 8 DROP KERBS FOR 6m+ WIDE DRIVE
 4. ALL BLOCK PAVING TO BE PENCIL EDGE STYLE

IMPORTANT NOTE

DRAWING TO BE READ IN CONJUNCTION WITH DRAWING "23085 - 81 HIGHWAY CONSTRUCTION DETAILS".

CONTRACTOR TO TAKE NOTE OF KERB LAYOUT ON SPECIFIC RAMP, VEHICULAR CROSSING, AND PEDESTRIAN CROSSING DETAILS.

ANY AREAS OF DEEP PLANING/PATCHING TO BE AGREED ON-SITE WITH BMCB HIGHWAYS ENGINEER AND TO BE REMEDIATED ACCORDINGLY. COST OF WORKS TO BE BOURNE BY THE DEVELOPER.



| Issue | Date | Description | By | Chkd | Appd |
|-------|----------|--|----|------|------|
| P2 | 21.08.25 | Updated in accordance with client comments | GW | PB | PB |
| P1 | 30.06.25 | Preliminary Issue | GW | PB | PB |



7 Silverton Court, Northumberland Business Park, NE23 7RY
0191 5577879

BELLWAY HOMES

Job Title
HOYLAND BARNSELY

Drawing Title
SURFACE FINISHES & KERB LAYOUT SHEET 1

Scale at A1
1:250

Drawing Status
PRELIMINARY

| | | |
|------------------------|-------------------------|--------------------|
| Job No 25035 | Drawing No 51 | Issue P2 |
|------------------------|-------------------------|--------------------|