



Evo 1 Wordmark - Raceway Mounted

Wordmark:

5mm 050 opal face, 3mm clear returns

10mm foamex with white face & black returns bonded to 3mm powder coated aluminium backs

Letter returns finished white then black externally using block out vinyl

LEDs mounted within letter to provide even illumination throughout full face

Raceway

2mm thick aluminium, folded and fabricated to form 60x50mm raceway with closed end being powder coated to match fascia/satin black

Transformers mounted within