

# PLANTING SCHEDULE- TREES

Ref Species	Form	Girth (cm)	Height (m)	Root	Breaks	Tot No.
Ac. Acer campestre 'Eisryk'	ESe	10-12	300-350	B	4	9
Bu. Betula utilis 'jacquemonti' 'Domenbos'	EHS	14-16	425-600	RB	5	3
Ob. Carpinus betulus 'Fastigiata'	SSe	10-12	300-350	RB	4	17
Cl. Carataegus baeurgata 'Paul's Scarlet'	SSe	10-12	300-350	B	4	6
Ms. Malus sylvestris	SSe	10-12	300-350	B	4	16
Pc. Prunus serotina 'Tibical'	SSe	10-12	300-350	B	4	12
Pc. Prunus celtiberana 'Charitcheer'	EHS	14-16	425-600	B	5	4
Pc. Prunus celtiberana 'Charitcheer'	SSe	10-12	300-350	B	4	5
Sa. Sorbus aucuparia 'Cardinal Royal'	SSe	10-12	300-350	B	4	6
Tc. Tilia cordata 'Green Spire'	SSe	10-12	300-350	B	4	8

# PLANTING SCHEDULE- SHRUBS

Species	Height (cm)	Root Size/Age	Habit	Breaks	Plants per m <sup>2</sup>	Planting Area %	Total No.
<b>Native Shrub Mix</b>							
<b>Mix A</b> (Tot. area: 148 msq) (Med-large)							
Conus sanguinea 'Mid-Winter Fire'	60-80	C	15L	B	5	10	30
Ilex aquifolium 'Golden King'	60-80	C	10L	L/L	-	25	37
Ligustrum ovalifolium 'Aureum'	80-100	C	10L	B	9	25	74
Rosa carnea	80-100	C	3L	-	2	25	74
Viburnum lantana	60-80	B	T+1+	-	3	15	22
<b>Tree Shrub Mix</b>							
<b>Mix B</b> (Tot. area: 63 msq) (Tall)							
Aucuba japonica 'Crotonifolia'	40-60	C	10L	Bu	6	20	25
Jasminum nudiflorum	60-80	C	10L	B	9	15	9
Kentia japonica 'Pleniflora'	60-80	C	10L	B	7	15	9
Philadelphus 'Beale Etolie'	40-60	C	10L	B	7	15	14
Photinia x fraseri 'Red Robin'	60-80	C	10L	B	8	20	19
Pyracantha 'Saphyr Yellow'	80-100	C	10L	L+L	6	15	9
<b>Med-Tall Shrub Mix</b>							
<b>Mix C</b> (Tot. area: 27 msq) (Small)							
Buddleia davidii 'Royal Red'	80-100	C	10L	Bu	7	1	20
Cytisus x praecox 'Algold'	40-60	C	3L	Bu	7	2	10
Hebe 'Mrs Winder'	40-60	C	10L	Bu	9	2	25
Lonicera nitida 'Baggesen's Gold'	40-60D	C	10L	Bu	10	2	20
Prunus laurocerasus 'Oto Luyken'	60-80	C	10L	Bu	7	2	35
<b>Med-Low Shrub Mix</b>							
<b>Mix D</b> (Tot. area: 281 msq) (Small)							
Chaenomeles x superba 'Crimson and Gold'	40-60	C	3L	B	2	15	84
Hebe 'Red Edge'	40-60	C	10L	Bu	6	25	70
Lonicera nitida 'Silver Beauty'	30-40	C	10L	Bu	9	15	84
Potentilla fruticosa 'Red Ace'	40-60	C	10L	Bu	7	2	30
							169
							84
<b>Med-Low Shrub Mix</b>							
<b>Mix E</b> (Tot. area: 370 msq) (Med-large)							
Cistus 'Silver Pink'	40-60	C	10L	Bu	8	25	165
Euonymus fortunei 'Emerald Gaiety'	30-40	C	10L	Bu	11	2	148
Hebe angustifolia 'Pagei'	30-40	C	10L	Bu	9	2	148
Lonicera nitida 'May Green'	40-60	C	10L	Bu	10	2	25
Spiraea bumalda 'Anthony Waters'	40-60	C	10L	Bu	9	2	15
							111
<b>Groundcover Mix</b>							
<b>Mix F</b> (Tot. area: 253 msq) (Med-large)							
Hypericum calycinum	40-60	C	10L	Bu	9	2	30
Symphoricarpos x chenaultii 'Hancock'	60-80	C	10L	Bu	9	2	40
Viburnum dentifolium	40-60	C	10L	Bu	5	2	30
							158
<b>Groundcover Mix</b>							
<b>Mix G</b> (Tot. area: 94 msq) (Med-large)							
Ceanothus 'hystriflorus repens	60-80	C	10L	Bu	6	2	30
Coloneaster 'Coral Beauty'	60-80	C	10L	Bu	8	2	40
Geranium 'Wargane Pink'	-	C	3L	-	-	3	75
							85
<b>Hedge</b>							
<b>Hedge</b> (Tot. length: 383 m)							
Fagus sylvatica	60-80	B	1+2	-	-	0.5m c/s	100
							736
<i>Double staggered row, rows 0.5m apart</i>							



## KEY

- + Selected Standard Tree
- + Extra Heavy Standard Tree
- Proposed Grass
- Proposed Beech Hedge
- Proposed Ornamental Shrub
- Proposed Native Shrub Mix

## OUTLINE SPECIFICATION:

### GENERAL

All works to be in accordance with all relevant British Standards and the Landscaping Consultant's planting plans and specifications (to Specification (ANSI) 1998, latest revision).

### SETTING OUT

All dimensions and levels should be checked and adjusted on site. Contractor responsible for care around all services. Do not scale from this drawing.

### SITE PREPARATION

Building rubble in excess of 50mm dimension to be removed, compaction ripped 150mm deep or broken out by JCB back-actor leaving surface rough. Ensure free drainage.

### TOPSOIL

General purpose Grade topsoil BS:3882 medium loam, not more than slightly stoney, pH 5.7-7.5. Depth 450mm all planting areas. 150mm to all other areas. 1 line sample of topsoil should be sent to Weddle's office for pH testing and approval.

### TREE PIT

Shrub Standard: 1200mmØ x 750mm depth  
Extra Heavy Standard: 1200mmØ x 750mm depth

### PREPARATORY HERBICIDE

Weed allowed to grow and treated with up to three applications glyphosate prior to cultivation or planting during the fallow period.

### GRASSING

Grassing between April-October.  
Cultivate to prepare seed bed. Finished seed bed levels 25mm above pavings and kerb edges. Stones pick to 25mm. Pre-seeding fertiliser 50g/m<sup>2</sup>. Grass mix chosen for low maintenance requirements:-  
GRASS SEED MIX from DLF Trifolium Tel: 01386 791102; LAMN Pro 50 Quality lawn (with Ryegrass)

### PLANTS

General  
Plant material in accordance with the HTA's National Plant Specification 1997. All plants container grown, well formed and free from disease. Plant handling to C-SE Plant Handling Code. Quality as supplied by:  
Jones of Whitley Ltd, York, YO26 8AQ. Tel: 01423 330234.  
Or other nursery listed in the Horticultural Trades Association Nursery Certification Scheme.

### Planting

Plant November to March.  
Planting areas cultivated 150 mm deep and stone picked of material greater than 50mm. Plant material pit planned 300 x 300 x 200 minimum. Approved planting compost incorporated into the soil during planting.

### Backfill mix

Emmgag	P4	Compost
Shrubs	5g	10 litres
Select Standard	50g	75 litres
Extra Heavy Standard	75g	50g
	50g	75 litres

Backfill mix (30%) incorporated into topsoil (70%) during planting.

### TREE STAKING

Select Standard/Extra Heavy Standard - Short Double Staking  
Preserved sapwood 100mm min diameter. Driven vertically 450mm into base of pit on either side. Cross bar - timber, as stake. Secure with rubber J Toms 375mm wide standard nylon reinforced rubberbelt ref L2 ties including rubber spacer pads ref L1.

### MULCH

Total cover coarse bark mulch to shrub areas. Melcourt Bark Nuggets 75mm depth.

### AFTERCARE

24 months aftercare by planting contractor. Including grass cutting, weed, pest and disease control, pruning and watering. Weed control by residual herbicide to a weed free condition around plants. Spot treat with glyphosate and hand weed as necessary.

Watering 10 litres per plant in periods of drought.

### DEFECTS LIABILITY

Twenty-four months on plant material and grass. Replacements in November in year of loss.

### ONGOING MAINTENANCE

Continue to maintain for five years from completion of planting by hand weeding and spot treatment of glyphosate herbicide to any weed in planted areas until plants close canopies. Replace failures for 5 years.

### REVISIONS:

Rev. A: Rev to OD dwg no. OD309-01-01, TA Oct 09.

Based on client's layout drawing.

no. QD254-01-01, Rev. C

**Weddle Landscape Design**  
LANDSCAPE ARCHITECTURE  
ENVIRONMENTAL PLANNING  
Mews Studio, Charmwood House,  
8 Kenwood Bank, Sheffield S7 1NU  
www.weddles.co.uk

Job: KEEPMOAT HOMES

Title: LESLIE ROAD KENDRAY BARNSLEY

PLANTING PLAN SHEET 1 OF 4

Scale: A1: 1:500

Scale: A2: 1:500

Scale: A3: 1:500

Scale: A4: 1:500

Scale: A5: 1:500

Scale: A6: 1:500

Scale: A7: 1:500

Scale: A8: 1:500

Scale: A9: 1:500

Scale: A10: 1:500