



MAIN GEOMETRIC DESIGN FEATURES	ALDHAM HOUSE LANE	WINDMILL ROAD
WIDTH OF CARRIAGEWAY	7.6M*	7.6M*
KERBED CENTRAL RESERVE	N/A	N/A
WIDTH OF KERBED CENTRAL RESERVE	N/A	N/A
FORWARD VISIBILITY FOR RIGHT TURNING VEHICLES	112M	116M
HAS RIGHT TURN BAY	NO	NO
WIDTH OF RIGHT TURN BAY	N/A	N/A
BLOCKING TRAFFIC	YES	YES
BLOCK TRAFFIC QUEUE (PCU)	0	0

MAIN GEOMETRIC DESIGN FEATURES	PIT LANE	SUMMER LANE
VISIBILITY TO LEFT	28M	38M
VISIBILITY TO RIGHT	22M	30M
MINOR ARM TYPE	ONE LANE	ONE LANE
GIVEWAY WIDTH	10.9M (5M)**	15.2M** (5M)
5M WIDTH	4.8M	7.9M** (5M)
10M WIDTH	2.6M	4.7M
15M WIDTH	2.6M	3.8M
20M WIDTH	2.9M	3.9M
AVERAGE	3.6M	4.5M

*AVERAGE
**REDUCED TO 5M WHEN CALCULATING AVERAGE

TITLE
PIT LANE, WOMBWELL - ALDHAM HOUSE LANE/
WINDMILL ROAD/SUMMER LANE/PIT LANE -
EXISTING HIGHWAY LAYOUT AND PICADY DIMS

REF
23081/IN/01REV/A

SCALE
1:250@A3

