



- Notes**
- Dimensions in mm unless otherwise stated, and to be verified on site.
 - Do not scale this drawing as this may lead to errors.
 - Hatch patterns and fills are indicative only unless stated otherwise.
 - Information outside site boundary shown for contextual purpose only.
 - Any discrepancies in the design information must be clarified with project Landscape Architect prior to commencement of site works, and all other relevant information from the wider design team.
 - Any levels information on this drawing indicates design intent. Contractor is to verify all levels and dimensions against site survey information.
 - All proprietary products to be installed in accordance with manufacturer's instructions.
 - Any proposed deviation from the design specification and/or plant schedule to be agreed with the project Landscape Architect prior to ordering.
 - This drawing is the property of Urban Wilderness Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without written consent of Urban Wilderness Ltd.

- KEY**
- Unit 7 - Site Boundary
 - Land Under Harworth Ownership
 - On-Plot Landscape designed by others

- Landscape Softworks**
- Proposed native scrub planting
 - Proposed native woodland planting
 - Proposed native woodland planting supplemented with mature multi-stem trees
 - Proposed wildflower meadow planting
 - Proposed areas of mown grass
 - Proposed specimen tree
 - Proposed informal hedge
 - Proposed wet meadow
 - Existing woodland to be retained
 - Proposed development drainage outfall
 - Permissive footpaths, existing and proposed
 - Existing public footpath network

Plant Schedule

Specimen Trees				
No.	Abbr.	Botanical Name	Specification	Height (cm)
3	PAV	<i>Prunus avium</i>	3x; Standard; clear stem minimum 200cm	300-425cm
3	QRO	<i>Quercus robur</i>	3x; RB; Large Feathered: 5 brks	300-425cm
1	QUE PGP	<i>Quercus palustris</i> 'Green Pillar'	Bareroot; ;2x; Clear Stem 150-175 ;3 brks	250-300cm

NHM - Native Hedgerow Mix - Hedgerows planted in double staggered rows at 300mm centres				
No.	Abbr.	Botanical Name	% Cont.	Specification
306	Cmo	<i>Crataegus monogyna</i>	50%	B: 1+1; Transplant - seed raised
30	Vop	<i>Viburnum opulus</i>	5%	B: 1+1; Transplant - seed raised
61	Csa	<i>Cornus sanguinea</i>	10%	B: 1+1; Transplant - seed raised
61	Cav	<i>Corylus avellana</i>	10%	B: 1+1; Transplant - seed raised
30	Lvu	<i>Ligustrum vulgare</i>	5%	B: 1+1; Transplant - seed raised
30	Iaq	<i>Ilex aquifolium</i>	5%	B: 1+1; Transplant - seed raised
61	Psp	<i>Prunus spinosa</i>	10%	B: 1+1; Transplant - seed raised
30	Rca	<i>Rosa canina</i>	5%	B: 1+1; Transplant - seed raised

Total length: 87m

NWM - Native Woodland Mix - *Planted in groups of 9-11 at 1m centres					
No.	Abbr.	Height	Botanical Name	% Cont.	Specification
510	Aca	40-60cm	<i>Acer campestre</i>	6%	B: 1+1; Transplant
170	Aca	125-150cm	<i>Acer campestre</i>	2%	Feathered; Bareroot; plant 1 per 9m2
425	Agl	40-60cm	<i>Alnus glutinosa</i>	5%	B: 1+1; Transplant
170	Agl	125-150cm	<i>Alnus glutinosa</i>	2%	Feathered; Bareroot; plant 1 per 9m2
850	Bpu	40-60cm	<i>Betula pubescens</i>	10%	B: 1+1; Transplant
170	Bpu	125-150cm	<i>Betula pubescens</i>	2%	Feathered; Bareroot; plant 1 per 9m2
425	Csc	40-60cm	<i>Cytisus scoparius</i>	5%	155cc min.: 1+0; Seedling; Cell Grown
850	Iaq	40-60cm	<i>Ilex aquifolium</i>	10%	155cc min.: 1+0; Seedling; Cell Grown
510	Lvu	40-60cm	<i>Ligustrum vulgare</i>	6%	B: 0/1; Branched: 2 brks
425	Msy	40-60cm	<i>Malus sylvestris</i>	5%	B: 1+1; Transplant - seed raised
850	Psy	40-60cm	<i>Pinus sylvestris</i>	10%	1+2; Transplant
850	Psp	40-60cm	<i>Prunus spinosa</i>	10%	B: 1+1; Transplant Seed Raised: Branched: 2 brks
425	Qpe	40-60cm	<i>Quercus petraea</i>	5%	B: 0/1; Branched: 2 brks
425	Qro	50-60cm	<i>Quercus robur</i>	5%	1+1; Transplant
170	Qro	125-150cm	<i>Quercus robur</i>	2%	Feathered; Bareroot; plant @ 1 per 9m2
425	Rca	40-60cm	<i>Rosa canina</i>	5%	B: 1+1; Transplant Seed Raised: Branched: 3 brks
425	Sar	40-60cm	<i>Sorbus aria</i>	5%	1+1; Transplant
425	Via	40-60cm	<i>Viburnum lantana</i>	5%	B: 1+1; Transplant Seed Raised: Branched: 2 brks

Total Area: 8,998m²
Betula pubescens and *Alnus glutinosa* should be planted in areas that are more prone to becoming water logged or remain wet for long periods

Woodland Matrix - Multi-stemmed trees *Planted in groups of 7-9 at 4m centres					
No.	Abbr.	Height	Botanical Name	% Cont.	Specification
30	Bpe ms³	200-250cm	<i>Betula pendula</i> ms³	NA	Multi-stem; Bushy; 3 stem minimum
30	Cav ms³	150-200cm	<i>Corylus avellana</i> ms³	NA	Multi-stem; Bushy; 3 stem minimum
30	Sal ms³	150-200cm	<i>Salix alba</i> ms³	NA	Multi-stem; Bushy; 3 stem minimum

NWM - Native Woodland Mix - *Planted in groups of 9-11 at 1m centres					
No.	Abbr.	Height	Botanical Name	% Cont.	Specification
111	Aca	40-60cm	<i>Acer campestre</i>	6%	B: 1+1; Transplant
37	Aca	125-150cm	<i>Acer campestre</i>	2%	Feathered; Bareroot; plant 1 per 9m2
94	Agl	40-60cm	<i>Alnus glutinosa</i>	5%	B: 1+1; Transplant
37	Agl	125-150cm	<i>Alnus glutinosa</i>	2%	Feathered; Bareroot; plant 1 per 9m2
187	Bpu	40-60cm	<i>Betula pubescens</i>	10%	B: 1+1; Transplant
37	Bpu	125-150cm	<i>Betula pubescens</i>	2%	Feathered; Bareroot; plant 1 per 9m2
94	Csc	40-60cm	<i>Cytisus scoparius</i>	5%	155cc min.: 1+0; Seedling; Cell Grown
187	Iaq	40-60cm	<i>Ilex aquifolium</i>	10%	155cc min.: 1+0; Seedling; Cell Grown
111	Lvu	40-60cm	<i>Ligustrum vulgare</i>	6%	B: 0/1; Branched: 2 brks
94	Msy	40-60cm	<i>Malus sylvestris</i>	5%	B: 1+1; Transplant - seed raised
187	Psy	40-60cm	<i>Pinus sylvestris</i>	10%	1+2; Transplant
187	Psp	40-60cm	<i>Prunus spinosa</i>	10%	B: 1+1; Transplant Seed Raised: Branched: 2 brks
94	Qpe	40-60cm	<i>Quercus petraea</i>	5%	B: 0/1; Branched: 2 brks
94	Qro	50-60cm	<i>Quercus robur</i>	5%	1+1; Transplant
37	Qro	125-150cm	<i>Quercus robur</i>	2%	Feathered; Bareroot; plant @ 1 per 9m2
94	Rca	40-60cm	<i>Rosa canina</i>	5%	B: 1+1; Transplant Seed Raised: Branched: 3 brks
94	Sar	40-60cm	<i>Sorbus aria</i>	5%	1+1; Transplant
94	Via	40-60cm	<i>Viburnum lantana</i>	5%	B: 1+1; Transplant Seed Raised: Branched: 2 brks

Total Area: 1,372m²
Betula pubescens and *Alnus glutinosa* should be planted in areas that are more prone to becoming water logged or remain wet for long periods

NScM - Native Scrub Mix - *Planted in groups of 9-11 at 1m centres					
No.	Abbr.	Height	Botanical Name	% Cont.	Specification
511	Cav	40-60cm	<i>Corylus avellana</i>	12%	1+1; Transplant Seed Raised: Branched: 2 brks
426	Cmo	40-60cm	<i>Crataegus monogyna</i>	10%	1+1; Transplant Seed Raised
340	Csa	40-60cm	<i>Cornus sanguinea</i>	8%	1+1; Transplant Seed Raised: Provenance UK Area 403
298	Csc	40-60cm	<i>Cytisus scoparius</i>	7%	155cc: 1+0; Seedling; Bushy; Cell Grown
298	Iaq	40-60cm	<i>Ilex aquifolium</i>	7%	155cc min.: 1+0; Seedling; Cell Grown
511	Psp	40-60cm	<i>Prunus spinosa</i>	12%	1+1; Transplant Seed Raised: Branched: 2 brks
298	Rca	40-60cm	<i>Rosa canina</i>	7%	1+1; Transplant Seed Raised: Branched: 3 brks
298	Rfr	40-60cm	<i>Rhamnus frangula</i>	7%	1+1; Transplant Seed Raised: Leader with Laterals: 3 brks
340	Sni	40-60cm	<i>Sambucus nigra</i>	8%	1+0; Seedling; branched: 2 brks
511	Lvu	40-60cm	<i>Ligustrum vulgare</i>	10%	0/1; Branched: 2 brks
426	Vop	40-60cm	<i>Viburnum opulus</i>	12%	1+1; Transplant Seed Raised: Branched: 2 brks

Total Area: 4,256m²
Corylus avellana and *Rhamnus frangula* should be planted in areas that are more prone to becoming water logged or remain wet for long periods

EM3 Emorsgate Seeds - Special General Purpose Meadow Mixture planted @ 4g/m²	
Area	
54m²	

Plant Mixes - WFG9 Germinial Seeds - Wet Meadow Mixture planted @ 5g/m2	
Area	
449m2	

Mown Grass - Grass seed Utility Mix planted @ 35g/m²	
Area	
69m²	

project title
Gateway 36, Rockingham

client
Harworth Group

drawing title
Unit 7 - Landscape Planting Plan

paper size
A1

scale
1:1000

status
PLANNING (RM)

drawing number
334-UW-P-081

revision
B

© Urban Wilderness Ltd

Date	Description of revision	Drn by	Chk by	Revision
26 Feb 25	Amended Red Line Boundary	ISA	TBR	B
12 Nov 24	Specimen Tree amended in line with On-Plot Landscape	ISA	TBR	A
8 Nov 24	First Issue	ISA	TBR	-

Leeds Office
7 Saw Mill Yard, Water Lane, Holbeck, Leeds, LS11 5WH
t: 0113 472 0030

Sheffield Office
Floor 2, Abbey House, 11 Leopold Street, Sheffield, S1 2GY
t: 0114 477 0250

design@urbanwilderness.co.uk
Registered in Scotland SC371979

www.urbanwilderness.co.uk