NORTH

KEY

Green Sprint - reused existing green/grey setts, new sawn & flame finished setts to match or a combination of the two. New step treads and trims to match.

Existing Yorkstone flags lifted and relaid around Town Hall perimeter, supplemented with new flags to match where necessary. Reclaimed or new Yorkstone kerbs and trims to match.

New Yorkstone setts 100mm deep to public square, suitable for vehicle loadings, with black granite trims.

Yorkstone terraces, 150mm & 300mm risers, buff front kerb, blocks and flags and blue/ grey setts/ planks as terrace infill.

Hot rolled asphalt with buff stone chippings.

Retaining walls and parapets, in situ concrete, natural colour, bush hammered finish. Climbers grown up outer faces to create green wall effect.

Proposed trees, small sized compact species, 2.2m clear stems.

Colourful annual & herbaceous perennial planting with some evergreen shrub structure (Box balls), designed for sensory experience and changing seasonal colour.

Indicative seat and litter bin positions.

Indicative lighting column positions, galvanised column with spotlights attached..

Portland Stone block plinths, with 'linen' artwork inscribed.

Sadler Gate

Town Hall

vehicle zone (HRA with buff stone chip)

replace concrete flags with new Yorkstone

new Yorkstone setts to form flush surface between Town Hall entrance & War Memorial

repoint & repair existing steps

Existing gardens

War Memorial

Church Street

Regent Street

replace concrete flags with new Yorkstone

repoint & repair existing steps

potential Puffin crossing & Town Hall loading area

replace concrete flags with new Yorkstone

vehicle zone (HRA with buff stone chip)

Existing gardens

green sprint (ramp, & steps, reused or new setts to match)

Royal Street

St Mary's Place

Experience Barnsley illuminated glass entrance feature

new Yorkstone steps

ramp

+112.8

flush

green sprint (reused setts or new to match existing)

reused & new Yorkstone to match

100mm Yorkstone kerb

limit of raised kerb

+110.20

+111.6

flush

4m

5m

Lancaster Gate

vehicle zone (HRA with buff stone chip)

+109.80

+107.50

109.60+

+109.35

+108.75

+108.15

110.30+

+107.40

+108.45

+107.85

+107.55

Portland Stone blocks, *linen* artwork & informal seats

entrance control barrier

falling fountains to animate square & create play feature

black granite trims, *coal* outcrops

+109.35

+109.05

+107.25

+107.10

109.50+

+106.95

Town Hall Gardens inscribed on Portland Stone block. Telecoms & signal control boxes contained inside.

public square

Yorkstone setts

+109.35

+111.80

+110.60

+109.90

Yorkstone steps (150mm)

Yorkstone steps (300mm with interim 150mm steps)

existing pavement narrowed to 2.5m min & resurfaced in Yorkstone

proposed trees, small compact form (eg Field Maple)

proposed planting (colourful herbaceous species with some evergreen shrub structure)

Shambles Street

Market Hill

0 10 20m

Town Hall Gardens, Barnsley

Landscape Proposals - Design Plan

Scale 1:200 May 2012 2275.01

Estell Warren
Landscape Architecture
5b Chevin Mill, Leeds Road, Otley, LS21 1BT
Tel: 01943 464384
mail@estellwarren.co.uk
www.estellwarren.co.uk