

LEGEND

- Existing tree planting to be retained. All trees to be protected to BS 5837:2005
- Existing structure planting to be retained. All trees to be protected to BS 5837:2005
- Existing hedge planting to be retained.
- Proposed individual tree planting (Heavy and light standards, feathered)
- Proposed woodland structure planting (Including woodland edge planting)
- Proposed Semi-ornamental structure planting
- Proposed shrub planting (Including climbers, grasses/herbaceous and emergent planting)
- Proposed hedge planting (Both formal and native planting)
- Proposed amenity grass areas (Including bulb planting)
- Proposed wildflower areas
- Proposed sports pitch areas
- Proposed pedestrian tarmac Areas
- Proposed vehicular tarmac Areas
- Proposed porous tarmac to hard games courts
- Proposed red tarmac areas
- Proposed car park bay surfacing (porous system)
- Proposed embankments/earth features
- Proposed feature paving. Large and small unit pavers to be detailed on hard landscape drawings. To be supplied by Marshalls or similar approved.
- Proposed bound gravel areas with small unit paver edge.
- Proposed rolled gravel areas with timber edge.
- Proposed raised pedestrian crossing area.
- Proposed ground graphics/edgings
- Trim trail/Orienteering stations
- Proposed covered cycle storage
- Proposed formal/informal seating
- Potential location for tensile structure
- Proposed 2.4m high weldmesh fence with matching vehicular and pedestrian gates.
- Proposed 1.8m high railing to prevent access/falling into into embankment area.
- 3m high Hard Games Area Fence with matching vehicular and pedestrian gates.
- Existing boundary treatments to be retained and repaired where necessary.

Notes
1. Proposed bus lay-by
2. Main vehicular access
3. Main pedestrian access
4. Drop-off area
5. East car park (115no. spaces some of which to be designated for leisure centre use. Incl. 4no. disabled spaces)
6. West car park (71no. spaces)
7. Disabled parking (9no. spaces)
8. Entrance feature
9. Main entrance plaza
10. Covered cycle storage (131no. spaces in total)
11. Reflection/memorial garden
12. Service yard
13. Energy centre
14. Meeting area
15. Outdoor gym
16. Social link
17. Covered walkway
18. Retaining wall and planted slope
19. Earth sculpted soft play area
20. Location of potential tensile structure
21. Hard play area with ground graphics and informal/formal seating. Areas divided by low walls/site furniture.
22. Informal soft play area with plinths for displaying school/artist sculptures
23. Grass reinforcement for fire tender access
24. Kitchen garden with raised planters and fruiting bushes
25. Arboretum
26. Habitat area containing woodland planting, bog garden and wildflowers
27. Sensory garden
28. Science garden
29. Feature area containing planting and features from existing memorial garden
30. Tensile structure/canopy
31. Amphitheatre and performance areas
32. Access to Primary School
33. Access from expressives blocks
34. Emergency access
35. Ramped/stepped access with terraced gardens
36. Hard games court (5no. tennis courts/5no. basketball/netball/1no. 5-a-side)
37. Long/triple jump with space for high jump equipment
38. Existing access point
39. Synthetic turf pitch with floodlights
40. Orchard
41. Athletics track - 300m, 8 lanes
42. Trim trail/Orienteering stations
43. Reinforced woodland planting
44. Feature earth tube
45. Existing leisure centre
46. Rounders
47. Cricket pitch
48. Pedestrian/cyclist access from east
49. Shot put/discus circles
50. Medium football pitch (75x45m)
51. Access to existing remote pitches
52. Large rugby pitch on existing grass (95x50m)
53. Cherry picker route on reinforced grass
54. Bin store

Site Furniture type and location to be agreed with the school.		
Benches	Chantry Standard by Broxap , and/or WMB/6 by Wybone	25 No.
Litter Bins	Derby Slimline by Broxap , and/or MV/40 by Wybone	20 No.
Picnic tables	Big Bench 8 Seater Timber/Concrete Picnic Bench	9 No.
Bollards	Broxap BX14 6501B2-RT	15 No.

All products to be similar or approved.
Galvanised and polyester powder coated to an approved colour

NOTE
All doorways to have level access.
Manholes in paving to have recessed covers.

REV.	DESCRIPTION.	DATE.
E	Issued for Reserved Matters and approved.	06.03.09
P01	Preliminary Issue.	01.06.09
P02	Masterplan updated in accordance with latest topographical survey. Revised External Energy Centre incorporated and west car park layout amended to suit. Bin store area added. Entrance plaza and Reflection/Memorial garden rationalised. Hard play area updated. Cherry picker route added to south of main building. Earth sculpture rationalised. External performance area and amphitheatre revised. DH	21.08.09
P03	Bin store area revised to accommodate turning vehicles. AP	21.12.09
C01	Item 13, latest Energy Centre layout added. Item 54, Bin store area rotated. Item 13, latest Energy Centre layout added. Item 54, Bin store area rotated. Item 4, Reflection /memorial gardens and outdoor dining area revised and under review by LOR. Item 9, Entrance plaza amended in line with AHMM comments. Item 35, Zigzag access revised to eliminate the need for steps, hand rail added to sloped paths. Item 3, amphitheatre revised to eliminate steps	21.12.09

REV.	DESCRIPTION.	DATE.
C02	construction area reviewed with deterrent paving to base of columns and in-situ concrete surface. DH Synthetic Turf Pitch amended in line with AR requirement. 3no. cycle shelters relocated. 3no. benches relocated. 3no. concrete cubes relocated. Triangle picnic tables replaced with 9no. concrete/ timber square picnic tables to outdoor dinning area. Structure and hedge planting added to south west corner of site. DH	31.03.10
C03	Proposed bus lay-by added as per BH drawing BP4L_KBK_BUR_DR_95_SW_LL_05 with re-aligned gabion retaining wall. Entrance proposals updated in line with recent design review (KBK_SK84 Rev A) and planning comments. Access to Core 02 escape door revised as instructed by AHMM. Cherry Picker Route landing area revised and shrub planting added to steep slope. Proposed channel drain added to east of Link Corridor. Additional retaining wall to east of Expressives Block updated. LS	23.06.10

REV.	DESCRIPTION.	DATE.
C04	Updated in line with changes to Hardworks dwg's BP4L_KBK_AWP_DR_94__BW_LL_22/23. Tree planting amended to suit. LS	01.07.10
C05	3 no. bollards added to Outdoor Gym area, ramped area added north of expressives, tree relocated and existing stone wall shown to drop off area, grassed area replaced with tarmac in west car park, fire tender access amended, ground graphics amended, seating and bin positions updated. DH	29.03.11
C06	Bus layby moved to east of main entrance. Existing wall to the west of the main entrance shown as being retained, proposed retaining walls removed and tree/shrub planting amended accordingly. DH	27.06.11

Barnsley Partnership For Learning

IMPORTANT CDM / H&S NOTE
The designers would draw the readers attention to key residual construction health and safety hazards that have not been eliminated from the designs shown on the drawings by the design process. These hazards are identified below:
This construction drawing does not contain significant or unusual risks that a competent contractor would not expect to encounter.

Any construction personnel including operatives intending to construct the designs shown on this drawing should ensure that they have been thoroughly briefed by the principle contractor on all health and safety matters and have sight of:
1. The full designers and contractors hazard risk assessments and risk registers.
2. The developed construction phase health and safety plan.
3. The contractors construction method statements.

awp

PROJECT
Barnsley BSF - Kirk Balk ALC

DRAWING TITLE
Landscape Masterplan

DRAWING No.	SCALE (A1)	DATE	DRAWN	CHKD
BP4L_KBK_AWP_DR_94_BW_LL_01 C06	1:1000	Jan '09	DH	DP

Anthony Walker and Partners Limited
10 Summerhill Terrace
Newcastle upon Tyne
NE4 6EB
Tel: 0191 233 0188
Fax: 0191 261 1527
Email: info@awpenvironment.co.uk
www.awpenvironment.co.uk

This document is copyright and must not be used, amended or reproduced in any form without written consent from Anthony Walker & Partners