



Proposed Side Elevation B

Proposed Rear Elevation

Proposed Side Elevation

EXTERNAL WALLS
To be cavity wall construction with external leaf of brick to match existing with 100mm cavity with 50mm Kingspan Kooltherm K8 insulation wall batts fixed to internal leaf of 100mm Thermalite shield blocks. Walls ties to be 5 number per metre square and 225mm vertical centres to reveals, stainless steel double triangle to BS 1243. The internal wall to be finished with 15mm two coat gypsum plaster or 12.5mm plasterboard on dabs. The blockwork and brickwork to be either block bonded or tied using Furfix stainless steel ties to the existing, with the cavities made continuous with existing. The dpc is to be 150mm above the adjacent finished ground level and linked with the existing, cavities closed with Thermabate or similar approved cavity closer.

WINDOWS & VENTILATION
The windows and doors are to have a U value of 1.6 and be UPVC double glazed with 16mm air gap and a "soft" low-E coating and draught stripped with trickle ventilation of 8000mm2 and opening lights minimum 5% floor area of the room. Glazing to doors and side panels within 1500mm and windows within 800mm of the floor must laminated or toughened safety glass and marked according to BS 6206. Mechanical ventilation provided to kitchen, bathroom & En-suite of 60L/sec and 30L/sec respectively and ducted to the external air. All new first floor windows to habitable rooms to be provided with escape windows a minimum area 0.33m2 with a minimum clear opening height and width of 450mm (ie. minimum clear opening of 450mm wide and 750mm high) with the opening window between 800mm and 1100mm above finished floor level.

LINTELS
The lintels to be Catnic CG90/100 or similar approved to be insulated and have a minimum end bearing of 150mm with tray dpc over and weep holes at 450mm centres and with exposed internal faces covered with 12.5mm plasterboard and 5mm skim. The lintel over the rear doors is to be heavy duty and those over new opening at first floor level are to be Naylor R4 concrete lintels.

GENERAL
These Plans are to be used for Planning and Building Regulations purposes only. The contractor shall ensure that all works comply with the Planning consent and the Building Regulations and that all materials are fixed in a workmanlike manor and in accordance with the relevant British Standard Codes of Practice and in accordance with the manufacturers recommendations. The contractor is to be responsible for checking and verifying all levels and dimensions on site and for submitting the relevant notices at the appropriate stages to the local authority for inspection of work. The contractor to verify with the client the position and number of, socket outlets, switches, lighting points, radiators and similar fitting before commencement of work on site.

Revised for Town Planning rear first floor bedroom window moved to centre of ridge line
3/08/2011

Drawing No. 24CS/11/02

© Copyright I. J. Mawson

Address	24 Cross Street Monk Bretton Barnsley
Project	Proposed Elevations
Scale	1 : 50
Date	June 2011

Willowbrook Design Services
Mr. I. J. Mawson M. B. Eng. 14 Willow Brook Close Darton Barnsley Telephone 01226 – 380043