



Plant Codes (full schedules on Sheet 1)

Code	Plant Name
Ac	Acer campestre
Ae	Acer campestre 'Elaeagn'*
AcLS	Acer campestre 'Louise Red Shine'
Ag	Alnus glutinosa
AsRH	Amelanchier arborea 'Robin Hill'
BAN	Berberis thunbergii 'Atropurpurea Nana'
Bp	Betula pendula
Ch	Carpinus betulus
CBM	Ceanothus 'Blue Mound'
Cl	Choisya ternata
Cv	Corylia avellana
Cm	Castanea monogyna
EEG	Euonymus fortunei 'Emerald 'n' Gold'
ESQ	Euonymus fortunei 'Silver Queen'
Fs	Fagus sylvatica
Fp	Fagus sylvatica 'Purpurea'
Gl	Griselinia littoralis
HMW	Hebe 'Mrs Winder'
HRE	Hebe 'Red Edge'
Is	Ilex aquifolium
Lah	Lavandula angustifolia 'Hidcot'
Lam	Lavandula angustifolia 'Munstead'
LoA	Ligustrum ovalifolium 'Aureum'
LmG	Lonicera nitida 'May Green'
PuRR	Prunella x haasi 'Red Robin'
PE	Potentilla 'Elizabeth'
PPa	Prunus 'Pendula'
PaP	Prunus avium 'Plena'
Pi	Prunus laurocerasus
POL	Prunus laurocerasus 'Otto Luyken'
Pp	Prunus padus
Ps	Prunus spinosa
PSR	Pyracantha 'Saphyr Red'
PSY	Pyracantha 'Saphyr Yellow'
Qp	Quercus petraea
Qr	Quercus robur
Sc	Salix caprea
SoP	Salvia officinalis 'Purpurea'
SoT	Salvia officinalis 'Tirolo'
SRU	Skimmia japonica 'Rubella'
Sar	Sorbus aria
Sau	Sorbus aucuparia
ScR	Sorbus aucuparia 'Cardinal Royal'
ScE	Sorbus commixta 'Embley'
Tc	Tilia cordata
Vd	Viburnum davidii
Vo	Viburnum opulus
Vt	Viburnum tinus
Vmi	Vincetoxicum

Planting Notes

Topsoil shall be a minimum of 400mm depth over planting beds and graded to fall. Imported topsoil must be BS3882:2007 compliant and existing topsoil must be cultivated in accordance with BS3882:2007. No cultivation should take place in well waterlogged conditions.

Herbicide and cultivation: Topsoil to be treated with two applications of herbicide prior to planting, where necessary, strictly in accordance with the Control of Pesticides Regulations 1986 (as amended 1997 or, otherwise, updated/superseded legislation) and following manufacturer's instructions by qualified staff. The topsoil shall then be cultivated to 150mm depth.

Planting: All planting and turfing shall conform to BS: 3036: 1992 and BS: 4428: 1993.

Trees: Standard trees to be planted in pits 800x800x450mm or dimensions of rootball, whichever is greater. Tree to be supported by 11tr stake (1500mm long, per tree, 600mm above ground, 75mm diameter) and 1N bio-degradable tee. Heavy and Standard trees to be planted in pits 1000x1000x600mm or dimensions of rootball, whichever is greater. Tree to be supported by 2Nr stakes (1500mm long, 600mm above ground, 75mm diameter), cross bar (400x100x15mm) and 1N bio-degradable tee. All trees to be planted with 150g Emring (or equivalent) to be incorporated into the soil of all new tree pits. Trees to be planted centrally within a tree pit. Trees planted within grass to have 1m diameter circle around stem kept clear of vegetation using mechanical or chemical means.

Container grown shrubs, transplants and whips: Shrubs and transplants shall be planted in pits 300x300x400mm depth, and the backfill shall include 3 litres of peat-free tree and shrub compost. Where two or more shrub species are indicated within a single bed each species shall be randomly mixed throughout the bed in groups of 3:5.

Herbicide: Spot treat with herbicide throughout the maintenance period in accordance with the manufacturer's instructions.

Mulch: Planting beds to receive 75mm depth pulverized ornamental bark mulch. Native woodland-edge plants to be planted with 800g flax fibre mulch mat pinned to soil. Native hedgerow to be planted through 800g flax fibre mulch roll, edges tucked. Ensure the top of the mulch layer is a minimum of 15mm below adjacent pavements and other surfaces, to prevent spillage.

Plant position: Final position of trees and shrubs subject to confirmation of service location and approval of statutory undertakers.

Protection to planting: Native hedgerow plants to be protected by spiral shelters. Native trees and shrubs within mixes to be protected by shelter guards as supplied by Acorn Planting Products Ltd (01268 523633), or equivalent.

Ornamental hedging: Hedges to comprise a single row of plants, 400mm wide trench excavated to take plants and topsoil cultivated to 400mm depth prior to application of fertilizer.

Grass: All turfseeded areas to be cultivated and levelled as required removing any stones, rubble, subsoil, general construction waste.

Planting Season: Bare-root plants to be planted between mid-November and mid-March dependent upon the planting season.

LEGEND

- Site boundary
- Existing tree to be retained
- Proposed tree Standard (Heavy)
- Proposed tree Standard (Selected)
- Proposed shrub bed
- Proposed hedge
- Proposed grass

- Proposed Native Hedge Mix
- Proposed wildflower / grass mix Emorsgate EM1 'Basic General Purpose Meadow Mixture'

This drawing is the copyright of Rosetta Landscape Design and cannot be reproduced in any form without the express consent of the company. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. If in doubt please ask.

This drawing has been prepared for the purpose of planning approval.

PROJECT	Calver Lane, Dodworth, Barnsley
TITLE	Detailed Landscape Proposals (2 of 3)
CLIENT	Avant Homes
DATE	05 Nov 21
SCALE	1 : 250
SHEET	A0
DRAWN	BP/jr
DRAWING NO	3842/2
CHECKED	MP
REVISION	-

ROSETTA
LANDSCAPE DESIGN

Chartered Landscape Architects

Swallow's Nest, Main Street
Ashham Richard, York, YO23 3PT
Telephone +44 (0)1904 500410
Email design@rosettalandscapedesign.co.uk
Web www.rosettalandscapedesign.co.uk