




Health and Safety, 2004 and CDM Regulations 2007

In line with the above regulations we are obliged to inform the Contractor of the potential risks that may be encountered in the construction of these works. As part of the design process all the relevant health & safety aspects are given full consideration and these are identified within the design and on this document. Although considerable effort is undertaken to eliminate risks, the very nature of the project gives rise to some hazards and risks.

Significant risks that cannot be eliminated by design and could not be foreseen by a competent contractor are noted in the risk assessment based on the drawings.

- S38 AGREEMENT LEGEND**
- Adoptable Footpath/Hard Margin
 - Adoptable Verge
 - Adoptable Highway
 - Adoptable Gully and Pipe
 - Adoptable Street Lighting
 - Development Boundary
 - Works to Existing Public Highway
 - Gr6 Bms

Street Lighting Arrangement

Denotes 6M galvanised steel column with 20 Aria LED lantern complete with electronic PEC.

Denotes 8m galvanised steel column with 100 Aria LED lantern complete with electronic PEC.

All materials to comply fully with current BMBC Street Lighting Specification.

It is the responsibility of the developer to advise their clients of the location of street lighting columns relative to their property and to programme column installation works commensurate with property occupation.

Column positions may be adjusted slightly to suit site conditions and services, but must not normally be erected within 500mm of defined driveway boundaries.

BMMC will not enter into third party discussion on column positions, any such discussions will be carried out between BMMC and the developer.

The street lighting columns and lanterns and their maintenance remain the responsibility of the developer until completion of the adoption process.

All lighting columns are to be provided with an unmetered single phase electricity supply via the REC cable network.

It is expected that the developer will coordinate with the REC regarding the installation of any cable ducts they may require.

A Road 7, 7-TH, 14 amended, plots re-numbered, plots 189-198 amended and all associated external levels and drainage amended accordingly.		DL	16.12.15
Rev	Description	By	Date
Client:			
Persimmon Homes West Yorkshire			
Project Title:			
Wilthorpe Road, Barnsley			
Drawing Title:			
Section 38 Agreement Layout Sheet 3			
Scale		Date	
1:500 @ A0		09.11.15	
Drawing No	Revision	Status	
4015-C-D7-03	A	Approval	

North East & Yorkshire:
Aske Stables, Aske, Richmond,
North Yorkshire, LS18 5HD
T: 01748 899015
F: 01565 740263

North West & Midlands:
Caldonian House,
Farnon Street, Altrincham,
Cheshire, WA16 6AG
T: 01565 755557
F: 01565 740263