








Rev	Revision Note	Date	Drawn by	Approved
1	First Issue	22/02/10	DS	MS
1-1	Section A - A Dimensions Amended	06/04/10	JS	DO
1-2	Door Structural opening height altered	15/06/10	NN	MS
1-3	Wall hatch and drainpipe description altered	19/08/10	DS	KB
1-4	Electrical notes amended	13/01/11	SW	KB
1-5	Bundled foundation and various general amendments added	18/02/11	AS	MS
1-6	Dimension and Eaving amendments	10/06/11	AS	MS
1-7	Door and Eaves details amended, ducts added	29/03/12	AS	MS



APPROVED FOR CONSTRUCTION



FOR MORE FOUNDATION DETAIL PLEASE REFER TO GTC SUBSTATION DRAWING GTC-E-EA-0003 AND SUBSTATION DOCUMENT EIN0012



GENERAL NOTES

- IF IN DOUBT - ASK !!! DO NOT SCALE
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER ENGINEERING DRAWINGS IN THIS SERIES AND THE GTC SUBSTATION SPECIFICATION.
- ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE RELEVANT BRITISH STANDARDS, CODES OF PRACTICE AND BUILDING PRACTICE.
- ALL DIMENSIONS TO BE CHECKED PRIOR TO STARTING THE WORKS ON SITE. ANY DISCREPANCIES TO BE REPORTED TO THE ENGINEER IMMEDIATELY.
- CONTRACTOR TO ASCERTAIN THE LOCATION OF SERVICES ON SITE PRIOR TO STARTING THE WORK.

ELECTRICAL NOTES

THE SUPPLY FOR THE SUBSTATION POWER AND LIGHTING WILL BE TAKEN FROM THE TRANSFORMER MOUNTED SUBSTATION AUXILIARY FUSE WAY USING 6mm² COPPER SWA PVC CABLE TO SUPPLY A SINGLE PHASE 230V STREET LIGHTING OUTLET MOUNTED BELOW THE POWER AND LIGHTING FUSE BOARDS. THIS WILL FEED A LOGA CONSUMER UNIT WITH A MAINBORN OF 4 MCB CONTROLLED WAYS (2x 16A FOR POWER AND 2x 6A FOR LIGHTING WITH A SPARE 16A WAY FOR SPECIAL REQUIREMENTS SUCH AS SCADA OR REMOTE ACTUATOR UNITS. EACH OUTGOING WAY WILL BE LABELED TO IDENTIFY CIRCUITS.

ALL INTERNAL WIRING TO BE CONTAINED IN 20mm HIGH IMPACT BLACK PVC CONDUIT AND ALL ACCESSORIES WILL BE NON METALLIC HIGH IMPACT AND FULLY INSULATED AND WEATHERPROOF AND SOURCE FROM A QUALITY MANUFACTURER (e.g. MEM OR MK).

TWO 13A SWITCHED SOCKET OUTLETS WITH 30mA RCD PROTECTION WILL BE PROVIDED IN A CONVENIENT LOCATION ON THE LEFT HAND SIDE OF THE SUBSTATION.

TWO 1800mm FLUORESCENT LAMP UNITS WITH POLYCARBONATE COVERS TO AT LEAST IP56 SPECIFICATION WILL BE FITTED TO THE CEILING AND CONTROLLED BY A NON METALLIC FULLY INSULATED LIGHTING SWITCH FITTED 1350mm ABOVE FINISHED FLOOR LEVEL ADJACENT TO THE FIRST LEAF OPENING DOOR. FOR GRP ROOFED SUBSTATIONS WALL MOUNTED BULKHEAD LIGHTS WILL BE FITTED.

THE SOCKETS ARE TO BE WIRED IN 2.5mm² COPPER CABLE AND THE LIGHTING WIRED IN 1.5mm² COPPER CABLE.

THE ELECTRICAL INSTALLATION IS TO BE IN ACCORDANCE WITH THE CURRENT EDITION OF BS7671 - IEE WIRING REGULATIONS

FOR SUBSTATIONS WITH SEPARATE HV AND LV EARTHING (NOT EARTHING)

CARE MUST BE TAKEN WITH LIGHTING AND SOCKET SUPPLIES TO AVOID THE POSSIBILITY OF MAKING CONTACT BETWEEN DIFFERENT EARTHING SYSTEMS.

AT HOT SITES ALL FITTINGS, SWITCHES AND CONDUIT MUST BE NON-METALLIC AND FULLY INSULATED TO THE SPECIFICATION ABOVE.

ALL 13A SOCKETS (INCLUDING SOCKET OUTLETS IN THE TRANSFORMER MOUNTED FUSE CABINET) MUST BE PROTECTED BY A 30mA RCD WITH THE EARTH TERMINAL CONNECTED TO THE HV STEELWORK.




APPROVED SUPPLIERS

STANDARD GRP SUBSTATION DOORS, VENTILATORS AND GRP TRENCH COVERS:
 ENVED MANUFACTURING, OBTAINED FROM:
 UTILITY POWER SYSTEMS, CARWOOD ROAD, CHESTERFIELD TRADING ESTATE, CHESTERFIELD S41 9QB
 Tel: 01246 202860
 Fax: 01246 455915
 Contact: JON TAYLOR

STEEL DOORS AND VENTILATORS AND GRP TRENCH COVERS:
 SUNRAY ENGINEERING LTD, KINGSNORTH INDUSTRIAL ESTATE, WOOTTON ROAD, ASHFORD, KENT TN23 8LL
 Tel: 01223 639279
 Fax: 01223 625137
 Email: SALES@SUNRAYDOORS.CO.UK

GAZDOWLING SYSTEM
 ERICO, 52 MILFORD ROAD, READING, BERKSHIRE, RL1 8JL
 Tel: 01189 588386

LEGEND:
 ○ LIGHT SWITCH
 △ 13A SWITCHED SOCKET OUTLET
 □ DISTRIBUTION BOARD
 ▭ FLUORESCENT LIGHT (1800mm LONG) INCLUDING DIFFUSER



Drawing Scale : 1:50
 O.S.REF : N/A
 Network Number : N/A
 Project Number :
 Drawing Number : GTC-E-SS-0012_R1-7_1_of_1

enc
 the electricity network co.

CLOSE COUPLED SUBSTATION
 PYRAMID ROOF DETAIL
 GENERAL ARRANGEMENT

SHEET SIZE **A1**