

A2

SECTION '104' SURFACE WATER
MANHOLE SCHEDULE – PHASE 2

Table with columns: MANHOLE REF NO., COVER LEVEL, PIPE DIAMETER, INVERT LEVEL, DEPTH TO SOFFIT (m), MANHOLE TYPE, COVER GRADE, NOTES. Rows include MH S4, MH S4A, MH S4B, MH S5, MH S5A, MH S6, MH S6A, MH S7, MH S7A, MH S18, MH S19, MH S19A, MH S19B, MH S20, MH S20A, MH S21, MH S21A, SURFACE WATER PUMP STATION, MH S22, OUTFALL 1.

SECTION '104' APPROVED
DEMARCATON CHAMBERS

Table with columns: MANUFACTURER, PRODUCT NAME, MATERIAL, MAX DEPTH, COVER TYPE. Rows include Naylor, Hepworth, Uponor, Marshalls, Wavin, Wavin, Wavin, Marley, Polypipe, Polypipe.

SECTION '104' FOUL WATER
MANHOLE SCHEDULE – PHASE 2

Table with columns: MANHOLE REF NO., COVER LEVEL, PIPE DIAMETER, INVERT LEVEL, DEPTH TO SOFFIT (m), MANHOLE TYPE, COVER GRADE, NOTES. Rows include MH F10, MH F10A, MH F10B, MH F11, MH F11A, MH F12, MH F12A, MH SD2, MH SD3, MH SD3A, MH SD8, MH SD8A, MH SD8B, MH SD9, MH SD9A, MH SD10, MH SD10A, MH SD11, MH SD11A, MH SD11B.

Concrete surround shall be provided to demarcation chamber where subject to vehicle loading (eg. driveways). For depths in excess of 1.2m a restricted access opening 350mm diameter (or 300x300mm) shall be used.

Alternatively, pre-cast concrete ring manhole to 'Sewers for Adoption' 6th Edition Specification may be used as a demarcation chamber. Chamber covers shall be ductile iron and appropriate strength for area situated (minimum classification B125).

DO NOT SCALE.

Only PDF/DWF Issues of this drawing are controlled. All other formats (eg. DWG AutoCAD FILES) are UN-controlled and are used at your own risk.

This drawing is copyright ©. It is sent to you in confidence and must not be copied, used or disclosed to any third parties without 3E permission. It remains the property of 3E and must be returned on request.

Contractors should refer to the residual risks contained in the CDM Pre Construction Information before carrying out any site operations and should not issue parts of this drawing without including the CDM notes and references. This information will include details of the SIGNIFICANT risks which 3E have considered beyond that which a competent contractor should be aware.

Revisions table with columns: Date, Revisions, Drawn, Rev. Includes entries for 30.07.13 and 14.05.13.

3E consulting engineers logo and contact information: 4 Calder Close, Vieldfield, W14 3BA, t 01924 240420, f 01924 240421, www.3econslult.com

Client: Kier Property Development Limited

Project: Midland Road, Royston

Title: Manhole Schedule Phase 2

Scale: NTS, Drawn: JM, Checked: AL, Date: MAY 13

Drawing Status: Preliminary

Job No.: 11120, Drawing No.: C1036, Revision: P2