

Datasheet

Viva-City Pro



Product Description

A modular, slimline, performance street lantern with improved efficacy and output. Viva-City Pro offers a choice of optics with asymmetrical distribution including an area optic.

Specification Text


The luminaire shall be manufactured from high-pressure die-cast aluminium. It shall have an LED efficacy of up to 150.0 lm/W and will be capable of producing up to 24,660 luminaire lumens at 4000K with a CRI >70. It shall have an asymmetric forward throw optic and is rated at IP66 and IK08.

Specify 2700K for IDA compliance.


Specification

Weight: 4.5 - 9.0kg
Windage: 0.09m²
Material: Die-cast Aluminium
Paint finish: RAL7016 Anthracite

Optics



Asymmetric Forward Throw Optic 70°



Street Optic - Wide 70°

Key Features

- 15.0 - 180.0W
- 2,250 - 24,660 Luminaire Lumens
- Efficacy up to 150.0 lm/W
- 4000K, CRI >70
- Lifetime >100,000hr, L80



Mounting Options

- Post Top 60mm

Other Options

- Part Night Dimming
 - Colour Temperature Option
 - Photocell Option
 - Emergency Option
- [Contact for details](#)

Code	Power	Luminaire Lumens	Drive Current	Optic	CCT(K)	IP	IK	Weight kg	Paint Finish	Driver Included	Driver Type
VCYP-AY70-4.3-15D	15.0	2,260	640	Street Optic - Wide 70°	4000	IP66	IK08	4.5	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-AY70-4.8-40D	40.0	5,927	805		4000	IP66	IK08	6.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-AY70-4.6-60D	60.0	8,844	610		4000	IP66	IK08	6.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-AY70-4.8-80D	80.0	11,120	805		4000	IP66	IK08	6.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-AY70-4.6-120D	120.0	17,828	610		4000	IP66	IK08	9.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-AY70-4.8-180D	180.0	24,840	880		4000	IP66	IK08	9.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-FW70-4.3-15D	15.0	2,250	640	Asymmetrical Forward Throw Optic - 70°	4000	IP66	IK08	4.5	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-FW70-4.8-40D	40.0	5,880	805		4000	IP66	IK08	6.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-FW70-4.6-60D	60.0	8,760	610		4000	IP66	IK08	6.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-FW70-4.8-80D	80.0	11,040	805		4000	IP66	IK08	6.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-FW70-4.6-120D	120.0	17,760	620		4000	IP66	IK08	9.0	RAL7016 Anthracite Grey	Driver Inc	DALI
VCYP-FW70-4.8-180D	180.0	24,660	880		4000	IP66	IK08	9.0	RAL7016 Anthracite Grey	Driver Inc	DALI



Dimensions

