

PHASE I
SITE INVESTIGATION

AT

MIXED USE DEVELOPMENT
WEST ROAD
SITE C

Ashton Bennett
ENGINEERING GEOLOGISTS AND ENVIRONMENTAL SCIENTISTS





**PHASE I
SITE INVESTIGATION**

AT

**PLOT 3, LAND OFF WEST ROAD
POGMOOR, BARNSELY**

FOR

TREVOR SIMPSON

ASHTON BENNETT CONSULTANCY

Engineering Geologists & Environmental Scientists

NOVEMBER 2010

Ashton Bennett Limited Co Reg No: 3318828 is a member of the Ashton Bennett Consultancy group of companies



CONTENTS

EXECUTIVE SUMMARY

RECOMMENDATIONS

1 INTRODUCTION

2 THE SITE

3 REPORT OBJECTIVE AND REPORT SCOPE

3.1 Report Objective

3.2 Report Scope

4 SITE HISTORY

5 POTENTIAL CONTAMINATION

6 SITE GEOLOGY

6.1 Geology

6.2 Geological Faults

6.3 Engineering Geology

7 SITE HYDROLOGY AND HYDROGEOLOGY

7.1 Hydrology

7.2 Hydrogeology

8 QUARRYING AND MINING

8.1 Quarrying

8.2 The Coal Authority Report

8.3 Shallow Mining

8.4 Mine Shafts

9 REGULATED INDUSTRIES

10 ENVIRONMENTAL RISK ASSESSMENT

10.1 Introduction

10.2 Potential Sources of Contamination, Pathways and Receptors

10.2.1 Potential Sources of Contamination

10.2.2 Potential Pathways of Migration

10.2.3 Potential Sensitive Receptors

10.3 Risk Assessment

11 RECOMMENDATIONS

12 GENERAL REMARKS




PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR, BARNSLEY
Mr. Trevor Simpson
TSI 2904

DRAWINGS

TSI 2904/1	Site Location Plan
TSI 2904/2	Site Plan
TSI 2904/3	Conceptual Model

APPENDICES

APPENDIX A	Historic OS Maps
APPENDIX B	Photographs
APPENDIX C	The Coal Authority Report



PHASE I DESK STUDY
 PLOT 3, LAND OFF WEST ROAD, POGMOOR
 Mr Trevor Simpson
 TSI 2904

EXECUTIVE SUMMARY

- OS maps indicate the site was previously occupied by land associated with a refuse destructor, a railway branch, filled ground and buildings which have since been demolished.
- Due to the presence of filled ground on the site, the unknown past uses of the site, the presence of nearby contaminative sources and pollution incidents there is a high potential for the site to be contaminated.
- The site is underlain by mudstone of the Middle Coal Measures, probably with a covering of clay derived from weathering of the mudstone. Made ground is known to be present. Major excavations have recently been underway at the site with significant quantities of made ground removed from the site.
- Made ground is unsuitable bearing strata. Sandstone and mudstone of the Middle Coal Measures generally provide good bearing strata for low rise development.
- The site lies on a minor aquifer overlain by soils of high leaching potential and does not lie in a fluvial or pluvial floodplain
- Very steep slopes around the site perimeters need supporting.
- The Coal Authority Report states that the site according to their records is within the zone of influence from 6 seams of coal mined at 30-370m depth. An abandoned mine shaft is present on the site.
- Shallow unrecorded mining may underlie the site at <30mbgl. Voids within shallow mining may migrate to the ground surface and cause ground subsidence.
- There are eight recorded landfills within 250m and infilled ground is present on the site.
- A potable water abstraction is located within 671m of the site. The nearest surface water is 200m from the site.
- Radon protection is not required.
- Soakaways are unlikely to be viable and are not recommended if contamination is present. An existing drainage installation is present on the site that requires further investigation.
- Intrusive ground investigation is required to assess foundation design and to monitor for gas and test made ground and groundwater (if present) for contamination.
- Intrusive ground investigation is required to assess the potential for voids in shallow mined ground and to locate and stabilise the mine shaft.

RECOMMENDATIONS

Investigation	Nature of Investigation	Details
Intrusive	Window sampling and cable percussion boring	To determine ground conditions and collect soil samples for both strength tests for foundation design and for contamination testing.
	Rotary Drilling	Drilling to assess dimensions and condition of mine shaft, potential for voids in shallow mined coal & ground instability
Non-Intrusive	Geophysics	To ascertain location of mine shaft.
Monitoring	Standpipe installation in WS and CP boreholes	To monitor for toxic gases and collect groundwater samples for testing
Laboratory Testing	Geotechnical Environmental	Plasticity if clay encountered. Testing for contamination in made ground and in any proposed landscaped areas. Testing of groundwater if encountered.



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904



1. INTRODUCTION

This report describes the results of a Phase I Desk Study undertaken at Plot 3, Land off West Road, Pogmoor, Barnsley. The work was undertaken on behalf of Trevor Simpson and was carried out by this Consultancy, the Ashton Bennett Consultancy.

The purpose of this Phase I Study was to collate and assess information on the site including geological, hydrogeological and mining information, archival maps and historical review to determine past use, a database review, environmental data on water and soil, and to undertake a site reconnaissance to enable a desk top assessment to determine the likely presence and areas of environmental concerns on the site and the presence of pathways of migration and potentially sensitive receptors, and to determine solutions to any geotechnical, environmental and mining concerns to the proposed change of use of the site for residential development.

This report describes the research work carried out, presents the results of the desk study and from the conceptual model of the site makes recommendations regarding solutions to environmental, geotechnical and mining risks to the site being redeveloped for residential development.



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904

2. THE SITE

A walk over survey of the site was undertaken on 3rd November 2010. The site has an area of approximately 0.35ha and is situated just to the south of West Road, Barnsley, South Yorkshire. Access to the site was directly from West Road. At the time of the walk over survey, the site was being excavated with significant quantities of material being taken off site. Towards the north of the site, excavation depths in the order of 10m had been reached with the limits of excavation close to the surrounding property to the west and road to the north. A significant stock pile of material was present in the south east corner of the site. The excavated and stock piled material was noted to comprise of colliery spoil (clay, mudstone, coal) with much glass and pottery fragments. Natural ground comprising of very weak thinly laminated mudstone was exposed by excavation in the centre of the site.

The site boundaries were noted as follows:

- West: Very steep slope circa 10m high formed by site excavations.
- South: Railway line (on embankment).
- East: Temporary fencing together with semi-mature deciduous trees.
- North: Very steep slope circa 10m high formed by site excavations with circa 2.5m high concrete block wall on top in poor condition.

Points of note on the site include:

- A portacabin used as a site office was present in the north east corner of the site.
- A steel portable tank was present in the centre of the site.
- A small concrete block building of unknown usage and in a poor condition was present at the top of the slope on the western boundary.
- A 1.5m diameter modern concrete cylindrical chamber with no cover was present in the south west corner of the site. The cylindrical chamber was surrounded by stock piled colliery spoil. Water was seen to be flowing at the base of the chamber. The depth of the cylindrical chamber was not determined but was in the order of 5m to 10m.

Vegetation on the site comprised of a number of semi-mature deciduous trees present on the eastern boundary, semi-mature coniferous trees present on the western boundary at the top of the slope with shrubs and bushes present on the southern boundary.

Observations of the land immediately surrounding the site were as follows:

- West Road was present immediately beyond the northern site boundary (cracks were noted in the road, possibly due to excavations on the site).
- A disused light industrial building was located immediately to the west of the site.
- Open scrub land was present immediately to the south west of the site.
- Open grassed land was present immediately to the east of the site.



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904

- A railway line was present immediately to the south of the site.

The surrounding land uses comprise of residential properties and park land to the north and north east, light industrial units and derelict buildings to west, a railway to the south and open land to the east.

The site lies around National Grid Reference SE 3314 0649 at a height of 135m above Ordnance Datum. A site location plan is presented as Drg No TSI 2904/1 and a site plan is presented as Drg No TSI 2904/2. A Conceptual Model is presented as Drg No TSI 2904/3. Archival maps are presented in Appendix A. The Coal Authority Report is presented in Appendix B and photographs are presented in Appendix C.

3. REPORT OBJECTIVE AND REPORT SCOPE

3.1 Report Objective

The objective of the desk study is to determine the environmental nature of the site and to establish any environmental concerns and liabilities with particular reference to past contaminative uses of the site as far as is possible from historical and database review. Contaminative use is defined as "any use of land which may cause it to be contaminated by toxic substances" (Section 143 of the Environmental Protection Act 1990). The report undertaken is a Phase I Desk Study and Risk Assessment taking into account the possible contamination, the migration pathways and the presence of potentially sensitive receptors and the engineering properties of the strata and the mining history of the site.

3.2 Report Scope

The information for this report is from sources recommended by the Institute of Civil Engineers (ICE), the Association of Geotechnical and Geoenvironmental Specialists (AGS), Construction Industry Research and Information Association (CIRIA) and the Department of the Environment Transport and the Regions (DETR). The report has been compiled in accordance with the latest ICE, DETR, Department of Environment, Food and Rural Affairs (DEFRA) and British Standard Draft Documents and British Standards, and Contaminated Land Reports.

In addition the scope of the investigation has used the extensive knowledge and experience of the staff of Ashton Bennett Consultancy to assess the data and to interpret the data findings.

4. SITE HISTORY

The following maps and plans were inspected to assess the history of the site and its past environments. The maps are presented in Appendix A.



PHASE I DESK STUDY
 PLOT 3, LAND OFF WEST ROAD, POGMOOR
 Mr Trevor Simpson
 TSI 2904

TABLE 1
Historical Maps Inspected

DATE	SCALE	DESCRIPTION	
		SITE	SURROUNDING AREA
1850	Plotted at 1:10,560	The map shows the site to be occupied by open land with Osiers at the southern end.	An unoccupied linear easement is present running along the southern boundary of the site. A footpath runs along the northern boundary of the site. The site surroundings generally comprise of farm land with a number of sandstone quarries and wells within a 500m radius.
1855	Not to Scale	No change to the site.	The easement to the south of the site is occupied by a railway line. The footpath forming the northern site boundary is now shown as a road.
1893	1:2,500	No change to the site.	An Old Clay Pit is present immediately to the west of the site. Slackhills Colliery and two Shafts are present approximately 200m to the north east of the site. An Old Shaft is present approximately 140m to the south west of the site. A Clay Pit is present approximately 190m to the south west of the site. A Brick Works and two Old Shafts are present 370m to the south west of the site.
1906	1:2,500	No change to the site.	The Old Clay Pit to the west of the site is now Summer Lane Brickworks.
1929	1:10,560	The site is now shown as part of land associated with but not occupied by a Refuse Destructor (Barnsley corpn). The map indicates that the ground on the site is covered by a Refuse Tip.	An area of raised ground is present approximately 130m to the west of the site. Summer Lane Brickworks is now shown as Refuse Destructor (Barnsley corpn). Old Shafts are shown approximately 180m to the south west of the site. The Old Shaft approximately 140m to the south west of the site is no longer shown. Farm House Colliery and a Drift mine are shown approximately 450m to the west of the site. A large area of excavated ground is shown immediately to the north of the site (beyond the road). A Brickworks with associated chimneys is shown approximately 80m to the north east of the site.
1932	1:2,500	No change to the site.	A Chimney is shown as part of the Refuse Destructor operation to the west of the site. Allotment gardens are present immediately beyond the eastern site boundary.
1956	1:10,560	No change to the site.	Farm House Colliery is shown as disused.
1961	1:2,500	The annotation showing the site as being occupied by a refuse tip has	The Refuse Destructor to the west of the site is now shown as Works and there has been



PHASE I DESK STUDY
 PLOT 3, LAND OFF WEST ROAD, POGMOOR
 Mr Trevor Simpson
 TSI 2904

DATE	SCALE	DESCRIPTION	
		SITE	SURROUNDING AREA
		been removed and the site is now shown to be occupied by significantly raised ground. A cluster of seven small buildings is present towards the southern end of the site. A branch of the railway line to the south of the site has been constructed over the southern portion of the site in cutting.	significant earthworks undertaken. A large pond is present to the north of the site occupying the majority of the excavated ground. The remainder of the excavated ground is shown as a Spoil Heap. The Brickworks and Old Clay Pits to the south and south west of the site are no longer shown and have been part replaced by residential housing.
1966	1:10,560	No change to the site.	No significant change.
1973	1:10,000	No change to the site.	Some buildings are present immediately beyond the western site boundary. The Pond and Spoil Heap to the north of the site are no longer shown.
1979	1:10,000	The cluster of buildings on the site has been removed. A new building has been built on the western side of the site. The railway branch that was on the site is no longer present.	A building is present immediately beyond the eastern site boundary.
1991	1:1,250	The site is now shown to be part of an industrial estate	Two Tanks are present approximately 100m to the west of the site.
1993	1:10,000	No change to the site.	The Allotment Gardens to the east of the site are no longer shown.

In summary, the site was open ground prior to 1929 when the site was shown to be part of land associated with a Refuse Destructor and the site was annotated as a refuse tip. Around 1961, the site was shown as raised ground, the neighbouring refuse destructor was replaced by a Works, a cluster of small buildings and a railway branch line were built on the site. Around 1979, the cluster of buildings and the railway branch line were removed and a new building was built. The site then assumed its present day layout. In the surrounding area, clay pits and brick works have been present from the late 1800s to the 1960s and significant spoil heaps, excavations and subsequent land filling has occurred.

5. POTENTIAL CONTAMINATION

The site has harboured significant imported material including refuse and possibly colliery spoil. A railway branch line was present on the site during the 1960s and 1970s. An industrial building has partially occupied the site since around 1979. Potential contamination may arise from the materials that have been imported onto the site and from the operations carried out within the building. The former usage of the building on the site is unknown therefore the potential for low-level contamination associated with this former usage exists.



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904

Potential off-site sources of contamination comprise of the clay pits, collieries, brick works, the refuse destructor and landfill operations that occurred in close vicinity to the site.

6. SITE GEOLOGY

6.1 Geology

The published British Geological Survey (BGS) maps at scales of 1:50,000 (Sheet 87 "Barnsley") & 1:10,000 (Sheet SE30NE "Barnsley") show the site area to be underlain by mudstone of the Carboniferous Pennine Middle Coal Measures. The Pennine Middle Coal Measures comprises an alternating sequence of mudstone, siltstone and sandstone with coal seams. Sandstone is shown to outcrop approximately 20m to the east of the site. Additionally, the 1:10,000 map shows the site to be occupied by Colliery Tip Material.

The Barnsley Coal (2.29m to 3.10m) is shown to outcrop approximately 100m to the south of the site. The general dip of the strata in the area is gently towards the north east.

An abandoned mine shaft is shown approximately 100m west of the site. Three abandoned mine shafts are shown approximately 200m to the north east of the site

An adit is shown approximately 150m to the south of the site.

An Old Brick Pit is shown 10m to the north of the site.

A borehole is shown 70m to the east of the site

6.2 Geological Faults

The BGS maps indicate the presence of a NE-SW trending geological fault with down throw to the south east running approximately 140m to the north west of the site. The 1:10,000 BGS map shows the Barnsley Coal Seam underlying this fault to be downthrown by 10m to the south east.

Another fault trending NW-SE with down throw to the north east outcrops approximately 100m to the south west of the site. The map notes the fault to be recorded in the Barnsley Coal Seam underground.

As tectonic activity is not active at the present time it is unlikely that the fault will detrimentally affect the stability of the site.

6.3 Engineering Geology

The Pennine Middle Coal Measures sandstone and mudstone strata provide good bearing strata where unweathered and unfaulted for carrying the bearing pressures imposed by low rise development without undue settlement. There is a very low risk of the site being



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904

detrimentally affected by shrinkable clays, landslides, compressible ground and running sand. There is a negligible risk of the site being affected by ground dissolution and collapsible deposits.

7. SITE HYDROLOGY AND HYDROGEOLOGY

7.1 Hydrology

The rainfall over the area of the site will drain into town drains and open ground on or adjacent to the site.

The site is shown by the Environment Agency not to lie within a fluvial flood risk area. The site is shown not to lie within a pluvial or surface water flood area. There are no available river quality assessments within 500m of the site. It is important that any contamination found on site is not allowed to detrimentally affect any watercourses. There are no surface water abstractions within 1000m of the site.

A small un-named stream is present approximately 200m to the south east of the site. The small stream appears to be in culvert for some distance. The next closest surface water course to the site is a tributary of the River Dearne, located approximately 1km to the north of the site.

During the site reconnaissance, a deep concrete shaft was noted in the southern corner of the site with water flowing at the base. It is believed that this shaft is an entry point to a large soakaway structure or a culverted storm water drain that has been recently installed. The direction of flow in the base of the shaft was towards the south east. Details of the outlet of the soakaway / drainage feature are not known at this stage and require further investigation.

7.2 Hydrogeology

The previously referenced BGS geological maps of the area indicate the site to be underlain by low-permeability mudstones overlying permeable sandstones. The sandstone bedrock will have moderate permeability through fractures in the rock.

Groundwater is not expected to lie at shallow depths below ground level. Groundwater is expected to be present at depth in the unweathered sandstone bedrock.

The Environment Agency Groundwater Vulnerability map indicates the site to lie on an area of a minor aquifer with high leaching potential. These are formations, which have a low permeability and may provide base flow to some rivers.

The Groundwater Vulnerability map indicates the minor aquifer is overlain by soils of high leaching potential which readily transmit liquid discharges because they are shallow or susceptible to rapid flow directly to rock, gravel or groundwater, and are soils with little



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904

ability to attenuate diffuse source pollutants in which non absorbed diffuse source pollutants and liquid discharges have the potential to move rapidly to underlying strata or shallow groundwater. Care should be taken not to intrude into any aquifer and cause pollution to enter the aquifer.

The Environment Agency holds details of four potable groundwater abstractions within 1000m of the site. Two are situated 671m to the south east of the site and use water from a groundwater spring from the Middle Coal Measures sandstone for water bottling. Two are situated 709m to the south east of the site and use groundwater from a spring from the Middle Coal Measures sandstone for water bottling. The local groundwater may also be utilised for abstraction from old unlicensed wells. It is thus important that it is protected from pollution. It is an offence to pollute the groundwater, whether or not it is used for abstraction.

The Environment Agency holds no records of authorisation issued by the Environment Agency to discharge to watercourses in accordance with the Water Resources Act 1991, within 250m of the site.

8. QUARRYING AND MINING

8.1 Quarrying

Old clay pits are present immediately to the north and west of the site and approximately 190m to the south west of the site. A number of small old sandstone quarries are present within 500m of the site.

8.2 The Coal Authority Report

The Coal Mining Report obtained from The Coal Authority for the site states that according to their records the property is in the likely zone of influence from 6 seams of coal mined at 30-370m depth, and last worked in 1978. Any ground movement associated with these workings should have stopped by now. The property is not in the likely zone of influence of any present underground coal workings. The property is not in an area for which the Coal Authority is determining whether to grant a license to remove coal using underground methods. Reserves of Coal do exist in the local area which could be worked at some time in the future. The property is not in an area for which a notice of entitlement to withdraw support has been published. Details of The Coal Authority Report are presented as Appendix B and should be read in full.

8.3 Shallow Mining

The geological maps indicate the possible presence of The Barnsley Coal (2.29m to 3.10m) at shallow depth beneath the site, <30 mbgl. Additionally, the Coal Authority report indicates that the site is within the zone of influence of coal previously worked from 30m.bgl. It is also possible that coal seams were worked before the requirement in 1872 to deposit



PHASE I DESK STUDY
 PLOT 3, LAND OFF WEST ROAD, POGMOOR
 Mr Trevor Simpson
 TSI 2904

abandonment plans with the Ministry of Power and as such will not be recorded by the Coal Authority. If voids are present in shallow mined coal seams they can migrate by successive roof collapse over the years and cause ground subsidence and structural damage to overlying structures.

8.4 Mine Shafts

The Coal Authority report indicates the presence of an abandoned mine shaft on the site. It is not known as to what measures have been taken to backfill the shaft.

9. REGULATED INDUSTRIES

Results of searches for regulated industries are presented in Table 2.

TABLE 2
Authorisations, Incidents and Registers

	ON SITE	WITHIN 250m	DETAILS
Historic Ground Workings	-	3	Old clay pits are present immediately to the north and west of the site and approximately 190m to the south west of the site.
Landfill Sites (within 250m)	-	8	16m north of site: Allotment Gardens. On site: West Road (licensed 15-07-87 to 31-12-90 – Barnsley Metropolitan Council) On site: Land West of Summer Dairy (inert, industrial, commercial). Licensed 18-11-82 to 03-06-88 – Co-op Retail Services). 38m south of site. Land north of Dodsworth Road. 33m east of site: West Road (inert). Record dated 01-09-87 76m north east of site: West Road (inert). Record dated 01-07-87 152m south east of site: Summer Lane Dairy (inert). Record dated 01-07-83. 242m west of site: Recreation Ground
Treatment & Transfer Sites	-	1	15m south of site. Haulage Yard off West Road. Non hazardous Waste Type.
Waste Management Sites	-	2	53m west of site. Haulage Yard. Off West Road. Household, Commercial & Industrial Waste 15m south of site. Haulage Yard, Off West Road. Household, Commercial & Industrial Waste
Radioactive Consents	-	-	-



PHASE I DESK STUDY
 PLOT 3, LAND OFF WEST ROAD, POGMOOR
 Mr Trevor Simpson
 TSI 2904

	ON SITE	WITHIN 250m	DETAILS
Dangerous Substance Inventory	-	-	-
Control of Major Accident Hazards Regs and NIHHS	-	-	-
Prosecutions or Enforcement Action	-	2	69m west of site. S J Autowelding, West Road-Waste Oil Burning Process (Current Permit). No Enforcement notified 75m south of site. Polar Motor Co Ltd, Dodsworth Road – Vehicle Re-spray Process. (Current Permit) No Enforcement Notified
Hazardous Substances Consents	-	-	-
Integrated Pollution Control (IPC)	-	3	3No. entries 148m north east of the site: Royston Lead Limited (non ferrous metals).
Integrated Pollution Prevention and Control (IPPC)	-	9	9No. entries 148m north east of the site: Royston Lead Limited (non ferrous metals).
Local Authority Pollution Prevention and Control	-	-	-
Pollution Incidents	-	4	3No. entries at 80m north west of site (06-02-03). Natural organic (unidentified oil); other general biodegradable waste or material. Category 3 minor impact (land), Category 4 no impact (water, air) 86m north west of site (09-09-02). Other general biodegradable waste or material. Category 3 minor impact (land, air), Category 4 no impact (water)
Fuel Stations (within 250m)	-	1	135m south west of the site. Obsolete, Polar Motor Company Ltd, Dodsworth Road.
Designated Environmentally Sensitive Sites (SSSI, NNR, LNR, SAC, SPA, RAMSAR, AONB, Nat Parks)	-	1	Nitrate Vulnerable Zone
Radon Affected Area	NO		Property in area where less than 1% of properties are above the Action Level.
Discharge Consents	-	-	-
Red List Discharges to Controlled Water	-	-	-
Adjacent Potentially Contaminative Sites	-	16	10m west, 67m & 168m north west of site – Industrial Estate. 95m west of site – Tanks 69m west of site – S J Auto Welding – Cutting, drilling and welding Services. 230m north west of site - Tanks 52m west of site – Hiltons Electrical Services Ltd. 150m north of site - Easy Life Mobility



PHASE I DESK STUDY
 PLOT 3, LAND OFF WEST ROAD, POGMOOR
 Mr Trevor Simpson
 TSI 2904

	ON SITE	WITHIN 250m	DETAILS
			57m south & 110m east of site-Works 67m east & 144m south of site-Electricity Sub Station. 131m south east of site – Royston Lead Limited 119m south east of site – Probike Security 207m east of site – Modern Signs and Designs Limited 209m south east of site – S E Gas Services.
Site Determined as Contaminated Land Part IIA EPA 1990	NO		-
Residential Property (within 250m)	YES		70m north west of site.

Results of searches for regulated industries are presented in Table 2 above and indicate that a number of potentially contaminative off-site past and present activities could have affected the site.

10. ENVIRONMENTAL RISK ASSESSMENT

10.1 Introduction

It is proposed to change the site use from industrial land use to residential housing with hard cover and landscaped ground and gardens. The environmental liabilities of the site and risk assessments have been undertaken for this potential future use. If the proposed site use changes then a further risk assessment will be required.

Environmental risk considerations on the site have been assessed by adopting a site specific qualitative approach to identify the risk, if any, of environmental harm. In accordance with the DETR Draft Statutory Guidance on Contaminated Land the approach is by identifying a hazardous source and establishing possible links between the source via exposure pathways to a potential receptor.

The hazard is a contaminant or potentially polluting substance that is in, on or under the land and which has the potential to cause harm or to cause pollution to controlled waters. The receptor is a living organism or organisms, an ecological system or piece of property, which is being harmed, interfered with or polluted by the contaminant. The pollutant linkage is by means of the pathway which is one or more routes by or through which that receptor is being, or could be, exposed to, or affected by, that contaminant. Thus the presence of a hazard on a site does not necessarily mean that there are risks unless pathways and receptors are present and are receptive to being affected by that specific hazard or contaminant.



PHASE I DESK STUDY
 PLOT 3, LAND OFF WEST ROAD, POGMOOR
 Mr Trevor Simpson
 TSI 2904

SOURCE	release of pollutant	PATHWAY	route to receptor	RECEPTOR
	eg. oil spills		eg. permeable strata	eg. River

The likelihood of contamination affecting the environment depends on the migration and persistence of contaminants which varies with the nature of the contaminant and the ground and groundwater conditions, and the presence of sensitive receptors.

The likelihood or risk of sensitive receptors being affected is based on a very low/low/medium/high/very high risk rating.

Very Low	=	It is very unlikely that an environmental risk exists, no remediation
Low	=	It is unlikely that an environmental risk exists, remediation unlikely
Medium	=	It is possible that an environmental risk exists, remediation possible
High	=	It is likely that an environmental risk exists, remediation probable
Very High	=	It is very likely that an environmental risk exists, remediation certain

Any category which shows as medium risk or above may require investigation and if high risk is proven, remediation may be required following investigation.

10.2 Potential Sources of Contamination, Pathways and Receptors

10.2.1 Potential Sources of Contamination

In summary, the site was open ground prior to 1929 when the site was shown to be part of land associated with a Refuse Destructor and the site was annotated as a refuse tip. Around 1961, the site was shown as raised ground, the neighbouring refuse destructor was replaced by a Works, a cluster of small buildings and a railway branch line were built on the site. Around 1979, the cluster of buildings and the railway branch line were removed and a new building was built. In the surrounding area, clay pits and brick works have been present from the late 1800s to the 1960s and significant spoil heaps, excavations and subsequent land filling has occurred.

More recently, significant excavations have taken place on the site which have revealed that several metres thickness of made ground has been removed from the site. At the time of the site reconnaissance, a mobile tank was present close to the centre of the site (the contents of the tank were unknown).

Off site sources of contamination exist including the backfilled clay pits, nearby industrial land uses and recorded pollution incidents.

There is thus a potential for contamination to exist on the site, either from past or present on-site and off-site activities.



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904

10.2.2 Potential Pathways for Migration

The potential pathways for carrying any contamination present on the site to reach sensitive receptors may include:

- a) Ingestion of and/or skin contact with contamination in the soil
High – the site has harboured imported material and potentially contaminative land uses since the 1920s. There is therefore a high risk to future occupants of houses which should be assessed by intrusive investigation and testing. There will be risk to workmen which may be mitigated by appropriate use of Personal Protective Equipment. There is a low risk of contamination in the soil migrating off site due to low permeability of expected clay soil underlying the site.
- b) Ingestion of contamination and uptake of contamination in plants/vegetables/animals
High – vegetables may be grown in proposed residential gardens on the site, presenting a risk to occupants of the proposed houses and this risk requires investigating with suitable remediation or mitigating measures deployed as necessary. It is considered that animals in the food chain are unlikely to be present on site.
- c) Ingestion of contaminated drinking water through leaching of contamination into groundwater flowing to underlying aquifers/water abstractions
Medium – leaching of any contamination may detrimentally affect shallow groundwater if present beneath the site. The site lies on a minor aquifer and it is important that it is not contaminated. There are two recorded potable water abstraction located 671m to the south east and a further two located 709m to the south east which should be protected from contamination. It is recommended that any groundwater encountered during ground investigation is tested for contamination. In addition to the above, further investigation to establish the drainage details of the soakaway on site needs to be undertaken to make an assessment of the risk to controlled groundwater.
- d) Inhalation of vapours produced by landfill/radon/hydrocarbons/old mines
High – It is known that material has been imported on to the site since the 1920s. Also, there are eight recorded landfill sites within 250m of the site. The site does not lie in a radon protection area. Ground gas may be produced by any organic materials or contamination present in any made ground that may be present on the site. Hydrocarbons may be present in the ground from previous and existing land use and mine gas may be present from shallow mining. Monitoring is required to assess risk.
- e) Inhalation of contaminated airborne dust
Low – The appropriate safety measures must be exercised to protect both the workers and the local residents from dust during construction. Provided this work is carried out diligently, the ongoing risk is low.



f) Contamination of controlled surface waters

Medium – Further investigation to establish the drainage details of the soakaway on site needs to be undertaken to make an assessment of the risk to controlled surface waters.

10.2.3 Potential Sensitive Receptors

By considering where a viable pathway exists which connects a source to a receptor, this assessment will identify where pollutant linkages may exist. If there is no pollutant linkage, then theoretically there is no risk. Therefore only where a viable pollutant linkage is established does this assessment go on to consider the level of risk. On this site there is a medium to high potential for contamination to exist and viable pathways are present for distribution of contamination to sensitive receptors.

TABLE 3
Risk Assessment for Residential With Plant Uptake

Pathways	Receptors	Risk	Probability of Risk	Severity of Risk Risk Reduction
Inhalation of vapours such as methane from landfill and radon, hydrocarbons and mine gas	Existing/future occupants of the proposed development and workmen. Neighbouring land use.	High – Infilled ground within 250m of the site. Made ground known to be present on site. Potential for mine gas. Radon protective measures not required.	High	High. Methane can be explosive in air. Risk reduction required by monitoring for toxic gases and mine gas and adopting appropriate mitigation.
Ingestion of and/or skin contact from contaminated soil	Existing/future occupants of the proposed development and workmen.	High – Made ground known to be present beneath the site. Potentially contaminative existing and former usage of buildings on the site.	High	High. Risk reduction required by testing soil for contamination and adopting appropriate mitigation measures.
Ingestion of contaminated drinking water	Local abstraction wells	Medium – Site on minor aquifer. Closest registered potable boreholes 671m from the site. Drainage details of the soakaway on the site need to be established to properly assess risk.	Medium	High. Severe consequences if potable water is contaminated. Risk reduced by testing for contamination, testing any groundwater encountered and adopting suitable mitigation measures.
Transportation by surface and/or groundwater	Groundwater. Surface water 200m to the south east. Unknown drainage feature /	Medium – Drainage details of the soakaway on the site need to be established to properly assess risk. However, site is on a minor aquifer and	Medium	High. Prosecution can occur if site is affecting controlled waters.



PHASE I DESK STUDY
 PLOT 3, LAND OFF WEST ROAD, POGMOOR
 Mr Trevor Simpson
 TSI 2904

Pathways	Receptors	Risk	Probability of Risk	Severity of Risk / Risk Reduction
	soakaway on site.	groundwater should be tested if encountered.		
Ingestion and uptake of contamination in plants/animals/vegetables	Existing/future occupants of the proposed development.	High - Gardens may be included as part of the proposed development.	Medium to High	Medium to high. Risk reduction required by testing soil, remediating any contamination and sealing and or importing clean materials if necessary.
Inhalation of airborne dust	Workmen & future occupants of the site. Neighbouring land use.	Low – Provided dust suppression during construction and any asbestos removed according to government regulations	Low	Low. Provided recommendations undertaken.

The potential sensitive receptors on the site, once the site is changed for residential use with plant uptake, which could be detrimentally affected by any contamination and the likelihood of them being affected, are identified in Table 3.

10.3 Risk Assessment

The risks have been assessed purely on the Phase I Desk Study undertaken and on the assumption that the site will in the future be used for residential dwellings with hard cover, landscaped ground and gardens.

The potential contamination, pathways and receptors were taken into account during the Desk Study. The assessment of the likelihood of receptors being affected detrimentally is that there is a medium likelihood that groundwater, potable water or surface water is being polluted due to the presence of the soakaway / drainage feature on the site and that the site is on a minor aquifer. However the closest known potable abstractions and surface water features are distant. It is considered that there is a high likelihood that land or humans on and / or adjacent to the site are being detrimentally affected by any contamination on the site. Without remediation, there is a high risk that future occupants of the site could be detrimentally affected by inhalation/ingestion or skin contact with contamination in the ground, landfill and mine gas. Workmen may be detrimentally affected by contamination and ground gas.

It is considered high risk that contamination exists on the site and a medium risk that contamination could migrate and detrimentally affect surface and groundwater. There is a high risk that contamination may detrimentally affect site users or workman by ingestion/skin contact. There is a high risk that contamination may detrimentally affect site users, adjacent land uses and workmen by inhalation. These preliminary risk assessments



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904

require quantifying by ground investigation and soil / groundwater testing and gas monitoring on the site.

Radon protection is not required.

There is a risk that voids may be present in shallow mined coal seams (<30m bgl) and the mine shaft on the site which require investigation to assess ground stability for the proposed development.

11. RECOMMENDATIONS

Based on the Desk Study undertaken it is concluded that there is a high risk of contamination detrimentally affecting sensitive receptors adjacent to and on the site. However, provided investigation, soil and groundwater testing and gas monitoring is undertaken to assess the potential for contamination and provided suitable precautions are undertaken to prevent any detected gas or contamination reaching sensitive receptors then the risks can be reduced to acceptable limits. There is a high risk of contamination being present on the site in the form of heavy metals, organic compounds, landfill and mine gas and detrimentally affecting future occupants, workmen and users of the site. A Phase II Investigation is recommended for assessment of load bearing strata, for foundation design, for undertaking tests for the presence of contamination in soil and groundwater and for ground gas monitoring. On completion of the Phase II the risks can be re-assessed and a remediation plan can be designed if significant contamination is found to be present at the site.

Soakaways are unlikely to be viable due to underlying clay soils and mudstone and are not recommended if contamination is present on the site.

Ground stability requires investigation to assess the potential for voids in shallow mined coal seams detrimentally affecting the proposed development. If voids are present at shallow depth ground investigation and stabilisation may be required beneath selected house plots. Additionally the abandoned mine shaft on the site needs to be located, investigated and stabilised.

Very steep slopes due to excavations on the site will need to be stabilised prior to development proceeding. The steep slopes on the western site boundary are in danger of destabilising the neighbouring property. The steep slopes on the northern site boundary are in danger of destabilising West Road.

Provided the investigation and any necessary remediation to residential use standards and ground stabilisation is undertaken then the site would be suitable for residential development with gardens.



PHASE I DESK STUDY
PLOT 3, LAND OFF WEST ROAD, POGMOOR
Mr Trevor Simpson
TSI 2904

12. GENERAL REMARKS

This report truly reflects the conditions found during the desk study. Whilst the desk study was undertaken in a professional manner taking due regard of additional information which became available as a result of ongoing research, the results portrayed only pertain to the information attained, and the ground and gas conditions, mining conditions and contamination expected and it is possible that other undetected information and undetected ground and gas conditions, undetected mining conditions and undetected contamination may exist. The desk study was only undertaken within the site boundaries and should not be used for interpretation purposes elsewhere. These conclusions are only a brief summary of the report, and it is recommended that the report is read in full to ensure that all recommendations have been understood.


This report is provided for the sole use of the client (Mr Trevor Simpson) and no responsibility will be accepted by this Consultancy to any other parties who rely on this report entirely at their own risk. The copyright for this report is held by Ashton Bennett Consultancy and no reproduction of any part or all of the report can be undertaken or any other reproduction undertaken without the written approval of this Consultancy.

Jim Dennis
BSc, MSc, FGS, DIC

Frances A Bennett
BSc, CGeol, FGS, FIMMM, CEnv, MCIWEM, AIEMA, MIEEnvSci.



Plot 3, Land off West Road, Pogmoor, Barnsley – SITE LOCATION PLAN



Scale: 1:50,000 Reduced

Drg. No. TSI 2904/1




Plot 3, Land off West Road, Pogmoor, Barnsley – SITE PLAN



Scale: 1:1,250 Reduced

Drg. No. TSI 2904/2



SOURCES	PATHWAYS	RECEPTORS	RISK	GEOLOGY
HISTORICAL USE AS INFILLED GROUND	1 Inhalation of vapours	Workmen/future occupants of residential house Neighbouring land use	High. Ground gas from backfilled quarries, underground mining and made ground.	
BUILDINGS	2 Ingestion and or skin contact	Workmen/future occupants of residential houses	High. Possible soil and groundwater contamination.	
REFUSE DESTRUCTOR	3 Ingestion of drinking water	Potable borehole 671m from the site	medium-due to dist to pot hole Soakaway needs investigatin	
REFUSE TIP	4 Leaching to surface/groundwater	Groundwater and surface water	medium-due to dist to pot hole Soakaway needs investigatin	
MINING	5			
NEIGHBOURING ACTIVITIES	6 Ingestion of plants/ animals/ veg	Future site occupants of residential houses	High. Gardens and landscaped ground may be proposed	
LANDFILL	7			
RAILWAY BRANCH LINE	Inhalation of dust	Workmen & neighbouring land use	Low - provided precautions taken during construction.	Drq. No. TSI 2904/3
MINING & QUARRYING	Ground subsidence	Possible shallow mining and mine shafts.	High - coal could have been mined locally at <30m bgl.	

Appendix A



Land off West Road, Pogmoor, Barnsley – OS MAP 1850



Scale: 6" TO 1MILE Reduced




Land off West Road, Pogmoor, Barnsley– OS MAP 1855




Scale: N T S



Land off West Road, Pogmoor-- OS MAP 1906



Scale: 1:2,500 Reduced




Land off West Road, Pogmoor, Barnsley – OS MAP 1929



Scale: N T S




Land off West Road, Pogmoor, Barnsley – OS MAP 1932



Scale: 1:2,500 Reduced



Land off West Road, Pogmoor, Barnsley – OS MAP 1956



Scale: 1:10,560 Reduced




Land off West Road, Pogmoor, Barnsley – OS MAP 1961




Scale: 1:2,500 Reduced



Land off West Road, Pogmoor, Barnsley – OS MAP 1966




Scale: 1:10,560 Reduced



Land off West Road, Pogmoor, Barnsley – OS MAP 1973



Scale: 1:10,000 Reduced



Land off West Road, Pogmoor, Barnsley – OS MAP 1979



Scale: 1:10,000 Reduced




Land off West Road, Pogmoor, Barnsley – MAP 2009



Scale: 1:1,250 Reduced

Appendix B



PLOT 3, LAND OFF WEST ROAD, POGMOOR, BARNSELY – PHOTOGRAPHS



View towards West Road from east of site.



View north over site from south boundary



View south over site from north boundary



Stockpile in southeast area of site



Large container in south of site.



Surface water soakaway in south east of site.

Appendix C

Issued by:

The Coal Authority, Mining Reports Office, 200 Lichfield Lane, Berry Hill, Mansfield, Nottinghamshire NG18 4RG
 ON-Line Service: www.groundstability.com - Phone: 0845 762 6848 - DX 716176 MANSFIELD 5

ASHTON BENNETT CONSULTANCY,
 BRIDGE MILLS,
 HOLMFIRTH,
 WEST YORKSHIRE,
 HD9 3TW

Person dealing with this matter: **Darren Moody**
 Our reference: **00048286-10**
 Your reference: **2904**
 Electronic Ref:
 RRUID: **007.00029105410001**
 Date of your enquiry: **29 October 2010**
 Date we received your enquiry: **29 October 2010**
 Date of issue: **01 November 2010**

This report is for the property described in the address below and the attached plan.

Non-Residential Coal and Brine Report Site At, West Road, Barnsley, South Yorkshire

This report is based on and limited to the records held by, the Coal Authority, and the Cheshire Brine Subsidence Compensation Board's records, at the time we answer the search.

Coal mining	Yes
Brine Compensation District	No

Information from the Coal Authority

Underground Coal Mining

Past

The property is in the likely zone of influence from workings in 6 seams of coal at 30m to 370m depth, and last worked in 1978.

Any ground movement from these coal workings should have stopped by now.

Present

The property is not in the likely zone of influence of any present underground coal workings.

Future

The property is not in an area for which the Coal Authority is determining whether to grant a licence to remove coal using underground methods.

The property is not in an area for which a licence has been granted to remove coal using underground methods.

All rights reserved. You must not reproduce, store or transmit any part of this document unless you have our written permission.

The property is not in an area that is likely to be affected at the surface from any planned future workings.

However reserves of coal exist in the local area which could be worked at some time in the future.

No notice of the risk of the land being affected by subsidence has been given under section 46 of the Coal Mining Subsidence Act 1991.

Mine entries

Within, or within 20 metres of, the boundary of the property there is 1 mine entry, the approximate position of which is shown on the attached plan.

There is no record of what steps, if any, have been taken to treat the mine entry.

Records may be incomplete. Consequently, there may exist in the local area mine entries of which the Coal Authority has no knowledge.

Coal-mining geology

The Authority is not aware of any evidence of damage arising due to geological faults or other lines of weakness that have been affected by coal mining.

Opencast Coal Mining

Past

The property is not within the boundary of an opencast site from which coal has been removed by opencast methods.

Present

The property does not lie within 200 metres of the boundary of an opencast site from which coal is being removed by opencast methods.

Future

The property is not within 800 metres of the boundary of an opencast site for which the Coal Authority is determining whether to grant a licence to remove coal by opencast methods.

The property is not within 800 metres of the boundary of an opencast site for which a licence to remove coal by opencast methods has been granted.

Coal-mining subsidence

The Coal Authority has not received a damage notice or claim for the property since 1 January 1984. There is no current Stop Notice delaying the start of remedial works or repairs to the property.

The Authority is not aware of any request having been made to carry out preventive works before coal is worked under section 33 of the Coal Mining Subsidence Act 1991.

Mine gas

There is no record of a mine gas emission requiring action by the Coal Authority within the boundary of the property.

Hazards related to coal mining

The property has not been subject to remedial works, by or on behalf of the Authority, under its Emergency Surface Hazard Call-Out procedures.

Withdrawal of Support

The property is not in an area for which a notice of entitlement to withdraw support has been published.

The property is not in an area for which a notice has been given under section 41 of the Coal Industry Act 1994, revoking the entitlement to withdraw support.

Working Facilities Orders

The property is not in an area for which an Order has been made under the provisions of the Mines (Working Facilities and Support) Acts 1923 and 1966 or any statutory modification or amendment thereof.

Payments to Owners of Former Copyhold Land

The property is not in an area for which a relevant notice has been published under the Coal Industry Act 1975/Coal Industry Act 1994.

Comments on Coal Authority information

In view of the mining circumstances a prudent developer would seek appropriate technical advice before any works are undertaken.

Therefore if development proposals are being considered, technical advice relating to both the investigation of coal and former coal mines and their treatment should be obtained before beginning work on site. All proposals should apply good engineering practice developed for mining areas. No development should be undertaken that intersects, disturbs or interferes with any coal or mines of coal without the permission of the Coal Authority. Developers should be aware that the investigation of coal seams/ former mines of coal may have the potential to generate and/or displace underground gases and these risks both under and adjacent to the development should be fully considered in developing any proposals. The need for effective measures to prevent gases entering into public properties either during investigation or after development also needs to be assessed and properly addressed. This is necessary due to the public safety implications of any development in these circumstances.

The attached plan shows the approximate location of the disused mine entry/entries referred to in this report. For reasons of clarity, mine entry symbols may not be drawn to the same scale as the plan. Property owners have the benefit of statutory protection (under the Coal Mining Subsidence act 1991*). This contains provision for the making good, to the reasonable satisfaction of the owner, of physical damage from disused coal mine workings including disused coal mine entries. A leaflet setting out the rights and the obligations of either the Coal Authority or other responsible persons under the 1991 Act can be obtained by telephoning 0845 762 6848 or online at www.coal.gov.uk/services/subsidence. If you wish to discuss the relevance of any of the information contained in this report you should seek the advice of a qualified mining engineer or surveyor. If you or your adviser wish to examine the source plans from which the information has been taken these are normally available at our Mansfield office, free of charge, by prior appointment, telephone 01623 637233. Should you or your adviser wish to carry out any physical investigations that may enter, disturb or interfere with any disused mine entry the prior permission of the owner must be sought. For coal mine entries the owner will normally be the Coal Authority.

The Coal Authority, regardless of responsibility and in conjunction with other public bodies, provide an emergency call out facility in coalfield areas to assess the public safety implications of mining features (including disused mine entries). Our emergency telephone number at all times is 01623 646333.

*Note, this Act does not apply where coal was worked or gotten by virtue of the grant of a gale in the Forest of Dean, or any other part of the Hundred of St. Briavels in the county of Gloucester.

Information from the Cheshire Brine Subsidence Compensation Board

The property lies outside the Cheshire Brine Compensation District.

Additional remarks

This report is prepared in accordance with the Law Society's Guidance Notes 2006, the User Guide 2006 and the Coal Authority and Cheshire Brine Board's Terms and Conditions 2006. The report is compliant with Home Information Pack requirements.


The Coal Authority owns the copyright in this report. The information we have used to write this report is protected by our database right. All rights are reserved and unauthorised use is prohibited. If we provide a report for you, this does not mean that copyright and any other rights will pass to you. However, you can use the report for your own purposes.

Issued by:	The Coal Authority, 200 Lichfield Lane, Mansfield, Nottinghamshire, NG18 4RG
Date:	01 Nov 2010
Coal and Brine Report at:	Site At, West Road, Barnsley, South Yorkshire
Reference number:	00048286-10
Cost:	£64.00
Plus VAT:	£11.20
Total received:	£75.20
VAT registration number:	598 5850 68

Location map



Approximate position of property



Enquiry boundary


These maps are reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office. © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. The Coal Authority. Licence number: 100020315. [2006]

Key

Approximate position of enquiry boundary shown



Disused Adit or Mineshaft



This page is intentionally blank