



Office: 01634 684 235

Mobile: 07718 123 372

E-mail: info@sovereign-sports.co.uk

- SERVICES
- - New construction
 - Reconstruction
 - MUGA Construction

-
-
-
-
-
-
-
-
-
-

NEW SURROUND CHAIN LINK FENCING SYSTEMS





Our company provides two systems as standard, tubular or angle iron powder coated in either green or black. The first is the supply and erection of a 2.75m (9ft) high struttred, tubular fence to the complete surround, along with a standard single leaf gate. In the vast majority of cases, for example where the court is clearly visible from the house or if you wish to have a viewing area to one side of the court, then we can incorporate a dropped section to one length, to a height of approximately 1m, with a small 1m x 1m gate positioned at the centre of the perimeter fence.

We are able to customise your fence design in numerous ways, such as installing larger posts, extra large gates, double gates, kick boards, altering the fence height, using more robust thicker core chain link netting, installing tubular systems with decorative finials, top and bottom rails can be included for extra rigidity.

We also supply and erect a wide variety of alternative fencing systems. These are aimed more at the multi-use games areas (MUGA) such as football and hockey. These sports require a more robust fencing system due to the high impact of the balls.

BALL COURT FENCING SYSTEMS



We can offer all types of ball court fencing to fit your facility from 1m high viewing barriers, to full 5m height MUGA rebound fencing, along with the required goal ends and basketball hoops.

The most popular type of sports fencing we install, is the 3m high sports rebound fencing. This is typically manufactured from twin 8mm horizontal wires . This sports court system can easily be installed at 4m high or 5m high and all our fencing whether it be tennis court, MUGA, or rebound fencing can be galvanised and powder coated.

ZAUN



The Super Sports Rebound Panel by ZAUN has become the preferred and popular choice over wooden rebound board systems which offer a hiding place to trespassers and children, and acts as a canvass for graffiti, and is not able to provide a long lasting service life due to the nature of the material used.

The Twin horizontal 8mm wires ensure vital resistance to deformation from impacts and vandalism and it is suitable for a range of multi sports games areas. Most importantly, the high-density twin wire construction allows for rebound qualities similar to that of a solid surface, meaning that the angle at which a ball strikes the surface will be the same as the angle at which it leaves the surface. The panels' structural strength makes it ready for the pressure and abuse of many sports activities, giving the fence a degree of rigidity unparalleled by any other wire product commonly available.

WISA PA SYSTEM



Designed, manufactured and installed for use in Multi Sport Areas for High Impact activities such as five-a-side football where the fence surround, is an integral part of the play. This system incorporates robust fibre panels around the lower part of the fence.

358 PA SYSTEM FENCE



This kind of fencing is incredibly durable and a necessity for multi-games areas where football and other high impact sports are going to be played. '358' comes from the old imperial measurements, 3" x 0.5" x 8 gauge, which refers to the dimensions of the panels. Originally this style of fencing was designed for high security environments, combined with an all steel framework coated to industry standards.

REBOUND PANEL

High Density welded mesh panel, with a rigid but forgiving surface. The 358 Panel offers excellent Vandal Resistance as well as aesthetic qualities when polyester powder coated with any colour from the RAL range. The 358 PA SYSTEM framework uses a combination of Durable box section and angle steel. The upper fence cladding materials to be typically a 50 x 50 x 3mm roll format welded mesh fixed using the optimum amount of high tensile line wires, ensuring a strong but flexible deflection surface.

CUSTOMISED FENCING



MUGA SYSTEMS



SURFACES



Sovereign Sports offer a range of synthetic surfaces suitable for Multi use play. Ranging from Matchplay2, which is a 6mm sand dressed synthetic surface through to Conqueror 60 MF 3rd Generation 60 mm sand and rubber infill, ideal for five-side football.

MORE

MAINTENANCE



All surfaces need regular maintenance to retain good condition, whether it is porous macadam, synthetic clay, synthetic grass. Every surface should be swept clean and all leaves, pine needles, detritus and rubbish should be removed on a weekly basis

MORE

FLOODLIGHTING



Sovereign Sports are able to offer 2 types of lighting system, Static or Retractable. Our retractable system is aimed more at the private client, being less obtrusive than the full size static option. The static system we offer complies with SAPCA and LTA recommendations and is the preferred choice for clubs and schools.

MORE

ASSOCIATED WORK



Along with our main concern, being the construction of tennis courts and sports surfaces. We also carry out a wide range of associated works and optional extras which include double edge perimeters, personalised fencing posts, practice walls, retaining walls, paths, patio areas, steps and landscaping to the surround of the court.

MORE

SOVEREIGN SPORTS 26 CORNWALL CRESCENT, WOULDHAM, ROCHESTER, KENT. ME1 3XR

V.A.T NO:907 052054 OFFICE: 01634 684 235

MOBILE: 07718 123 372 ; E-MAIL:



Sovereign-Sports © 2014 Privacy Policy