

LEGEND

- Existing tree planting to be retained. All trees to be protected to BS 5837:2005
- Proposed individual tree planting (Range of sizes from semi-mature to feathered dispending on location - actual sizes and numbers to be finalized during stage 2)
- Existing trees to be removed
- Proposed shrub planting (Including climbers, herbaceous/grasses and emergent planting)
- Proposed hedge planting (Including both formal and native planting)
- Proposed amenity grass areas (Including wildflower and bulb planting)
- Proposed sports pitch areas
- Proposed raised planter
- Proposed retaining wall
- Proposed pedestrian tarmac areas
- BV Proposed vehicular tarmac areas
- P Proposed porous tarmac to hard games court
- C Proposed coloured tarmac areas
- Proposed car park bay/drop off surfacing
- Proposed resin bound gravel
- Proposed feature paving
- Existing embankments
- Proposed pedestrian crossing
- Proposed ground graphics/edgings
- Proposed formal/informal seating
- Potential location for tensile structure
- Proposed 2.0m high weldmesh fence with matching pedestrian and vehicular gates
- Proposed 1.5m high weldmesh fence with matching pedestrian gate
- Proposed 3m high fence to hard games courts with matching vehicular and pedestrian gates
- Proposed 2.0m high decorative steel fence with matching pedestrian gates
- Proposed 2.4m high timber screen to bin store area, with matching gates
- Proposed 0.9mm high timber roundtop fence
- Proposed 0.9mm high steel flat top fence
- Proposed 1.1mm high steel balustrade/ guardrail
- Potential 2.0m high living willow acoustic screen
- Existing boundary treatments to be retained and repaired or repositioned where necessary
- Indicative proposed contours

Notes

1. Main vehicular access
2. Main pedestrian access
3. Carpark - 31 no. spaces
4. Carpark - 10 no. spaces
5. Main vehicular exit
6. Entrance sign
7. Potential location for sculptural/feature stone from site
8. Taxi drop-off/additional parking
9. Main entrance plaza with 5no. covered cycle racks
10. Disabled parking - 2 no. spaces
11. Location of Energy Centre
12. Service yard access
13. Soft play reinforced grass/fire tender route
14. Hard games court
15. Synthetic turf pitch
16. Willow tunnel/arbor
17. Grassed brookout area with conservation kerb
18. Outdoor dining/social breakout
19. KS1/2 breakout area/social space
20. Sensory Garden
21. Existing Well
22. Outdoor performance space/amphitheathre
23. Tensile structure/canopy
24. Habitat garden
25. KS3 breakout area
26. Service path
27. Viewing platform
28. KS4 breakout area
29. Internal courtyard - Reception/Staff
30. Internal courtyard - KS1/2
31. Internal courtyard - KS3
32. Internal courtyard - KS4
33. Natural turf sports pitch
34. 70m running track - white lining only
35. Rounders pitch - white lining only
36. Softball pitch - white lining only
37. Reinforcement planting to existing trees
38. Soft play areas
39. Bin store
40. Polytunnel
41. Parking area for Art Bus

REV.	DESCRIPTION	DATE
P12	Key Stage external learning areas and courtyards amended further to Landscape Engagement with the school on 08.12.09. Latest ground floor plan shown.	06.01.10
P13	Alterations to key and addition of notes. Levels to playing field altered and mounding acided to north and west of hard games courts. Latest courtyard details shown and acoustic fence added to north boundary.	05.03.10
P14	Alterations to road adjacent to the Energy Centre and trees repositioned accordingly. Hard games courts moved slightly to the north.	06.05.10
C15	Amendments to Masterplan due to revised Architect's layout. Revisions to mounding to west of hard games courts	09.06.10
C16	Rounders, softball and running track markings shown to grass pitch area. Gate shown to south of gabion wall for maintenance access and fence shown from Energy Centre to site boundary as requested in school meeting. Path to north east of site amended to show standard radii.	26.07.10
C17	Gabion retaining wall to south of Energy Centre omitted where existing stone faces is to be retained. Trees moved from area where bus layby is proposed.	24.08.10
C18	Steps to south west carpark amended. Key amended. Play equipment shown in Key Stage 1 /2 and Key Stage 3 areas. Contours amended. Edging to path in Sensory Garden amended. Timber steps shown to east of Sensory Garden path. White lining shown to pedestrian path in south west carpark.	09.09.10
C19	Retaining wall and access road alignment amended.	11.10.10
C20	Layby for Art Bus shown to north of Energy Centre. Potential living willow acoustic fence, with associated gates, shown around Sensory Garden in lieu of fence along north boundary.	10.12.10
C21	Path through Sensory Garden realigned to reduce impact on existing trees and additional trees as mitigation shown. Boulders from site shown within the Sensory Garden. Wall shown around existing well rather than steps. Final contours illustrated to north and west of hard games courts rather than temporary mound.	29.03.11
C22	Steps from staff carpark amended and additional tree shown to be removed.	15.09.11
C22 cont/...	Tactile paving to disabled bays and pedestrian crossings shown. Fenceline amended by the Kitchen Garden and Energy Centre. Revisions to wall around existing well and soft surfacing around trim trail equipment in Key Stage 3 area.	01.06.11
C23	Climbing plants shown to south of Energy Centre Pedestrian crossings and tactile paving amended. Ten parking bays within the site amended to be echelon and southern section of exit road revised accordingly.	18.08.11
C24	Ramps before pedestrian crossings moved a further 0.5m away from them. Hedge added to main entrance plaza as agreed with the school and BMBC. Potential to retain some of the temporary access road near service yard shown.	15.09.11

Barnsley Partnership For Learning

Design Risk Management Reference: C2W

BP4L_SPR_AWP_RA_94_BW_LL_01

awp

PROJECT: Barnsley BSF - Springwell SEN School

DRAWING TITLE: Landscape Masterplan

DRAWING No: BP4L_SPR_AWP_DR_94_BW_LL_01 C24 | SCALE (A1): 1:500 | DATE: 09-06-2010 | DRAWN: AH | CHKD: SLL

Anthony Walker and Partners Limited, 10 Summerhill Terrace, Newcastle upon Tyne, NE4 6EB
Tel: 0191 233 0186 Fax: 0191 261 1527 Email: info@awpenvironment.co.uk www.awpenvironment.co.uk

This document is copyright and must not be used, amended or reproduced in any form without written consent from Anthony Walker & Partners