

d e s i g n & a c c e s s s t a t e m e n t

Project: Barnsley NHS Hospital Foundation Trust
Proposed Canopy Extension Wards A3 & A4

Job No: 3205

The proposed works are required to provide improved shelter to wards A3 & A4 entrances as well as improving the visual way finding and adding entrance barrier matting to protect the existing floors.

15 collegiate crescent

sheffield

S10 2BA

t: 0114 266 3001

f: 0114 266 3002

e: sheffield@beaumontandcowling.co.uk

w: www.beaumontandcowling.co.uk

Entrance to A4 currently has a projecting canopy, but this does not extend to provide protection for ambulance drop off and pick up. It is proposed to extend this existing canopy full width to encompass entrances A3 & A4 whilst providing a sheltered pull in zone for ambulances.

Barnsley NHS Hospital is fully DDA Compliant and the proposed works will not affect the existing access arrangements and are intended to provide a more comfortable transfer between vehicle and Hospital. The entrance dropped kerbs will be adjusted to suit the new layout and will include new blister paving.

New external stage 1 barrier matting will provide a means for cleaning heavy soiled shoes, whilst the internal stage 2 barrier matting will remove any remaining water before entering the hospital streets. The stage 1 barrier matting is under cover of the new extended canopy, and protected from driving rain by the inclusion of new glazed screens. Both matts will meet DDA requirements.