



Electrical installation to be by member of competent person scheme & certified to BS 7671.

- Smoke alarm fitted in circulation area on each floor, interlinked & wired to power circuit with battery back up.
- Heat detector fitted in kitchen & wired to system.

40 mm Shower waste
32 mm Low bath waste
to discharge to
B.I. Gully.

New drainage in 100m pipe laid on granular bed & surround with fall 1:40 and connected to existing drain all to the satisfaction of B.C.O on site.

Existing s.e.v. adjusted to new position.

Any drain under to be
diverted to new position
and protected to satisfaction
of B.C.O. on site

to existing
S.W. soakaway

