


Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m) 	Notes	Recommendations		Vigour	Amenity Value
										Physiological Condition	Life Expectancy (yrs)
								Priority	Inspect Freq (yrs)	Structural Condition	Safety Class
T1	Early-Mature Deodar Cedar Cedrus deodara.	12	4	59	6.5 6.5 8 6		Position: Tag number: 0501. Form: Twin-stemmed at 3m with a balanced crown. History: No evidence of significant pruning. Defects: Minor bark wounds at 1m (acceptable condition at present) and significant split branch to north, overhanging driveway.	Remove split branch overhanging driveway.		Moderate	Moderate
								Very High	3	Good	40+ 2
T2	Mature Sycamore Acer pseudoplatanus.	16	6	100	11 11 10		Position: Tag number: 0502. Form: Triple-stemmed with a well-formed crown. History: Occasional pruning wounds due to crown lifting (significant cavities developing, acceptable condition at present). Defects: Significant deadwood over driveway and scattered dead twigs throughout. Other: Historic root severance adjacent driveway.	Remove deadwood and monitor.		Low	Moderate
								High	1.5	Fair	10-20 3
T3	Early-Mature Beech Fagus sylvatica.	12	2	80	8 6 7 9		Position: Tag number: 0503. Form: Multi-stemmed at 2m with a well-formed crown. History: Occasional pruning wounds due to crown lifting. Defects: Minor bark wound to underside of eastern limb, small dead branches and significant bark wound to branch overhanging road. Other: Beech bark scale presence.	Remove Beech bark scale and remedial prune.		High	Moderate
								Moderate	3	Good	40+ 2
T4	Early-Mature Hawthorn Crataegus monogyna.	5	1.5	41	2 1.5 1.5		Position: Tag number: 0504. Form: Multi-stemmed at ground level with a slightly unbalanced crown. History: Previously reduced. Defects: Major decay to base of stems and minor deadwood to upper crown. Other: Historic root severance adjacent driveway.	Closely monitor, or remove.		Moderate	Low
								Moderate	1.5	Fair	<10 3
T5	Semi-Mature Sycamore Acer pseudoplatanus.	8	2.5	4 at 25	5 5 5 6		Position: Tag number: 0508. Form: Multi-stemmed at ground level with a balanced crown. History: Occasional pruning wounds due to crown lifting. Defects: Minor included bark at base and scattered dead twigs throughout. Other: Compost heap against lower stem, prevented thorough inspection of all stems.	No action required.		Moderate	Low
								n/a	1.5	Fair	10-20 1
G6	Semi-Mature Eucalyptus Eucalyptus sp.	av 6	av 1.5	av 15	av 1 1 1 each		Position: Situated on third party land. Form: Three specimens. History: Reduced. Defects: No significant defects observed. Other: Access prevented detailed inspection.	No action required.		High	Low
								n/a	3	Good	10-20 1
G7	Early-Mature Lime Tilia sp.	av 14	av 6	av 58	av 5.5 5 3 each		Position: Tags 0511 and 0951. Form: Two vertical specimens. History: Occasional pruning wounds due to crown lifting. Defects: Significant and minor dead branches to upper crown. Covering of Ivy to one specimen. Other: Bird nests found at circa 1.5m above ground level within ivy.	Remove deadwood.		Moderate	Moderate
								Moderate	1.5	Fair	40+ 2

Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m) 25  0	Notes	Recommendations		Vigour	Amenity Value
										Physiological Condition	Life Expectancy (yrs)
								Priority	Inspect Freq (yrs)	Structural Condition	Safety Class
T8	Early-Mature Sycamore Acer pseudoplatanus.	16	6	60	5 5 8	Position: Tag 0515. Form: Twin-stemmed at 5m with an unbalanced crown. History: Occasional pruning wounds due to crown lifting. Defects: Scattered significant dead branch stubbs to upper crown and significant bark wound to branch overhanging adjacent property.	Remedial prune.	Moderate	Moderate		
	Moderate	1.5	Fair Good	20-40 2							