

PLANTING SCHEDULES

ORNAMENTAL PLANTING SCHEDULE				
Herbaceous				
Nr	Name	Ht in cm	Pot(L)	Density
49	Carex morrowii 'Evergold'	3L		12.00
64	Geranium endressii 'Wargrave Pink'	3L		6.00
Shrub				
Nr	Name	Ht in cm	Pot(L)	Density
57	Berberis thunbergii 'Atropurpurea Nana'	25-30cm	3L	6.00
48	Ceanothus thyrsiflorus 'Repens' (5-7.5L)	40-60cm(D)	5-7.5L	4.00
73	Choisya ternata (5-7.5L)	40-60cm	5-7.5L	3.00
36	Choisya ternata 'Sundance' (10L)	40-60cm	10L	2.00
16	Choisya ternata 'Sundance' (5-7.5L)	40-60cm	5-7.5L	4.00
33	Cistus lavis 'Snow White'	30-40cm	3L	5.00
55	Cistus Silver Pink	30-40cm	3L	5.00
7	Cornus alba ' Ivory Hail' (10L)	80-100cm	10L	2.00
7	Cornus alba ' Ivory Hail' (5-7.5L)	60-80cm	5-7.5L	2.00
8	Cornus sanguinea 'Mid-Winter Fire' (10L)	80-100cm	10L	3.00
12	Cornus sanguinea 'Mid-Winter Fire' (5-7.5L)	40-60cm	5-7.5L	3.00
21	Escallonia 'Apple Blossom' (10L)	60-80cm	10L	2.00
15	Escallonia 'Donard Redance' (10L)	60-80cm	10L	2.00
37	Eucalyptus fortunei 'Emerald Gaiety' (5-7.5L)	30-40cm(D)	5-7.5L	4.00
63	Eucalyptus fortunei 'Emerald n' Gold' (5-7.5L)	30-40cm(D)	5-7.5L	4.00
56	Hebe 'Oratia Beauty' (5-7.5L)	30-40cm	5-7.5L	4.00
26	Hebe 'Oratia Beauty' (5-7.5L)	25-30cm	3L	6.00
13	Hebe 'pinguifolia 'Sutherlandii' (5-7.5L)	30-40cm	5-7.5L	5.00
21	Hebe 'Red Edge' (5-7.5L)	25-30cm	3L	5.00
33	Hebe 'Red Edge' (5-7.5L)	30-40cm(D)	5-7.5L	5.00
29	Hebe 'White Gem' (5-7.5L)	40-50cm	5-7.5L	5.00
165	Lavandula angustifolia 'Hidcote' (5-7.5L)	30-40cm	5-7.5L	5.00
10	Nandina domestica 'Firepower' (5-7.5L)	40-60cm	5-7.5L	3.00
44	Philadelphus 'Manteau D'Hermine' (5-7.5L)	40-60cm	5-7.5L	3.00
33	Phodha fraseri 'Red Robin' (10L)	60-80cm	10L	2.00
23	Prunus laurocerasus 'Otto Luyken' (5-7.5L)	40-60cm	5-7.5L	2.00
47	Skimmia japonica 'Rubella' (5-7.5L)	40-60cm	5-7.5L	4.00
72	Skimmia X confusa 'Kew Green' (5-7.5L)	30-40cm	5-7.5L	4.00
31	Viburnum davidii (5-7.5L)	30-40cm	5-7.5L	4.00

All shrub material shall be first quality, sturdy, well rooted, non-refrigerated stock with well branched heads and fibrous root systems. Shrubs shall be planted into 450mm good quality fibrous topsoil incorporating organic compost and slow release fertiliser in accordance with all good horticultural practice.

All plant material shall be a minimum of 3L pot size unless otherwise specified and conform to BS3936 Part 1 and BS 4428. Finished beds shall be lightly forked over and dressed with 50mm coarse forest bark mulch.

TREE SCHEDULE

SPECIES	NUMBERS REQUIRED			
	HT in m	3.0-3.5	3.5-4.25	4.0-6.0
	Girth in cm	⊕10-12	⊕12-14	⊕14-16
Acer campestre 'Estrifk' (4AE)	2	-	-	-
Betula pendula (BP)	12	-	-	-
Carpinus betulus 'Frans Fontaine' (CBFF)	-	2	-	-
Quercus robur (Q)	-	2	-	2
Sorbus aucuparia (Ssu)	2	-	-	-
Sorbus Joseph Rock' (SJR)	1	2	-	-
Sorbus aucuparia 'Shepherdia Seedling' (SsSS)	2	-	-	-

All trees to have clear stems to 1.8m above ground level with well developed branching heads with a single, central leader and healthy, fibrous root systems.

Trees shall be planted into pits of an appropriate size to accommodate the root system without restriction backfilled with a 3:1 topsoil/compost mix and shall be secured to the ground with 4x4x1.8m steel rods and 100mm diameter bolts. The rods shall be secured to the ground with 100mm diameter bolts. A species rich grass seed mix such as Grass Seed Mix shall be applied to the tree above ground. Foundation design of new buildings shall accommodate proposed tree planting in accordance with NHC guidelines.

