



Units wrapped in geosynthetic impermeable membrane. Please contact unit manufacturer for a list of approved suppliers.

Excavations to be suitably propped or benched and graded back at safe angle.

Polystyrene Cell units or similar 95% void ratio, stacked and clipped together in accordance with manufacturers details.

## Typical Cell Unit Attenuation tank

### NOTES

All products to be installed in accordance with manufacturers recommendations and guidelines.  
Please refer to drainage design for invert levels and sizes.

Rev	Details	Date	Drawn	CHK
	<b>ABS Home Developments Ltd.</b>			
	Kings head, Kingsway Mapplewell, Barnsley			
	Cellular attenuation Typical details			
Dwg No. : STE/18/08/02				
Date : 21-9-18				
Scale : Not to scale				
Copyright © Shaun Tonge Engineering				



11 Bevanhead Road, Wetherhall, Barnsley, S73 0SA  
Tel: 01225 765920, Mobile: 07528 279370, Email: Shaun@shauntonge.co.uk