



Health and Safety Notes/CDM Regulations 2015

In line with the above regulations we are obliged to inform the Contractor of the abnormal risks that may be encountered in the construction of these works. As part of the design process all the salient health & safety aspects are given full consideration and these are observed within the designs viewed on this document. Although considerable effort is undertaken to eliminate risks, the very nature of the project gives rise to some hazards and risks.

Significant risks that cannot be eliminated by design and could not be foreseen by a competent contractor are noted in the risk assessment boxes on the drawings.

- NOTES**
- Overall discharge rate of 12.5 l/s agreed with Yorkshire Water.
 - Individual catchment splits have been agreed with Yorkshire Water.
 - Detailed technical design to follow after planning.

LEGEND

- Existing combined public sewer.
- Proposed foul water manhole and sewer.
- Proposed surface water manhole and sewer.
- Proposed geocellular attenuation crates.
- Foul water inspection chamber.
- [64.700] Proposed Finished Floor Level.

Rev	Description	By	Date

Client: **Keepmoat Homes**

Project Title: **Brunswick Street, Thurnscoe**

Drawing Title: **Drainage Strategy Layout**

Scale	Date	
1:250 @ A1	08.08.19	
Drawing No	Revision	Status
5022-C-D9-01	0	Approval

Geo Structures Civils

ID Civils Design Consulting Engineers

North East & Yorkshire:
 Aske Stables, Aske, Richmond,
 North Yorkshire, DL10 5HG
 T: 01748 889015
 F: 01565 740263

North West & Midlands:
 Caledonian House,
 Tatton Street, Knutsford,
 Cheshire, WA16 6AG
 T: 01565 755557
 F: 01565 740263