

Project

Wordsworth Crushing Vehicle Maintenance Building

Title

Drainage Strategy

Client

Wordsworth Excavations

MSJ Job No 221062

Document No

221062 GEN 0002 – Drainage Strategy

Rev P1

Date 01/12/21

Issue Record

Status	Rev	Description	By	Chk		Date
S2	P1	Initial Drainage Strategy	LW	MH		01/12/21
S2	P2	Drainage updated to suit new levels plan and drainage channels	LW	MH		22/12/21

Contents

Introduction	1
Existing Drainage Infrastructure	1
Drainage Investigations	1
Existing Drainage	1
Proposed Drainage Design	2
Foul Drainage	3
Proposed Building	3
Gantry Washes	3

Project Wordsworth Crushing Vehicle Maintenance Building	By LW	Checked MH	Job No. 221062
	Date 01-12-21	Date 01-12-21	Sheet No. / 1

Introduction

This design document is for the foul and surface water drainage for the proposed Wordsworth Crushing Vehicle Maintenance Building. It should be read in conjunction with the existing Flood Risk Assessment 221062 GEN 0001-P1 [Flood Risk Assessment], produced by Melia Smith and Jones.

Existing Drainage Infrastructure

See Existing Drainage Plans (Appendix A and B)

The existing site is a large irregular shaped piece of land. It has significant changes in level. The site falls approximately 1m from west to east and approximately 2.75m from south to north. The site has a maximum level of approximately +71.0m AOD and a minimum of approximately +66.5m AOD. The site is currently an industrial yard. There are existing buildings and car parks on parts of the site that serve the current industrial yard. An existing culverted watercourse (>50m long) passes the site approximately 300m to the north of the site. There is an abandoned canal 600m north beyond the rail lines and the River Dearne is approximately 1km north and east of the site.

There is an existing ditch on site which appears to flow North towards the railway line. The ditch does not appear to have a dedicated outfall.

There are no recorded Yorkshire Water sewers in the immediate vicinity of the site. Private foul and surface water sewers have been built in the entrance road and drainage tails have been built to accommodate the site. It is understood that these sewers connect into the adopted network further downstream and that they have been provided to service this site and adjoining plots. The surface water sewer has been built with oversized pipes and a Hydrobrake flow control device.

Foul water from the existing buildings drained to an onsite manhole which discharged to the existing Yorkshire Water sewer outside of the site. The foul system currently takes foul water from the other sites it is surrounded by, via a 150Ø pipe.

Drainage Investigations

See Drawing Drainage Investigation Results (Appendix C)

A CCTV survey of the existing off site sewer network has been carried out where possible. The network has generally been constructed in accordance with the existing drainage drawing. The current drainage is in good condition as is reusable for the proposed development.

See drawing for on-site existing drainage (Appendix B)

A site investigation was undertaken to determine the condition of the existing drainage on the site. The drainage on site consists of an existing ditch on site which appears to flow North towards the railway line. The ditch does not appear to have a dedicated outfall.

Existing Drainage

The existing surface water system discharges off site and into the Yorkshire Water network via a flow control (15l/s sec). Attenuated flow is stored in an oversized pipe located in the access road adjacent to the existing Naylor factory. The existing site access road and the existing Wordsworth office buildings currently discharge into the existing system. It is proposed to connect the new development into the existing system. See appendix A.

An analysis of the existing system has been carried out and the following results have been obtained.

Project Wordsworth Crushing Vehicle Maintenance Building	By LW	Checked MH	Job No. 221062
	Date 01-12-21	Date 01-12-21	Sheet No. / 2

- No surcharge for 1in2 year
- No flooding for 1in30 year
- 70m³ of flooding for 1in100 year of which 39m³ occurs in the existing Wordsworth office car park and 31m³ adjacent to the Naylor's Factory.

See Appendix D for further information.

The levels of the new development mean that a gravity connection is unlikely to be feasible.

Given that the existing system already floods for 100 year storms, it is considered that the existing system has no extra capacity to accept additional surface water flow without some form of mitigation.

Proposed Drainage Design

In accordance with the Approved Document H, adequate consideration has been taken to discharge via the following listed in priority.

1. Discharge via a soakaway or some other infiltration system
2. Discharge into a watercourse
3. Discharge into a sewer

Soakaway tests have not yet been carried out but the ground conditions (Shallow mudstone) suggest that they will not be viable.

There are no watercourses in the immediate locality of the site, so discharge to a watercourse is not considered viable.

It is proposed to limit run off to IH124 Greenfield runoff. The attached (See FRA) analysis shows Greenfield runoff to be:

Annual Probability (Return Period, years)	Greenfield Runoff (l/s) IH124*
Q _{BAR}	1.94
1 in 1 yr	1.67
1 in 30 yr	3.39
1 in 100 yr	4.03

These limits are very low and to limit flow to these amounts is likely to need an orifice which would be liable to blockage. It is proposed therefore to limit surface water discharge to 5l/s, with a minimum orifice of 75mm. Due to site levels it is unlikely that a gravity connection from the new surface water system will be possible. It is therefore proposed to pump surface water at a rate of 5 l/s into the existing system. Attenuated water will be stored in an underground tank upstream of the pump see appendix E, F and G. Silt traps will be used upstream of the attenuation tank.

Preliminary calculations suggest that an additional pumped flow of 5 l/s into the existing system will have a detrimental effect on the network and potential 1in100 year +40% flooding will increase adjacent to the existing Naylor factory. To compensate for this it is proposed to add an additional storage tank downstream of the new pump chamber, effectively increasing the volume of the existing storage system.

The calculations show that when the new Wordsworth development is added and additional mitigation storage, the existing Naylor's drainage system is not unacceptably affected.

In addition, the new Wordsworth development will be designed so that the system will:

- Not surcharge for 1in2 year

Project Wordsworth Crushing Vehicle Maintenance Building	By LW	Checked MH	Job No. 221062
	Date 01-12-21	Date 01-12-21	Sheet No. / 3

- Not flood for 1in30 year
- Flood for 1in100 year however the flood water will be managed so that property is not at risk on or off site.

See Appendix H for further information.

Foul Drainage

There is an existing foul water manhole and pipework on site. These drain through the existing Naylor's factory site and discharge off site into the existing public combined network. (See appendix B). It is proposed to divert the existing foul water drainage around the new gantry wash facility and re connect into the existing system. The proposed level of the existing building means that a gravity connection into the existing is unlikely to be feasible. It is proposed therefore to install a new pump chamber for the foul water for the new building which will discharge into a new manhole prior to discharge under gravity to the existing private system.

Discharge Unit Method adopted for calculation of flow within foul runs.

$k\sqrt{\sum \text{DU's}}$

k = Frequency Factor

$\sum \text{DU's}$ = Sum of Discharge Units

Frequency factor adopted = 0.7 for frequent use e.g Hospital, School, Restaurant

DU's

Toilet 1.5

Urinal 0.4

Wash Hand Basin 0.3

Kitchen Sink 1.3

Proposed Building

8 x Toilets 12 DU's

4 x Urinals 1.6 DU's

8 x Wash Hand Basin 2.4 DU's

1 x Kitchen Sink 1.3 DU's

$\sum \text{DU's} = 17.3$

$0.7\sqrt{17.3} = 2.91 \text{ l/sec}$

Flattest pipe in run is 100dia at 1:40

Capacity of 100dia at 1:40 (K = 1.5, $\frac{3}{4}$ cap) = 9 l/sec therefore OK

Gantry Washes

See appendix I for gantry wash schematic.

Two gantry washes are being built on the proposed site, the gantry washes are designed to allow under vehicle access in order for them to be cleaned. There will be an estimated 5 vehicles a day cleaned and the cleaning will be done using a handheld jet wash. The silt and oil from the vehicles and will be dealt with by firstly going into a silt trap chamber, then a silt buster, through an oil interceptor and then finally finishing in a clean water storage chamber.

Project Wordsworth Crushing Vehicle Maintenance Building	By LW	Checked MH	Job No. 221062
	Date 01-12-21	Date 01-12-21	Sheet No. / 4

We have estimated the peak discharge flow will not exceed 5 l/s, the current capacity of the existing foul water system is 9 l/s.


By adding the discharge of the gantry washes and the proposed foul drainage discharge from the proposed building together we believe that the current systems peak flow of 9 l/s is capable of taking the extra flow.

Cleaned wash water will be stored in a tank for reuse. Excess water will be allowed to drain into the onsite foul water system prior to discharging off site into the public combined system.

Appendix A

Appendix B

- Survey Requirements:**
- Manhole Cover levels, invert levels & depths
 - Pipe sizes
 - Direction of flow
 - Chamber diagrams & photos
 - Connectivity from point to point by dye tracing or CCTV surveys where possible



Appendix C

G.P. DRAIN SURVEYS

CLEANING, JETTING, RE-LINING, REPAIRS & SURVEYS

REGISTERED OFFICE:
THORNY CROFT
56 B SCATCHERD LANE
MORLEY
LEEDS
LS27 OJJ

TEL\FAX: 0113 2533154
MOBILE: 07973 834690

Our Ref : GMP/lhg/2805

Your Ref : Mark Holmes / Ben Mabbs

13th October 2021

Melia Smith & Jones Ltd
Vinery Court
58 Cardigan Lane
Leeds
LS4 2LD

For the attention of : Mark Holmes / Ben Mabbs.

C.C.T.V. DRAINAGE SURVEY.

Site at Wordsworth Crushing Barugh Green.

Manhole	Invert	Pipe Size	Material	Service
F1	790mm	4"	Plastic	Foul
F2	1090mm	4"	Plastic	Foul
F3	2250mm	4"	Plastic	Foul
	To top of biscuit			
F4	2240mm	4" & 6"	Clay	Foul
F5	Concealed	6"	Clay	Foul
F6	2250mm	6"	Clay	Foul
F7	2600mm	6"	Clay	Foul
F8	2850mm	6"	Clay	Foul
F9	2860mm	6"	Clay	Foul
S1	1460mm	6"	Clay	Surface Water
S2	1880mm	6"	Clay	Surface Water
S3	1740mm	6"	Clay	Surface Water
S4	1840mm	6" & 9"	Clay	Surface Water
S5	1710mm	6" 9" & 12"	Clay & concrete	Surface Water
S6	2340mm	6" 12" & 30"	Clay & concrete	Surface Water
	1920mm Invert of pipe from S5			
Open Ditch A		6"	Plastic	Surface Water
Open Ditch B		9"	Clay	Surface Water
M/HC	1250mm	6"	Clay	Surface Water
	To cover level – not raised concrete ring			

M/HF1 – B1

00.0 – Start scan
23.9 – Line of the drain deviates right
25.2 – Line of the drain deviates right
25.2 – Enter a soil stack – horizontal
25.2 – Blind branch 12.0'clock
28.7 – Line of the drain deviates right
29.4 – Line of the drain deviates left
35.5 – Line of the drain deviates right
35.7 – End of survey

Conclusion

This drainage run serves the yards toilet block cabins, no further action required.

M/HF1 – B2

00.0 – Start scan
67.7 – End survey at M/HF2

Conclusion

No action required.

M/HF3 – B1

00.0 – Start scan
70.4 – End survey at M/HF2

Conclusion

No action required.

M/HF3 – B2

00.0 – Start scan
48.0 – Drain increases in size from 4" plastic to 6" clay
48.6 – Line of the drain deviates right
49.1 – End survey at M/HF4

Conclusion

No action required.

M/HF4 – B1

00.0 – Start scan
51.4 – Enter concealed M/HF5 – Under a mass of concrete

Conclusion

We only surveyed this Sewer because we were unable to raise M/HF5 because it is buried under a mass of concrete and we wanted to prove that the outfall was not on a back-drop due to us being able to gain an invert of M/HF5.

M/HC – B1

00.0 – Start scan
00.4 – Survey abandoned at a mass of rubble

Conclusion

We are unsure if this drainage run is even in use, it seemed extremely dry and maybe used to serve something in the past. We would suggest that this not be used as an outfall chamber for the proposed development.

OPEN DITCH PIPE A – B1

00.0 – Start scan
 00.0 to 34.0 – Drain full of silt & mud
 33.8 – Material changes from 6” plastic to 9” clay
 34.0 – End survey at OPEN DITCH PIPE B
 34.0 – Clean camera and film in reverse
 00.0 – End survey back at OPEN DITCH PIPE A

Conclusion

We only surveyed this drainage system to prove the connectivity of the two ditches, no further action required

M/HC – B2

00.0 – Start scan
 00.0 to 14.0 – Rubble and silt within the drain
 00.5 – Material changes from clay to plastic
 14.0 – Survey abandoned at a mass of debris & silt

Conclusion

We are unsure if this drainage run is even in use, it seemed extremely dry and maybe used to serve something in the past. We would suggest that this not be used as an outfall chamber for the proposed development.

COMMENTS ON OUT FINDINGS.

We were instructed to attend site to carry out a connectivity survey on the open ditches and to gain inverts of existing foul and surface water chambers around the proposed development.


We have proved that the two ditches (A) & (B) are connected together with an underground drainage system although this is only 6” in diameter. We were unable to prove any positive connection marked (D) on the drawing where the open ditches actually discharge. It appears that any water just soaks away to ground at that point and also the whole length of the ditch.

We were asked to check if there was a connection coming into the open ditch marked (E) on the drawing. There is no sign of any drainage system entering the ditch at that position. Please note that there is a large hard standing area where there were a load of wagon trailers parked up and it looks as though this area just allows the surface water to fall into the open ditch at position (E).

Please see drawing for reference.

END OF SURVEY.

Appendix D

Melia Smith and Jones		Page 1
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	30	PIMP (%)	100
M5-60 (mm)	19.000	Add Flow / Climate Change (%)	0
Ratio R	0.352	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm



Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.027	4-8	0.376	8-12	0.099

Total Area Contributing (ha) = 0.501

Total Pipe Volume (m³) = 52.722


Network Design Table for Storm

- Indicates pipe length does not match coordinates
« - Indicates pipe capacity < flow
















PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	28.000	0.186	150.5	0.017	5.00	0.0	0.600	o	150	Pipe/Conduit	
S2.000	26.000	0.186	139.8	0.017	5.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	50.00	5.57	71.300	0.017	0.0	0.0	0.0	0.82	14.4	2.3
S2.000	50.00	5.51	71.300	0.017	0.0	0.0	0.0	0.85	15.0	2.3


Melia Smith and Jones		Page 2
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Network Design Table for Storm


PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.001	18.000	0.170	105.9	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S3.000	28.000	0.306	91.5	0.017	5.00	0.0	0.600	o	150	Pipe/Conduit	
S4.000	26.000	0.306	85.0	0.017	5.00	0.0	0.600	o	150	Pipe/Conduit	
S1.002	9.000	0.204	44.1	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S5.000	16.000#	0.230	69.6	0.041	5.00	0.0	0.600	o	150	Pipe/Conduit	
S5.001	5.000	0.150	33.3	0.140	0.00	0.0	0.600	o	225	Pipe/Conduit	
S1.003	8.000	0.100	80.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
S1.004	32.000	0.321	99.7	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S6.000	60.023	0.960	62.5	0.037	5.00	0.0	0.600	o	150	Pipe/Conduit	
S1.005	34.904	1.039	33.6	0.035	0.00	0.0	0.600	o	150	Pipe/Conduit	
S1.006	34.659	1.044	33.2	0.039	0.00	0.0	0.600	o	225	Pipe/Conduit	
S1.007	27.792	0.190	146.3	0.040	0.00	0.0	0.600	o	225	Pipe/Conduit	
S1.008	18.645	0.107	174.3	0.084	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.009	85.160	0.568	149.9	0.017	0.00	0.0	0.600	o	750	Pipe/Conduit	
S1.010	97.602	0.651	149.9	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.001	50.00	5.88	71.114	0.034	0.0	0.0	0.0	0.98	17.3	4.6
S3.000	50.00	5.44	71.250	0.017	0.0	0.0	0.0	1.05	18.6	2.3
S4.000	50.00	5.40	71.250	0.017	0.0	0.0	0.0	1.09	19.3	2.3
S1.002	50.00	5.98	70.944	0.068	0.0	0.0	0.0	1.52	26.8	9.2
S5.000	50.00	5.22	71.120	0.041	0.0	0.0	0.0	1.21	21.3	5.6
S5.001	50.00	5.26	70.890	0.181	0.0	0.0	0.0	2.27	90.4	24.5
S1.003	50.00	6.07	70.570	0.249	0.0	0.0	0.0	1.46	58.2	33.7
S1.004	50.00	6.60	70.470	0.249	0.0	0.0	0.0	1.01	17.8<	33.7
S6.000	50.00	5.79	71.020	0.037	0.0	0.0	0.0	1.27	22.5	5.0
S1.005	50.00	6.93	70.060	0.321	0.0	0.0	0.0	1.74	30.8<	43.5
S1.006	50.00	7.19	68.945	0.360	0.0	0.0	0.0	2.28	90.6	48.7
S1.007	50.00	7.62	67.901	0.400	0.0	0.0	0.0	1.08	42.9<	54.2
S1.008	50.00	7.88	67.636	0.484	0.0	0.0	0.0	1.19	84.0	65.5
S1.009	50.00	8.50	67.079	0.501	0.0	0.0	0.0	2.28	1008.7	67.8
S1.010	50.00	10.03	66.511	0.501	0.0	0.0	0.0	1.07	42.4<	67.8

Melia Smith and Jones		Page 3
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.011	50.042	0.334	149.8	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	

Network Results Table


PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.011	50.00	10.81	65.860	0.501	0.0	0.0	0.0	1.07	42.4«	67.8

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	0.000
Hot Start (mins)	0	Inlet Coefficient	1.000
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	1
Number of Online Controls	2	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.000	Storm Duration (mins)	30
Ratio R	0.400		

Melia Smith and Jones		Page 4
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Online Controls for Storm

Hydro-Brake® Optimum Manhole: SW Ex 10, DS/PN: S1.004, Volume (m³): 1.7

```

Unit Reference MD-SHE-0098-5000-1500-5000
Design Head (m) 1.500
Design Flow (l/s) 5.0
  Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 98
Invert Level (m) 70.470
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

```

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.500	5.0
Flush-Flo™	0.431	4.9
Kick-Flo®	0.878	3.9
Mean Flow over Head Range	-	4.3

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated


Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.2	1.200	4.5	3.000	6.9	7.000	10.3
0.200	4.4	1.400	4.8	3.500	7.4	7.500	10.7
0.300	4.8	1.600	5.1	4.000	7.9	8.000	11.0
0.400	4.9	1.800	5.4	4.500	8.4	8.500	11.3
0.500	4.9	2.000	5.7	5.000	8.8	9.000	11.6
0.600	4.8	2.200	6.0	5.500	9.2	9.500	11.9
0.800	4.3	2.400	6.2	6.000	9.6		
1.000	4.1	2.600	6.5	6.500	10.0		

Hydro-Brake® Optimum Manhole: SW Ex 17, DS/PN: S1.010, Volume (m³): 45.7

```

Unit Reference MD-SHE-0146-1500-3000-1500
Design Head (m) 3.000
Design Flow (l/s) 15.0
  Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 146
Invert Level (m) 66.511
Minimum Outlet Pipe Diameter (mm) 225
Suggested Manhole Diameter (mm) 1500

```


Melia Smith and Jones		Page 5
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Hydro-Brake® Optimum Manhole: SW Ex 17, DS/PN: S1.010, Volume (m³): 45.7

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	3.000	15.0
Flush-Flo™	0.636	12.9
Kick-Flo®	1.307	10.1
Mean Flow over Head Range	-	12.0

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	5.3	1.200	11.1	3.000	15.0	7.000	22.5
0.200	10.4	1.400	10.4	3.500	16.1	7.500	23.2
0.300	11.7	1.600	11.1	4.000	17.2	8.000	24.0
0.400	12.4	1.800	11.8	4.500	18.2	8.500	24.7
0.500	12.7	2.000	12.4	5.000	19.1	9.000	25.4
0.600	12.8	2.200	12.9	5.500	20.0	9.500	26.0
0.800	12.7	2.400	13.5	6.000	20.9		
1.000	12.2	2.600	14.0	6.500	21.7		


Melia Smith and Jones		Page 6
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Storage Structures for Storm

Cellular Storage Manhole: SW Ex 10, DS/PN: S1.004

Invert Level (m) 70.475 Safety Factor 2.0
 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
 Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	180.0	0.0	0.300	180.0	0.0
0.100	180.0	0.0	0.400	180.0	0.0
0.200	180.0	0.0	0.401	0.0	0.0

Melia Smith and Jones		Page 7
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000
Hot Start Level (mm) 0 Inlet Coefficient 1.000
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
Number of Online Controls 2 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0


Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.400
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status ON
DVD Status OFF
Inertia Status OFF

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440, 2160, 2880, 4320, 5760,
7200, 8640, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow
S1.000	SW Ex 2	15 Winter	2	+0%	100/15 Summer	100/15 Winter	
S2.000	SW Ex 1	15 Winter	2	+0%	100/15 Summer		
S1.001	SW Ex 3	15 Winter	2	+0%	100/15 Summer		
S3.000	SW Ex 5	15 Winter	2	+0%	100/15 Summer		
S4.000	SW Ex 4	15 Winter	2	+0%	100/15 Summer		
S1.002	SW Ex 6	15 Winter	2	+0%	30/15 Summer		
S5.000	SW Ex 7	15 Winter	2	+0%	100/15 Summer		
S5.001	SW Ex 8	15 Winter	2	+0%	30/15 Summer		
S1.003	SW Ex Tank	15 Winter	2	+0%	30/15 Summer	100/30 Winter	
S1.004	SW Ex 10	120 Winter	2	+0%	2/60 Winter	100/30 Winter	
S6.000	SW Ex 11	15 Winter	2	+0%	100/15 Summer		
S1.005	SW Ex 12	15 Winter	2	+0%	100/15 Summer		
S1.006	SW Ex 13	15 Winter	2	+0%	100/15 Summer		
S1.007	SW Ex 14	15 Winter	2	+0%	30/15 Summer		
S1.008	SW Ex 15	15 Winter	2	+0%	30/15 Summer	100/15 Winter	
S1.009	SW Ex 16	15 Winter	2	+0%	100/15 Summer	100/15 Winter	
S1.010	SW Ex 17	30 Winter	2	+0%	2/15 Summer		

Melia Smith and Jones		Page 8
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Cap. (l/s)	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)
S1.000	SW Ex 2		71.348	-0.102	0.000	0.22			3.0
S2.000	SW Ex 1		71.347	-0.103	0.000	0.21			3.0
S1.001	SW Ex 3		71.177	-0.087	0.000	0.37			6.0
S3.000	SW Ex 5		71.292	-0.108	0.000	0.17			3.0
S4.000	SW Ex 4		71.291	-0.109	0.000	0.16			3.0
S1.002	SW Ex 6		71.019	-0.075	0.000	0.51			11.9
S5.000	SW Ex 7		71.184	-0.086	0.000	0.37			7.4
S5.001	SW Ex 8		70.995	-0.120	0.000	0.44			28.6
S1.003	SW Ex Tank		70.733	-0.062	0.000	0.87			40.5
S1.004	SW Ex 10		70.629	0.009	0.000	0.24		84	4.2
S6.000	SW Ex 11		71.077	-0.093	0.000	0.29			6.5
S1.005	SW Ex 12		70.130	-0.080	0.000	0.43			12.9
S1.006	SW Ex 13		69.016	-0.154	0.000	0.22			18.6
S1.007	SW Ex 14		68.029	-0.097	0.000	0.61			24.2
S1.008	SW Ex 15		67.788	-0.148	0.000	0.50			36.2
S1.009	SW Ex 16		67.179	-0.650	0.000	0.04			38.5
S1.010	SW Ex 17		67.053	0.317	0.000	0.30			12.6


PN	US/MH Name	Status	Level Exceeded
S1.000	SW Ex 2	OK	1
S2.000	SW Ex 1	OK	
S1.001	SW Ex 3	OK	
S3.000	SW Ex 5	OK	
S4.000	SW Ex 4	OK	
S1.002	SW Ex 6	OK	
S5.000	SW Ex 7	OK	
S5.001	SW Ex 8	OK	
S1.003	SW Ex Tank	OK	17
S1.004	SW Ex 10	SURCHARGED	17
S6.000	SW Ex 11	OK	
S1.005	SW Ex 12	OK	
S1.006	SW Ex 13	OK	
S1.007	SW Ex 14	OK	
S1.008	SW Ex 15	OK	13
S1.009	SW Ex 16	OK	13
S1.010	SW Ex 17	SURCHARGED	

Melia Smith and Jones		Page 9
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.011	SW Ex 18	60 Summer	2	+0%					65.946

PN	US/MH Name	Surcharged		Flooded		Half Drain		Pipe		Level Exceeded
		Depth (m)	Volume (m ³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Status		
S1.011	SW Ex 18	-0.139	0.000	0.31				12.6	OK	

Melia Smith and Jones		Page 10
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000
Hot Start Level (mm) 0 Inlet Coefficient 1.000
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
Number of Online Controls 2 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.400
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status ON
DVD Status OFF
Inertia Status OFF


Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440, 2160, 2880, 4320, 5760,
7200, 8640, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow
S1.000	SW Ex 2	15 Winter	30	+0%	100/15 Summer	100/15 Winter	
S2.000	SW Ex 1	15 Winter	30	+0%	100/15 Summer		
S1.001	SW Ex 3	15 Winter	30	+0%	100/15 Summer		
S3.000	SW Ex 5	15 Winter	30	+0%	100/15 Summer		
S4.000	SW Ex 4	15 Winter	30	+0%	100/15 Summer		
S1.002	SW Ex 6	15 Winter	30	+0%	30/15 Summer		
S5.000	SW Ex 7	15 Winter	30	+0%	100/15 Summer		
S5.001	SW Ex 8	15 Winter	30	+0%	30/15 Summer		
S1.003	SW Ex Tank	15 Winter	30	+0%	30/15 Summer	100/30 Winter	
S1.004	SW Ex 10	120 Winter	30	+0%	2/60 Winter	100/30 Winter	
S6.000	SW Ex 11	15 Winter	30	+0%	100/15 Summer		
S1.005	SW Ex 12	15 Winter	30	+0%	100/15 Summer		
S1.006	SW Ex 13	15 Winter	30	+0%	100/15 Summer		
S1.007	SW Ex 14	15 Winter	30	+0%	30/15 Summer		
S1.008	SW Ex 15	15 Winter	30	+0%	30/15 Summer	100/15 Winter	
S1.009	SW Ex 16	60 Winter	30	+0%	100/15 Summer	100/15 Winter	
S1.010	SW Ex 17	60 Winter	30	+0%	2/15 Summer		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap. (l/s)	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)
S1.000	SW Ex 2		71.368	-0.082	0.000	0.41			5.7
S2.000	SW Ex 1		71.367	-0.083	0.000	0.40			5.7
S1.001	SW Ex 3		71.215	-0.049	0.000	0.69			11.1
S3.000	SW Ex 5		71.309	-0.091	0.000	0.32			5.7
S4.000	SW Ex 4		71.308	-0.092	0.000	0.31			5.7
S1.002	SW Ex 6		71.141	0.047	0.000	1.03			24.3
S5.000	SW Ex 7		71.239	-0.031	0.000	0.71			14.1
S5.001	SW Ex 8		71.129	0.014	0.000	0.96			63.4
S1.003	SW Ex Tank		70.988	0.193	0.000	1.73			80.7
S1.004	SW Ex 10		70.796	0.176	0.000	0.28		115	4.8
S6.000	SW Ex 11		71.102	-0.068	0.000	0.56			12.3
S1.005	SW Ex 12		70.175	-0.035	0.000	0.91			27.1
S1.006	SW Ex 13		69.056	-0.114	0.000	0.47			40.1
S1.007	SW Ex 14		68.287	0.161	0.000	1.32			52.8
S1.008	SW Ex 15		67.946	0.010	0.000	1.09			79.4
S1.009	SW Ex 16		67.628	-0.201	0.000	0.05			47.8
S1.010	SW Ex 17		67.626	0.890	0.000	0.30			12.4


PN	US/MH Name	Status	Level Exceeded
S1.000	SW Ex 2	OK	1
S2.000	SW Ex 1	OK	
S1.001	SW Ex 3	OK	
S3.000	SW Ex 5	OK	
S4.000	SW Ex 4	OK	
S1.002	SW Ex 6	SURCHARGED	
S5.000	SW Ex 7	OK	
S5.001	SW Ex 8	SURCHARGED	
S1.003	SW Ex Tank	SURCHARGED	17
S1.004	SW Ex 10	SURCHARGED	17
S6.000	SW Ex 11	OK	
S1.005	SW Ex 12	OK	
S1.006	SW Ex 13	OK	
S1.007	SW Ex 14	SURCHARGED	
S1.008	SW Ex 15	SURCHARGED	13
S1.009	SW Ex 16	OK	13
S1.010	SW Ex 17	SURCHARGED	

Melia Smith and Jones		Page 12
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.011	SW Ex 18	480 Summer	30	+0%					65.946

PN	US/MH Name	Surcharged Flooded		Half Drain Pipe			Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap. (l/s)	Overflow (l/s)	Time (mins)		
S1.011	SW Ex 18	-0.139	0.000	0.31			12.6	OK

Melia Smith and Jones		Page 13
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000
Hot Start Level (mm) 0 Inlet Coefficient 1.000
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
Number of Online Controls 2 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.400
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status ON
DVD Status OFF
Inertia Status OFF

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440, 2160, 2880, 4320, 5760,
7200, 8640, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow
S1.000	SW Ex 2	15 Winter	100	+40%	100/15 Summer	100/15 Winter	
S2.000	SW Ex 1	15 Winter	100	+40%	100/15 Summer		
S1.001	SW Ex 3	60 Winter	100	+40%	100/15 Summer		
S3.000	SW Ex 5	60 Winter	100	+40%	100/15 Summer		
S4.000	SW Ex 4	60 Winter	100	+40%	100/15 Summer		
S1.002	SW Ex 6	60 Winter	100	+40%	30/15 Summer		
S5.000	SW Ex 7	15 Winter	100	+40%	100/15 Summer		
S5.001	SW Ex 8	60 Winter	100	+40%	30/15 Summer		
S1.003	SW Ex Tank	180 Winter	100	+40%	30/15 Summer	100/30 Winter	
S1.004	SW Ex 10	180 Winter	100	+40%	2/60 Winter	100/30 Winter	
S6.000	SW Ex 11	15 Winter	100	+40%	100/15 Summer		
S1.005	SW Ex 12	15 Winter	100	+40%	100/15 Summer		
S1.006	SW Ex 13	30 Winter	100	+40%	100/15 Summer		
S1.007	SW Ex 14	30 Winter	100	+40%	30/15 Summer		

Melia Smith and Jones		Page 14
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap. (l/s)	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)
S1.000	SW Ex 2		71.850	0.400	0.002	0.62			8.5
S2.000	SW Ex 1		71.848	0.398	0.000	0.60			8.6
S1.001	SW Ex 3		71.831	0.567	0.000	0.65			10.5
S3.000	SW Ex 5		71.821	0.421	0.000	0.31			5.5
S4.000	SW Ex 4		71.821	0.421	0.000	0.30			5.5
S1.002	SW Ex 6		71.805	0.711	0.000	0.79			18.8
S5.000	SW Ex 7		71.922	0.652	0.000	1.40			27.7
S5.001	SW Ex 8		71.811	0.696	0.000	0.87			57.2
S1.003	SW Ex Tank		71.773	0.978	22.651	0.78			36.3
S1.004	SW Ex 10		71.767	1.147	16.788	0.28			4.8
S6.000	SW Ex 11		71.550	0.380	0.000	0.88			19.4
S1.005	SW Ex 12		70.795	0.585	0.000	1.19			35.5
S1.006	SW Ex 13		69.842	0.672	0.000	0.61			52.0
S1.007	SW Ex 14		69.666	1.540	0.000	1.77			70.5

PN	US/MH Name	Status	Level Exceeded
S1.000	SW Ex 2	FLOOD	1
S2.000	SW Ex 1	FLOOD RISK	
S1.001	SW Ex 3	FLOOD RISK	
S3.000	SW Ex 5	FLOOD RISK	
S4.000	SW Ex 4	FLOOD RISK	
S1.002	SW Ex 6	FLOOD RISK	
S5.000	SW Ex 7	FLOOD RISK	
S5.001	SW Ex 8	FLOOD RISK	
S1.003	SW Ex Tank	FLOOD	17
S1.004	SW Ex 10	FLOOD	17
S6.000	SW Ex 11	SURCHARGED	
S1.005	SW Ex 12	SURCHARGED	
S1.006	SW Ex 13	SURCHARGED	
S1.007	SW Ex 14	FLOOD RISK	

Melia Smith and Jones		Page 15
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Existing Calculations	
Date 26/11/2021 09:20 File 221062 - Existing Drain...	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.008	SW Ex 15	60	Winter	100	+40%	30/15 Summer	100/15 Winter	
S1.009	SW Ex 16	60	Summer	100	+40%	100/15 Summer	100/15 Winter	
S1.010	SW Ex 17	30	Winter	100	+40%	2/15 Summer		
S1.011	SW Ex 18	60	Winter	100	+40%			

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
S1.008	SW Ex 15	69.448	1.512	28.538	1.09		78.9	FLOOD
S1.009	SW Ex 16	69.451	1.622	1.148	0.10		94.5	FLOOD
S1.010	SW Ex 17	69.508	2.772	0.000	0.36		14.8	SURCHARGED
S1.011	SW Ex 18	65.954	-0.131	0.000	0.36		14.8	OK

PN	US/MH Name	Level Exceeded
S1.008	SW Ex 15	13
S1.009	SW Ex 16	13
S1.010	SW Ex 17	
S1.011	SW Ex 18	


Appendix E

Appendix F



1 External Works
1 : 500

Note:
All contours within red line boundary are proposed. All outside the red line boundary are existing.



2 External Works with Drainage
1 : 500

KEY

Surface Water Rising Main	- - - - -
Surface Water Drainage	- - - - -
Foul Water Drainage	- - - - -
Existing Surface Water Drainage	- - - - -
Existing Foul Water Drainage	- - - - -
Gully	□ - - - - -
Concrete channel	- - - - -
Sewer to be Abandoned	-X-X-X-X-X-X-X-X-
Grass verge	■

P1 Initial Issue	LW	MH	22.12.21
Rev	Revision Description	By	Chk
SCALE @ A1	ISSUING OFFICE	MSJ PROJECT NUMBER	
1 : 500	Leeds	221062	

STATUS	PURPOSE OF ISSUE
S0	WORK IN PROGRESS

	Melia Smith & Jones
	Consulting Civil & Structural Engineers Vinery Court 58 Cardigan Lane Leeds LS4 2LD 0113 2306680 www.msj.co.uk

PROJECT
**Wordsworth Properties Ltd.
Vehicle Maintenance Building**

TITLE
External Works and Proposed Drainage

CLIENT
Martin Walsh Architectural

DRAWING NUMBER	REV
221062-MSJ-XX-XX-DR-D-3000	P1

Appendix G

Drainage Notes

- Underground drains for foul and surface water drainage shall be as follows:-
Twin wall plastic to BS 13476
- Manhole covers to be as follows:-
D400 in parking areas
A15 in non-parking areas
- Rainwater and foul outlet positions to be confirmed by Architect.
- Drains passing through manhole walls to be built in. A flexible joint shall be provided within 150mm of the face of the wall with a further flexible joint within 600mm of the first joint.
- All gullies, rest bends, drainage channels, rodding eyes and attachments are to be installed strictly in accordance with the manufacturers printed instructions.
- The drainage shall be installed and tested strictly in accordance with the manufacturers printed instructions, BS 8000, BS 6301 and Local Authority byelaws.
- All existing manhole positions, invert levels & pipe sizes are to be confirmed on site by the contractor prior to commencement of work site and be reported to MSJ.
- All in-situ concrete to comply with BS 8500.
- All precast concrete items to comply with BS 5911.
- Sulphate resisting cement (C20-DC2) and pre-cast concrete products must be used or a laboratory report provided proving that such measures are not necessary.
- All private drainage works to comply with Approved Document 'H' of the Building Regulations.
- All gullies and rainwater outlets are to be trapped.


CDM Regulations - Drainage

- All design work has been carried out with health & safety aspects given full consideration. Wherever possible risks have been eliminated from the design, however due to the nature of this type of work it is not possible to remove all risk.

The contractor shall provide satisfactory responses via suitable method statements as to the manner in which they propose to carry out the work and deal with any highlighted risk, in particular the following :-

- All trench excavations, regardless of depth.
- Guarding to edges of excavations to prevent injury.
- Guarding of the works outside normal working hours.
- Undermining of adjacent roads or structures.
- Confined spaces operations.
- Dealing with existing services.
- Traffic management on existing highways.
- Procedures to be followed in the event of an emergency.
- Methods of working where ground contamination may be present.
- Dealing with existing sewer flows.

The above list is by no means exhaustive, but does highlight operations that present a risk to both contractors and the general public.



KEY

- PN7.000 - 550m²
- PN7.001 - 1540m²
- PN7.002 - 1650m²
- PN7.002 - 1650m²
- PN8.000 - 2680m²
- PN9.000 - 240m²
- PN9.001 - 1510m²
- PN7.005 - 220m²
- PN7.006 - 1200m²

2 Impermeable Area
1 : 500

P2	Impermeable areas updated to suit proposed channel drains	LW	MH	22.12.21
P1	Initial Issue	By	Chk	01.12.21
Rev	Revision Description	By	Chk	Date

SCALE @ A1	ISSUING OFFICE	MSJ PROJECT NUMBER
1 : 500	Leeds	221062

STATUS	PURPOSE OF ISSUE
SO	WORK IN PROGRESS


	Melia Smith & Jones Consulting Civil & Structural Engineers Vinery Court 58 Cardigan Lane Leeds LS4 2LD 0113 236699 www.msj.co.uk
	PROJECT Wordsworth Properties Ltd. Vehicle Maintenance Building

TITLE	Impermeable Area Plan
-------	------------------------------

CLIENT	Martin Walsh Architectural
--------	-----------------------------------

DRAWING NUMBER	221062-MSJ-ZZ-XX-DR-D-4001	REV	P2
----------------	----------------------------	-----	----

Appendix H

Melia Smith and Jones		Page 1
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	100	PIMP (%)	100
M5-60 (mm)	19.000	Add Flow / Climate Change (%)	0
Ratio R	0.352	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	500	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm



Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.026	8-12	0.104	16-20	0.000	24-28	0.196	32-36	0.030
4-8	0.371	12-16	0.000	20-24	0.000	28-32	0.898		

Total Area Contributing (ha) = 1.625

Total Pipe Volume (m³) = 87.065


Network Design Table for Storm

- Indicates pipe length does not match coordinates
« - Indicates pipe capacity < flow















PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section	Type	Auto Design
S1.000	26.000	0.186	139.8	0.017	5.00	0.0	0.600	o	150	Pipe/Conduit		
S2.000	28.000	0.186	150.5	0.017	5.00	0.0	0.600	o	150	Pipe/Conduit		

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	139.22	5.51	71.300	0.017	0.0	0.0	0.0	0.85	15.0	6.4
S2.000	138.67	5.57	71.300	0.017	0.0	0.0	0.0	0.82	14.4	6.4


Melia Smith and Jones		Page 2
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Network Design Table for Storm


















PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.001	18.000	0.170	105.9	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S3.000	28.000	0.306	91.5	0.017	5.00	0.0	0.600	o	150	Pipe/Conduit	
S4.000	26.000	0.306	85.0	0.017	5.00	0.0	0.600	o	150	Pipe/Conduit	
S1.002	9.000	0.204	44.1	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S5.000	16.000	0.230	69.6	0.041	5.00	0.0	0.600	o	150	Pipe/Conduit	
S5.001	5.000	0.150	33.3	0.140	0.00	0.0	0.600	o	225	Pipe/Conduit	
S1.003	8.000	0.100	80.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
S1.004	32.000	0.321	99.7	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S6.000	60.023	0.960	62.5	0.037	5.00	0.0	0.600	o	150	Pipe/Conduit	
S1.005	34.904	1.039	33.6	0.035	0.00	0.0	0.600	o	150	Pipe/Conduit	
S1.006	34.659	1.044	33.2	0.039	0.00	0.0	0.600	o	150	Pipe/Conduit	
S7.000	20.963	0.319	65.7	0.055	5.00	0.0	0.600	o	150	Pipe/Conduit	
S7.001	24.490#	0.545	44.9	0.154	0.00	0.0	0.600	o	225	Pipe/Conduit	
S7.002	31.980	0.320	99.9	0.330	0.00	0.0	0.600	o	375	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.001	135.93	5.88	71.114	0.034	0.0	0.0	0.0	0.98	17.3	12.5
S3.000	139.85	5.44	71.250	0.017	0.0	0.0	0.0	1.05	18.6	6.4
S4.000	140.29	5.40	71.250	0.017	0.0	0.0	0.0	1.09	19.3	6.5
S1.002	135.08	5.98	70.944	0.068	0.0	0.0	0.0	1.52	26.8	24.9
S5.000	141.98	5.22	71.120	0.041	0.0	0.0	0.0	1.21	21.3	15.8
S5.001	141.62	5.26	70.890	0.181	0.0	0.0	0.0	2.27	90.4	69.4
S1.003	134.30	6.07	70.570	0.249	0.0	0.0	0.0	1.46	58.2«	90.6
S1.004	130.02	6.60	70.470	0.249	0.0	0.0	0.0	1.01	17.8«	90.6
S6.000	136.75	5.79	71.020	0.037	0.0	0.0	0.0	1.27	22.5	13.7
S1.005	127.51	6.93	70.060	0.321	0.0	0.0	0.0	1.74	30.8«	110.8
S1.006	125.14	7.26	68.945	0.360	0.0	0.0	0.0	1.75	31.0«	122.0
S7.000	141.39	5.28	67.335	0.055	0.0	0.0	0.0	1.24	22.0	21.1
S7.001	139.42	5.49	66.941	0.209	0.0	0.0	0.0	1.96	77.8«	78.9
S7.002	136.76	5.78	66.246	0.539	0.0	0.0	0.0	1.81	200.2	199.6


Melia Smith and Jones		Page 3
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section	Type	Auto Design
S7.003	31.013	0.467	66.4	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit		
S8.000	42.800	0.350	122.3	0.268	5.00	0.0	0.600	o	300	Pipe/Conduit		
S7.004	39.158	0.320	122.4	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit		
S9.000	27.450	0.250	109.8	0.024	5.00	0.0	0.600	o	150	Pipe/Conduit		
S9.001	51.132	0.274	186.6	0.151	0.00	0.0	0.600	o	300	Pipe/Conduit		
S7.005	10.594	0.150	70.6	0.022	0.00	0.0	0.600	o	450	Pipe/Conduit		
S7.006	17.482#	0.300	58.3	0.120	0.00	0.0	0.600	o	450	Pipe/Conduit		
S7.007	10.589#	0.200	52.9	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit		
S7.008	164.700	-5.097	-32.3	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit		
S7.009	3.150	0.023	137.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit		
S7.010	2.200	0.016	137.5	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit		
S7.011	13.657	0.220	62.1	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit		
S1.007	27.792	0.190	146.3	0.040	0.00	0.0	0.600	o	225	Pipe/Conduit		
S1.008	18.645	0.107	174.3	0.084	0.00	0.0	0.600	o	300	Pipe/Conduit		
S1.009	85.160	0.568	149.9	0.017	0.00	0.0	0.600	o	750	Pipe/Conduit		
S1.010	97.602	0.651	149.9	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit		
S1.011	50.042	0.334	149.8	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit		

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S7.003	134.75	6.02	65.926	0.539	0.0	0.0	0.0	2.23	245.9	199.6
S8.000	139.31	5.50	65.809	0.268	0.0	0.0	0.0	1.42	100.4<	101.1
S7.004	131.81	6.37	65.384	0.807	0.0	0.0	0.0	1.84	292.1	288.1
S9.000	139.54	5.48	65.888	0.024	0.0	0.0	0.0	0.96	16.9	9.1
S9.001	133.04	6.22	65.488	0.175	0.0	0.0	0.0	1.15	81.1	63.1
S7.005	131.23	6.44	65.064	1.004	0.0	0.0	0.0	2.42	385.2	356.8
S7.006	130.37	6.55	64.914	1.124	0.0	0.0	0.0	2.67	424.2	396.9
S7.007	129.89	6.62	63.464	1.124	0.0	0.0	0.0	2.80	445.2	396.9
S7.008	61.16	29.00	63.264	1.124	0.0	0.0	0.0	0.12	4.9<	396.9
S7.009	61.10	29.05	68.361	1.124	0.0	0.0	0.0	1.12	44.3<	396.9
S7.010	61.06	29.08	68.136	1.124	0.0	0.0	0.0	1.11	44.3<	396.9
S7.011	60.88	29.22	68.120	1.124	0.0	0.0	0.0	1.66	66.1<	396.9
S1.007	60.34	29.65	67.901	1.524	0.0	0.0	0.0	1.08	42.9<	396.9
S1.008	60.02	29.91	67.636	1.608	0.0	0.0	0.0	1.19	84.0<	396.9
S1.009	59.91	30.00	67.079	1.625	0.0	0.0	0.0	2.28	1008.7	396.9
S1.010	59.91	30.00	66.511	1.625	0.0	0.0	0.0	1.07	42.4<	396.9
S1.011	59.91	30.00	65.860	1.625	0.0	0.0	0.0	1.07	42.4<	396.9

Melia Smith and Jones		Page 4
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	


Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	0.000
Hot Start (mins)	0	Inlet Coefficient	1.000
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs	0	Number of Storage Structures	3
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.000	Storm Duration (mins)	30
Ratio R	0.400		

Melia Smith and Jones		Page 5
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Online Controls for Storm

Hydro-Brake® Optimum Manhole: SW Ex 10, DS/PN: S1.004, Volume (m³): 1.7

Unit Reference MD-SHE-0098-5000-1500-5000
Design Head (m) 1.500
Design Flow (l/s) 5.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 98
Invert Level (m) 70.470
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.500	5.0
Flush-Flo™	0.431	4.9
Kick-Flo®	0.878	3.9
Mean Flow over Head Range	-	4.3


The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.2	1.200	4.5	3.000	6.9	7.000	10.3
0.200	4.4	1.400	4.8	3.500	7.4	7.500	10.7
0.300	4.8	1.600	5.1	4.000	7.9	8.000	11.0
0.400	4.9	1.800	5.4	4.500	8.4	8.500	11.3
0.500	4.9	2.000	5.7	5.000	8.8	9.000	11.6
0.600	4.8	2.200	6.0	5.500	9.2	9.500	11.9
0.800	4.3	2.400	6.2	6.000	9.6		
1.000	4.1	2.600	6.5	6.500	10.0		

Pump Manhole: SW 4, DS/PN: S7.008, Volume (m³): 6.9

Invert Level (m) 63.264

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	5.0000	0.900	5.0000	1.700	5.0000	2.500	5.0000
0.200	5.0000	1.000	5.0000	1.800	5.0000	2.600	5.0000
0.300	5.0000	1.100	5.0000	1.900	5.0000	2.700	5.0000
0.400	5.0000	1.200	5.0000	2.000	5.0000	2.800	5.0000
0.500	5.0000	1.300	5.0000	2.100	5.0000	2.900	5.0000
0.600	5.0000	1.400	5.0000	2.200	5.0000	3.000	5.0000
0.700	5.0000	1.500	5.0000	2.300	5.0000		
0.800	5.0000	1.600	5.0000	2.400	5.0000		

Melia Smith and Jones		Page 6
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

Hydro-Brake® Optimum Manhole: SW Ex 17, DS/PN: S1.010, Volume (m³): 44.4

Unit Reference	MD-SHE-0146-1500-3000-1500
Design Head (m)	3.000
Design Flow (l/s)	15.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	146
Invert Level (m)	66.511
Minimum Outlet Pipe Diameter (mm)	225
Suggested Manhole Diameter (mm)	1500

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	3.000	15.0
Flush-Flo™	0.636	12.9
Kick-Flo®	1.307	10.1
Mean Flow over Head Range	-	12.0

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	5.3	1.200	11.1	3.000	15.0	7.000	22.5
0.200	10.4	1.400	10.4	3.500	16.1	7.500	23.2
0.300	11.7	1.600	11.1	4.000	17.2	8.000	24.0
0.400	12.4	1.800	11.8	4.500	18.2	8.500	24.7
0.500	12.7	2.000	12.4	5.000	19.1	9.000	25.4
0.600	12.8	2.200	12.9	5.500	20.0	9.500	26.0
0.800	12.7	2.400	13.5	6.000	20.9		
1.000	12.2	2.600	14.0	6.500	21.7		

Vinery Court
 58 Cardigan Lane
 Leeds LS4 2LD

Wordsworth Excavations
 Wordsworth Vehicle Maintenance
 Proposed Calculations



Date 22/12/2021 14:40
 File v3 mark check.MDX

Designed by LW
 Checked by MH

Innovyze

Network 2020.1

Storage Structures for Storm

Cellular Storage Manhole: SW Ex 10, DS/PN: S1.004

Invert Level (m) 70.475 Safety Factor 2.0
 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
 Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	180.0	0.0	0.300	180.0	0.0
0.100	180.0	0.0	0.400	180.0	0.0
0.200	180.0	0.0	0.401	0.0	0.0

Cellular Storage Manhole: SW Tank, DS/PN: S7.007


Invert Level (m) 63.464 Safety Factor 2.0
 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
 Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	441.0	0.0	1.000	441.0	0.0
0.200	441.0	0.0	1.200	441.0	0.0
0.400	441.0	0.0	1.400	441.0	0.0
0.600	441.0	0.0	1.600	441.0	0.0
0.800	441.0	0.0	1.601	0.0	0.0

Cellular Storage Manhole: SW Tank, DS/PN: S7.010

Invert Level (m) 68.136 Safety Factor 2.0
 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
 Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	80.0	0.0	0.300	80.0	0.0
0.100	80.0	0.0	0.400	80.0	0.0
0.200	80.0	0.0	0.401	0.0	0.0

Melia Smith and Jones		Page 8
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

2 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000
Hot Start Level (mm) 0 Inlet Coefficient 1.000
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 3
Number of Online Controls 3 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.400
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status ON
DVD Status OFF
Inertia Status OFF

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440, 2160, 2880, 4320, 5760,
7200, 8640, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	SW Ex 2	15 Summer	2	+0%	100/15 Summer			
S2.000	SW Ex 1	15 Summer	2	+0%	100/15 Summer	100/15 Winter		
S1.001	SW Ex 3	15 Summer	2	+0%	100/15 Summer			
S3.000	SW Ex 5	15 Summer	2	+0%	100/15 Summer			
S4.000	SW Ex 4	15 Summer	2	+0%	100/15 Summer			
S1.002	SW Ex 6	15 Summer	2	+0%	30/15 Summer			
S5.000	SW Ex 7	15 Summer	2	+0%	100/15 Summer			
S5.001	SW Ex 8	15 Summer	2	+0%	30/15 Summer			
S1.003	SW Ex Tank	15 Summer	2	+0%	30/15 Summer	100/30 Summer		
S1.004	SW Ex 10	15 Summer	2	+0%	2/60 Winter	100/30 Winter		
S6.000	SW Ex 11	15 Summer	2	+0%	100/15 Summer			
S1.005	SW Ex 12	15 Summer	2	+0%	30/15 Summer			
S1.006	SW Ex 13	15 Summer	2	+0%	30/15 Summer			
S7.000	S14	15 Summer	2	+0%	100/15 Summer	100/15 Summer		

Melia Smith and Jones		Page 9
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

2 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
S1.000	SW Ex 2	71.346	-0.104	0.000	0.20		2.9	OK
S2.000	SW Ex 1	71.347	-0.103	0.000	0.21		2.9	OK
S1.001	SW Ex 3	71.175	-0.089	0.000	0.35		5.7	OK
S3.000	SW Ex 5	71.291	-0.109	0.000	0.16		2.9	OK
S4.000	SW Ex 4	71.290	-0.110	0.000	0.16		2.9	OK
S1.002	SW Ex 6	71.017	-0.077	0.000	0.48		11.4	OK
S5.000	SW Ex 7	71.182	-0.088	0.000	0.36		7.0	OK
S5.001	SW Ex 8	70.991	-0.124	0.000	0.42		27.3	OK
S1.003	SW Ex Tank	70.727	-0.068	0.000	0.82		38.2	OK
S1.004	SW Ex 10	70.572	-0.048	0.000	0.19		3.3	OK
S6.000	SW Ex 11	71.075	-0.095	0.000	0.28		6.2	OK
S1.005	SW Ex 12	70.127	-0.083	0.000	0.40		12.0	OK
S1.006	SW Ex 13	69.028	-0.067	0.000	0.58		17.3	OK
S7.000	S14	67.406	-0.079	0.000	0.45		9.4	OK


PN	US/MH Name	Level Exceeded
S1.000	SW Ex 2	
S2.000	SW Ex 1	1
S1.001	SW Ex 3	
S3.000	SW Ex 5	
S4.000	SW Ex 4	
S1.002	SW Ex 6	
S5.000	SW Ex 7	
S5.001	SW Ex 8	
S1.003	SW Ex Tank	18
S1.004	SW Ex 10	16
S6.000	SW Ex 11	
S1.005	SW Ex 12	
S1.006	SW Ex 13	
S7.000	S14	4

Melia Smith and Jones		Page 10
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

2 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) SurchARGE	First (Y) Flood	First (Z) Overflow	Overflow Act.
S7.001	S14	15 Summer	2	+0%	30/15 Summer	100/15 Summer		
S7.002	SW 1	15 Summer	2	+0%	30/15 Summer	100/15 Summer		
S7.003	S15	15 Summer	2	+0%	100/15 Summer			
S8.000	S18	15 Summer	2	+0%	30/15 Summer	100/15 Summer		
S7.004	S16	15 Summer	2	+0%	30/15 Summer			
S9.000	S20	15 Summer	2	+0%	100/15 Summer			
S9.001	S21	15 Summer	2	+0%	100/15 Summer			
S7.005	S17	15 Summer	2	+0%	30/15 Summer			
S7.006	SW 2	15 Summer	2	+0%	30/15 Winter	100/480 Winter		
S7.007	SW Tank	15 Summer	2	+0%	30/30 Summer	100/480 Winter		
S7.008	SW 4	15 Summer	2	+0%	2/15 Summer	100/600 Winter		
S7.009	SW 5	15 Summer	2	+0%	100/30 Winter			
S7.010	SW Tank	15 Summer	2	+0%	100/30 Summer			
S7.011	SW 6	15 Summer	2	+0%	100/15 Summer			
S1.007	SW Ex 14	15 Summer	2	+0%	30/15 Summer			
S1.008	SW Ex 15	15 Summer	2	+0%	30/60 Winter	100/60 Winter		
S1.009	SW Ex 16	15 Summer	2	+0%	30/60 Winter	100/60 Winter		
S1.010	SW Ex 17	15 Summer	2	+0%	2/15 Summer	100/120 Summer		
S1.011	SW Ex 18	15 Summer	2	+0%				

PN	US/MH Name	Water Surcharged Flooded			Half Drain		Pipe	Status
		Level (m)	Depth (m)	Volume (m³)	Flow / Cap. (l/s)	Overflow (l/s)	Time (mins)	
S7.001	S14	67.046	-0.120	0.000	0.44		31.7	OK
S7.002	SW 1	66.422	-0.199	0.000	0.44		78.7	OK
S7.003	S15	66.083	-0.218	0.000	0.36		78.8	OK
S8.000	S18	65.958	-0.151	0.000	0.48		45.2	OK
S7.004	S16	65.604	-0.230	0.000	0.48		124.1	OK
S9.000	S20	65.939	-0.099	0.000	0.25		4.1	OK
S9.001	S21	65.609	-0.179	0.000	0.33		25.3	OK
S7.005	S17	65.305	-0.209	0.000	0.55		150.6	OK
S7.006	SW 2	65.141	-0.223	0.000	0.50		166.3	OK
S7.007	SW Tank	63.649	-0.265	0.000	0.05		17.0	OK
S7.008	SW 4	63.648	0.159	0.000	0.31		5.0	SURCHARGED
S7.009	SW 5	68.424	-0.162	0.000	0.17		5.0	OK
S7.010	SW Tank	68.199	-0.162	0.000	0.17		4.9	OK
S7.011	SW 6	68.164	-0.181	0.000	0.09		4.9	OK
S1.007	SW Ex 14	68.023	-0.103	0.000	0.56		22.4	OK
S1.008	SW Ex 15	67.781	-0.155	0.000	0.46		33.6	OK
S1.009	SW Ex 16	67.175	-0.654	0.000	0.04		35.5	OK
S1.010	SW Ex 17	66.990	0.254	0.000	0.30		12.6	SURCHARGED
S1.011	SW Ex 18	65.945	-0.140	0.000	0.31		12.6	OK

Melia Smith and Jones		Page 11
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

2 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

PN	US/MH Name	Level Exceeded
S7.001	S14	4
S7.002	SW 1	2
S7.003	S15	
S8.000	S18	4
S7.004	S16	
S9.000	S20	
S9.001	S21	
S7.005	S17	
S7.006	SW 2	4
S7.007	SW Tank	4
S7.008	SW 4	2
S7.009	SW 5	
S7.010	SW Tank	
S7.011	SW 6	
S1.007	SW Ex 14	
S1.008	SW Ex 15	15
S1.009	SW Ex 16	14
S1.010	SW Ex 17	4
S1.011	SW Ex 18	

Melia Smith and Jones		Page 12
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

30 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000
Hot Start Level (mm) 0 Inlet Coefficient 1.000
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 3
Number of Online Controls 3 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.400
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status ON
DVD Status OFF
Inertia Status OFF

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440, 2160, 2880, 4320, 5760,
7200, 8640, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	SW Ex 2	15 Summer	30	+0%	100/15 Summer			
S2.000	SW Ex 1	15 Summer	30	+0%	100/15 Summer	100/15 Winter		
S1.001	SW Ex 3	15 Summer	30	+0%	100/15 Summer			
S3.000	SW Ex 5	15 Summer	30	+0%	100/15 Summer			
S4.000	SW Ex 4	15 Summer	30	+0%	100/15 Summer			
S1.002	SW Ex 6	15 Summer	30	+0%	30/15 Summer			
S5.000	SW Ex 7	15 Summer	30	+0%	100/15 Summer			
S5.001	SW Ex 8	15 Summer	30	+0%	30/15 Summer			
S1.003	SW Ex Tank	15 Summer	30	+0%	30/15 Summer	100/30 Summer		
S1.004	SW Ex 10	15 Summer	30	+0%	2/60 Winter	100/30 Winter		
S6.000	SW Ex 11	15 Summer	30	+0%	100/15 Summer			
S1.005	SW Ex 12	15 Summer	30	+0%	30/15 Summer			
S1.006	SW Ex 13	15 Summer	30	+0%	30/15 Summer			
S7.000	S14	15 Summer	30	+0%	100/15 Summer	100/15 Summer		

Melia Smith and Jones		Page 13
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

30 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
S1.000	SW Ex 2	71.365	-0.085	0.000	0.38		5.5	OK
S2.000	SW Ex 1	71.366	-0.084	0.000	0.39		5.4	OK
S1.001	SW Ex 3	71.204	-0.060	0.000	0.67		10.8	OK
S3.000	SW Ex 5	71.308	-0.092	0.000	0.31		5.5	OK
S4.000	SW Ex 4	71.306	-0.094	0.000	0.30		5.5	OK
S1.002	SW Ex 6	71.124	0.030	0.000	0.96		22.7	SURCHARGED
S5.000	SW Ex 7	71.222	-0.048	0.000	0.67		13.2	OK
S5.001	SW Ex 8	71.122	0.007	0.000	0.96		63.0	SURCHARGED
S1.003	SW Ex Tank	70.982	0.187	0.000	1.70		79.6	SURCHARGED
S1.004	SW Ex 10	70.663	0.043	0.000	0.26		4.4	SURCHARGED
S6.000	SW Ex 11	71.100	-0.070	0.000	0.53		11.7	OK
S1.005	SW Ex 12	70.223	0.013	0.000	0.84		25.0	SURCHARGED
S1.006	SW Ex 13	69.559	0.464	0.000	1.14		34.2	SURCHARGED
S7.000	S14	67.454	-0.031	0.000	0.85		17.7	OK


PN	US/MH Name	Level Exceeded
S1.000	SW Ex 2	
S2.000	SW Ex 1	1
S1.001	SW Ex 3	
S3.000	SW Ex 5	
S4.000	SW Ex 4	
S1.002	SW Ex 6	
S5.000	SW Ex 7	
S5.001	SW Ex 8	
S1.003	SW Ex Tank	18
S1.004	SW Ex 10	16
S6.000	SW Ex 11	
S1.005	SW Ex 12	
S1.006	SW Ex 13	
S7.000	S14	4

Melia Smith and Jones		Page 14
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

30 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.
S7.001	S14	15 Summer	30	+0%	30/15 Summer	100/15 Summer		
S7.002	SW 1	15 Summer	30	+0%	30/15 Summer	100/15 Summer		
S7.003	S15	15 Summer	30	+0%	100/15 Summer			
S8.000	S18	15 Summer	30	+0%	30/15 Summer	100/15 Summer		
S7.004	S16	15 Summer	30	+0%	30/15 Summer			
S9.000	S20	15 Summer	30	+0%	100/15 Summer			
S9.001	S21	15 Summer	30	+0%	100/15 Summer			
S7.005	S17	15 Summer	30	+0%	30/15 Summer			
S7.006	SW 2	15 Summer	30	+0%	30/15 Winter	100/480 Winter		
S7.007	SW Tank	15 Summer	30	+0%	30/30 Summer	100/480 Winter		
S7.008	SW 4	15 Summer	30	+0%	2/15 Summer	100/600 Winter		
S7.009	SW 5	15 Summer	30	+0%	100/30 Winter			
S7.010	SW Tank	15 Summer	30	+0%	100/30 Summer			
S7.011	SW 6	15 Summer	30	+0%	100/15 Summer			
S1.007	SW Ex 14	15 Summer	30	+0%	30/15 Summer			
S1.008	SW Ex 15	15 Summer	30	+0%	30/60 Winter	100/60 Winter		
S1.009	SW Ex 16	15 Summer	30	+0%	30/60 Winter	100/60 Winter		
S1.010	SW Ex 17	15 Summer	30	+0%	2/15 Summer	100/120 Summer		
S1.011	SW Ex 18	15 Summer	30	+0%				

PN	US/MH Name	Water Surcharged Flooded			Half Drain Pipe		Status
		Level (m)	Depth (m)	Volume (m³)	Flow / Overflow (l/s)	Time (mins)	
S7.001	S14	67.225	0.059	0.000	1.00		71.5 SURCHARGED
S7.002	SW 1	66.658	0.037	0.000	1.06		189.4 SURCHARGED
S7.003	S15	66.199	-0.102	0.000	0.86		187.8 OK
S8.000	S18	66.146	0.037	0.000	0.90		83.9 SURCHARGED
S7.004	S16	65.870	0.036	0.000	0.99		256.7 SURCHARGED
S9.000	S20	65.962	-0.076	0.000	0.48		7.7 OK
S9.001	S21	65.698	-0.090	0.000	0.78		59.5 OK
S7.005	S17	65.548	0.034	0.000	1.14		311.2 SURCHARGED
S7.006	SW 2	65.353	-0.011	0.000	1.00		334.3 OK
S7.007	SW Tank	63.827	-0.087	0.000	0.06		19.3 OK
S7.008	SW 4	63.840	0.351	0.000	0.31		5.0 SURCHARGED
S7.009	SW 5	68.424	-0.162	0.000	0.17		5.0 OK
S7.010	SW Tank	68.199	-0.162	0.000	0.17		4.9 OK
S7.011	SW 6	68.164	-0.181	0.000	0.09		4.9 OK
S1.007	SW Ex 14	68.173	0.047	0.000	1.12		44.8 SURCHARGED
S1.008	SW Ex 15	67.881	-0.055	0.000	0.99		71.9 OK
S1.009	SW Ex 16	67.296	-0.533	0.000	0.08		75.9 OK
S1.010	SW Ex 17	67.295	0.559	0.000	0.29		12.0 SURCHARGED
S1.011	SW Ex 18	65.943	-0.142	0.000	0.29		11.9 OK

Melia Smith and Jones		Page 15
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

30 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

PN	US/MH Name	Level Exceeded
S7.001	S14	4
S7.002	SW 1	2
S7.003	S15	
S8.000	S18	4
S7.004	S16	
S9.000	S20	
S9.001	S21	
S7.005	S17	
S7.006	SW 2	4
S7.007	SW Tank	4
S7.008	SW 4	2
S7.009	SW 5	
S7.010	SW Tank	
S7.011	SW 6	
S1.007	SW Ex 14	
S1.008	SW Ex 15	15
S1.009	SW Ex 16	14
S1.010	SW Ex 17	4
S1.011	SW Ex 18	

Melia Smith and Jones		Page 16
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m ³ /ha Storage	0.000
Hot Start Level (mm)	0	Inlet Coefficient	1.000
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	3
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details


Rainfall Model	FSR	Ratio R	0.400
	Region England and Wales	Cv (Summer)	0.750
M5-60 (mm)		20.000 Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	ON
DVD Status	OFF
Inertia Status	OFF

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow
S1.000	SW Ex 2	15 Summer	100	+40%	100/15 Summer		
S2.000	SW Ex 1	15 Winter	100	+40%	100/15 Summer	100/15 Winter	
S1.001	SW Ex 3	15 Summer	100	+40%	100/15 Summer		
S3.000	SW Ex 5	15 Summer	100	+40%	100/15 Summer		
S4.000	SW Ex 4	15 Summer	100	+40%	100/15 Summer		
S1.002	SW Ex 6	15 Summer	100	+40%	30/15 Summer		
S5.000	SW Ex 7	15 Summer	100	+40%	100/15 Summer		
S5.001	SW Ex 8	15 Summer	100	+40%	30/15 Summer		
S1.003	SW Ex Tank	180 Winter	100	+40%	30/15 Summer	100/30 Summer	
S1.004	SW Ex 10	180 Winter	100	+40%	2/60 Winter	100/30 Winter	
S6.000	SW Ex 11	15 Summer	100	+40%	100/15 Summer		
S1.005	SW Ex 12	15 Summer	100	+40%	30/15 Summer		
S1.006	SW Ex 13	15 Summer	100	+40%	30/15 Summer		
S7.000	S14	15 Winter	100	+40%	100/15 Summer	100/15 Summer	

Melia Smith and Jones		Page 17
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap. (l/s)	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)
S1.000	SW Ex 2		71.771	0.321	0.000	0.59			8.4
S2.000	SW Ex 1		71.850	0.400	0.003	0.62			8.5
S1.001	SW Ex 3		71.712	0.448	0.000	0.97			15.6
S3.000	SW Ex 5		71.655	0.255	0.000	0.47			8.4
S4.000	SW Ex 4		71.651	0.251	0.000	0.46			8.5
S1.002	SW Ex 6		71.591	0.497	0.000	1.35			31.9
S5.000	SW Ex 7		71.921	0.651	0.000	1.37			27.1
S5.001	SW Ex 8		71.784	0.669	0.000	1.61			106.0
S1.003	SW Ex Tank		71.773	0.978	22.643	0.78			36.3
S1.004	SW Ex 10		71.767	1.147	16.780	0.28			4.8
S6.000	SW Ex 11		71.820	0.650	0.000	0.78			17.2
S1.005	SW Ex 12		71.324	1.114	0.000	0.91			27.0
S1.006	SW Ex 13		70.563	1.468	0.000	1.44			42.9
S7.000	S14		68.687	1.202	2.137	1.62			33.6

PN	US/MH Name	Status	Level Exceeded
S1.000	SW Ex 2	FLOOD RISK	
S2.000	SW Ex 1	FLOOD	1
S1.001	SW Ex 3	FLOOD RISK	
S3.000	SW Ex 5	FLOOD RISK	
S4.000	SW Ex 4	FLOOD RISK	
S1.002	SW Ex 6	FLOOD RISK	
S5.000	SW Ex 7	FLOOD RISK	
S5.001	SW Ex 8	FLOOD RISK	
S1.003	SW Ex Tank	FLOOD	18
S1.004	SW Ex 10	FLOOD	16
S6.000	SW Ex 11	SURCHARGED	
S1.005	SW Ex 12	SURCHARGED	
S1.006	SW Ex 13	FLOOD RISK	
S7.000	S14	FLOOD	4

Melia Smith and Jones		Page 18
Vinery Court 58 Cardigan Lane Leeds LS4 2LD	Wordsworth Excavations Wordsworth Vehicle Maintenance Proposed Calculations	
Date 22/12/2021 14:40 File v3 mark check.MDX	Designed by LW Checked by MH	
Innovyze	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Flood Volume
(Rank 1) for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharges	First (Y) Flood	First (Z) Overflow	Overflow Act.
S7.001	S14	15 Winter	100	+40%	30/15 Summer	100/15 Summer		
S7.002	SW 1	15 Winter	100	+40%	30/15 Summer	100/15 Summer		
S7.003	S15	15 Summer	100	+40%	100/15 Summer			
S8.000	S18	15 Winter	100	+40%	30/15 Summer	100/15 Summer		
S7.004	S16	15 Summer	100	+40%	30/15 Summer			
S9.000	S20	15 Summer	100	+40%	100/15 Summer			
S9.001	S21	15 Summer	100	+40%	100/15 Summer			
S7.005	S17	15 Summer	100	+40%	30/15 Summer			
S7.006	SW 2	720 Winter	100	+40%	30/15 Winter	100/480 Winter		
S7.007	SW Tank	960 Winter	100	+40%	30/30 Summer	100/480 Winter		
S7.008	SW 4	720 Winter	100	+40%	2/15 Summer	100/600 Winter		
S7.009	SW 5	15 Summer	100	+40%	100/30 Winter			
S7.010	SW Tank	15 Summer	100	+40%	100/30 Summer			
S7.011	SW 6	15 Summer	100	+40%	100/15 Summer			
S1.007	SW Ex 14	15 Summer	100	+40%	30/15 Summer			
S1.008	SW Ex 15	180 Winter	100	+40%	30/60 Winter	100/60 Winter		
S1.009	SW Ex 16	120 Winter	100	+40%	30/60 Winter	100/60 Winter		
S1.010	SW Ex 17	600 Winter	100	+40%	2/15 Summer	100/120 Summer		
S1.011	SW Ex 18	15 Summer	100	+40%				

PN	US/MH Name	Water Surcharged Flooded			Half Drain Pipe		Status
		Level (m)	Depth (m)	Volume (m³)	Flow / Overflow Cap. (l/s)	Time (mins)	
S7.001	S14	68.375	1.209	9.487	1.62		115.7 FLOOD
S7.002	SW 1	68.097	1.476	1.271	1.52		270.0 FLOOD
S7.003	S15	67.525	1.224	0.000	1.16		252.7 SURCHARGED
S8.000	S18	67.243	1.134	8.742	1.46		137.1 FLOOD
S7.004	S16	66.903	1.069	0.000	1.38		357.5 SURCHARGED
S9.000	S20	66.813	0.775	0.000	1.01		16.3 SURCHARGED
S9.001	S21	66.714	0.926	0.000	1.22		93.5 SURCHARGED
S7.005	S17	66.278	0.764	0.000	1.71		464.0 SURCHARGED
S7.006	SW 2	67.003	1.639	21.233	0.17		55.9 FLOOD
S7.007	SW Tank	67.001	3.087	1.893	0.04		14.1 FLOOD
S7.008	SW 4	67.060	3.571	0.625	0.31		5.0 FLOOD
S7.009	SW 5	68.424	-0.162	0.000	0.17		5.0 OK
S7.010	SW Tank	68.247	-0.114	0.000	0.38		10.9 OK
S7.011	SW 6	68.389	0.044	0.000	0.18		10.6 SURCHARGED
S1.007	SW Ex 14	68.470	0.344	0.000	1.36		54.2 SURCHARGED
S1.008	SW Ex 15	69.445	1.509	25.322	0.57		41.4 FLOOD
S1.009	SW Ex 16	69.451	1.622	1.177	0.06		51.2 FLOOD
S1.010	SW Ex 17	69.480	2.744	0.018	0.36		14.8 FLOOD
S1.011	SW Ex 18	65.943	-0.142	0.000	0.29		11.9 OK

Vinery Court
 58 Cardigan Lane
 Leeds LS4 2LD

Wordsworth Excavations
 Wordsworth Vehicle Maintenance
 Proposed Calculations



Date 22/12/2021 14:40
 File v3 mark check.MDX

Designed by LW
 Checked by MH


Innovyze

Network 2020.1

100 year Return Period Summary of Critical Results by Maximum Flood Volume
 (Rank 1) for Storm

PN	US/MH Name	Level Exceeded
S7.001	S14	4
S7.002	SW 1	2
S7.003	S15	
S8.000	S18	4
S7.004	S16	
S9.000	S20	
S9.001	S21	
S7.005	S17	
S7.006	SW 2	4
S7.007	SW Tank	4
S7.008	SW 4	2
S7.009	SW 5	
S7.010	SW Tank	
S7.011	SW 6	
S1.007	SW Ex 14	
S1.008	SW Ex 15	15
S1.009	SW Ex 16	14
S1.010	SW Ex 17	4
S1.011	SW Ex 18	

Appendix I



P1 First Issue			
Rev	Revision Description	By	Chk Date
n.t.s.	Leeds		221062
SCALE @ A1	ISSUING OFFICE	MSJ PROJECT NUMBER	
S1	PURPOSE OF ISSUE	CO-ORDINATION	
 Melia Smith & Jones Consulting Civil & Structural Engineers Vinery Court 58 Cardigan Lane Leeds LS4 2LD 0113 2366890 www.msj.co.uk			
PROJECT			
Wordsworth Excavations & Crushing, Vehicle Maintenance Unit Barugh Green			
TITLE			
Wash Bay Schematic			
CLIENT			
Wordsworth Excavations & Crushing			
DRAWING NUMBER			REV
221062-SK01			P01