Barnsley Metropolitan Borough Council
2 [illegible] 2009
Corporate Mail Room

HEDGE SCHEDULE

Species	Form	Age	Minimum size (height in cms)	Root condition	Container size in litres	Number of breaks/branches	Ratio	Number of plants (4/lin.m.)
Acer campestre	Transplant	1+1	60-80	B	-	-	20%	180
Betula pendula	Transplant	1+1	40-60	B	-	-	15%	135
Ilex aquifolium	Bush	-	30-40	C	2	-	20%	180
Prunus spinosa	Branched	1+1	40-60	B	-	2	10%	90
Viburnum opulus	Branched	1+1	40-60	B	-	2	15%	135
Corylus avellana	Transplant	1+1	40-60	B	-	-	20%	180

TREE SCHEDULE

Species	Dwg Ref	Girth (cms)	Overall height (cms)	Clear stem (cms)	Root condition	Number of breaks/branches	Number of plants
Prunus padus	Pp	6-8	250-300	150-175	B	3	5
Sorbus aucuparia	Sa	6-8	250-300	150-175	B	3	9
Alnus glutinosa	Ag	6-8	250-300	150-175	B	3	4

