

Walls
Internal skin
Wall A
Exposed brickwork.
Provide 75mm Kingspan within cavity.

All other walls.
100 mm Thermolite shield or similar blockwork
Cavity
For 100 mm air gap filled with 50 gap + 50 kingspan k8.
Wall insulation to extend 150 mm below the top of the floor insulation.
Cavity to extend full height up into roof space.
Cavity fill of weak mix conc to be no higher than 225 mm below highest dpc
Cavity to be sealed at eaves with insulated cavity closer incorporating a vert dpc.
All cavity wall returns to be 655 mm minimum.
Insulated cavity closers to be provided to all reveals.

External skin
Brickwork to match existing
Stainless vertical twist wall ties to be provided at 750 horiz c/c and 450 mm vert c/c, every block depth to reveals.
Weep holes to be provided where applicable.

Construction (Design and Management) Regulations 1994
Applicable to all projects except work to a persons own house other than that carried out by the developer.
The client shall be advised that all projects lasting for more than 30 days or include more than 4 people engaged on the construction on site at any one time shall be subject to the above regulation.
The client shall take all reasonable steps to ensure that the appointed contractors have the competence and adequate resources sufficient to manage the construction work and comply with the above regulations.

If the project is subject to the above regulation the client shall appoint a planning supervisor and ensure that notice is served on the health and safety executive at tender acceptance stage using form 10.

DPC's
To be provided to
External walls 150 mm above fgl.
All door and window jamb / heads
Under lintols
Above all air bricks
Tray dpc to roof / wall junction.

Timber Ground Floor
(see 3) 38 x 175 softwood joists at 400 c/c with herringbone strutting at mid span. 19 mm T & G floor grade particle board (EN 312-5) screwed to joists or 19mm T&G floorboards (BS 1297)
170 mm fibre insulation to be provided between joists.
Joists to be built into walls or attached to joist hangers. Ends of joists where built in to be treated.
Provide oversite concrete on 1200 g visqueen. Provide 150mm between conc and u.s. of joists.
Airbricks required to all sides of extension at 900 c/c
Sleeper walls to be honeycombed to allow ventilation

Roof Ventilation.
Ridge ventilation to be equivalent to a continuous gap strip of 5 mm.
Eaves to be equivalent to a continuous gap strip of 25mm.

Plumbing and Drainage.
Hepworth or similar 112mm UPVC gutters, brackets and fittings down pipe to be 75 mm dia.

General
Re site any utility services where applicable around the extension. Re site any meter boxes outside line of walls.
Any structural steel supports to have full half hour fire protection encasement comprising 2 layers of 12.5 mm plasterboard / skim.
Any details indicated on the calculations shall override any details shown on this drawing.

Multi fuel stove
A chimney flue shall be fitted in accordance with the suppliers requirements.
An air vent to outside air shall be fitted to provide combustion air supply.
An information plate containing all relevant information shall be fitted.
Full specifications incl flue, hearth flue height and combustion air details etc to be provided to the local authority 28 days prior to installation for approval.

Foundations
All concrete to be grade C35
Foundations to be 600mm x 225 mm deep. Placed 1000 mm below fgl. Or as directed by the Building Inspector.
Where foundations cross drainage services the foundations to be taken down below the L.L. of the pipe. A concrete lintol to be placed over to bridge the pipe.
Provide rocker pipes either side of the wall and a 50mm space between masonry and pipe with flexible seal.
Any eccentric foundations to be 750 x 450 thk reinforced with 2 layers B783 mesh 50mm cover to all faces.
It is assumed that the ground conditions facilitate the use of traditional strip foundations.
The building Inspector to advise otherwise.

Lintols
Structural steel Beams are required as shown refer to calculations
All door / openings / window lintols to be "Calmic". Size and type as agreed with the Building Inspector.
End bearing for all lintols to be 150 mm.

Facia / soffit boards
From 25 mm x 250 mm or similar
In timber or pvc. provide air vents as described.

Radon Barrier
Where Radon Barrier is required visqueen to be 2000 g with all joints overlapped and gas taped and all penetrations thro to be sealed. This to continue thro the external leaf with tray dpc. On suspended timber floor visqueen to be placed under oversite conc.

For category 1 land fill sites use gas membrane such as Monarflex or similar

Proposed Ground Floor Layout

Surface water
All external drains to be 100mm Osma plastic pipe bed and surround in gravel to falls
Surface water - 1:100
All new surface water to be taken to a soakaway a min of 5m from any building
All drainage and protection details to existing shall be agreed with the Building Inspector.

Doors / windows.
All to be UPVC double glazed (min 16 mm gap between panes) glazed with Pilkington K glass with soft low "E" coating.
Style and colour of all to match existing.
All windows to have 1/20 th floor area as open light.
Safety glass (stamped accordingly) to be provided to all critical areas. Door and panels 1.5 m from fl. Or windows within 800 mm from fl.
Trickle vents to be provided to all new windows 8000 mm2 min equivalent area

Electrical Installations.
All installations to be subject to certification under the "competent persons scheme"
Qualified to a min of Part P
A certificate shall be supplied on completion of all electrical works
Lighting - 75% to be low energy.
Light switches to be fixed 1200 above ffl, Power sockets to be fixed at 450mm above ffl.

Means of escape.
1 No self contained operated smoke alarm to BS 5446 Part 1 to be installed on each storey smoke detectors interlinked.
All detectors to be a min of 300 mm from any wall.
Interconnected & wired to a separated fused circuit. Battery back up required.

Heating.
The existing gas central heating boiler to be assessed for suitability for extension.
All hot water pipes shall be insulated with foam equivalent to the outside dia of the pipe. Radiators to have thermostatic valves.

U Values
The builder shall ensure that the following values are achieved.
Pitched roof insulation
A1 rafter level 0.18w/m2k
Walls 0.28w/m2k
g.f. 0.22 (with P/a D9)
Windows / doors 1.6w/m2k
All roof and wall insulation to be continuous.

Roof design (Traditional.)
Tiled covering laid in accordance with the manufacturers instructions suitable for pitch to match existing on 50 x 25 battens and a layer of Tyvek fully breathable felt.
Rafters 47 x 150 at 400 c/c secured to ridge and birdsmouth joint over 100 x 75 wall plates to steel purlins and wall plates.
Purlins to be steel beams - refer to calculations.

Valleys to have 5 lb lead flashing.
Roof shall ensure a continued air flow.
Soffits shall be fitted with vents or a 25 mm gap with bird mesh.
Ridge vents shall be fitted where necessary and as directed by the Building Inspector.
Roof to be suitably wind braced to appendix A of BS 5268 PT 3.
Wall plates to be fixed by gale steel straps @ 1800 c/c
Roof ventilation - Vents to be provided to eaves soffit, ridge and tile vents all as directed by the building Inspector.

Roof Insulation.
To rafters on roof slopes. + velux sides
100 mm kingspan k7 between rafters + underdrawn 62.5 kingspan k18 under rafters
Min 50 mm min air flow required between insulation and roof covering.

Lateral Restraint to floors / gable roof
Galvanised mild steel strap 38 x 5 @ 2m c/c to joists and rafters spanning 3 joists with solid noggins at 450 c/c down cavity.

Typical Section On A - A
1 : 25

Existing Ground Floor Layout

NOTES:
All dimensions must be checked on site and not scaled from this drawing.

General.
Construction of a single storey rear extension

Notes.
General
These plans and details have been prepared for the purpose of providing information to the local authority to assist them in determining approval or rejection of planning / building regulations.
These notes and details indicated on these drawing drawings are to be checked and verified by the contractor at the time of pricing and prior to commencement, the builder shall satisfy himself that all details and dimensions are correct.
Any discrepancies shall be identified at the time of tendering and the client notified in writing of such changes required.
All dimensions to be taken to the nearest brick size.
His price shall be deemed to include for: Any additional calculations as required by building control and as a result any additional building works that may be required.
Satisfying all current relevant codes of practices and British Standards shown or omitted from these drawings.
When appropriate it is the owners responsibility to serve notice on the adjoining / adjacent neighbours for the proposed works under the Party Wall act 1996. The explanatory booklet can be obtained free of charge from ODPM free literature PO Box 236 West Yorkshire LS23 7NB. Tel 0870 122 6236

E	
D	
C	
B	
A	
	Date
	Revisions
© copyright	
	
SDC Projects Ltd 336 Manchester Road Deepear Sheffield S36 2RH Tel 0114 3279 118 Tel 07970 291539	

21 Tollbar Close
Oxspring
S36 8WJ

Client

Paul Raggett

Job Title

SINGLE STOREY
REAR EXTENSION.

Drawing Title

General Arrangement /
Floor Layouts

Scale 1 : 50

Date 1.10.12 Drawn by Steve Camps

Drp. No. PR / 01 Rev

RMB
CORPORATE MAIL ROOM

17 OCT 2012

Received by:
ORIGINAL COPY