
[illegible]

no excavation work to be carried out within a 6m rad. root protection area
tree protection plan to BGS372005 i.e. 2.3m high scaffold pole framework
with weldmesh panels, no additional planting within the site
max. No of HGVs entering site to be 12 per day
jet wash to be provided to clean wheels of vehicles leaving site when muddy.
jet washing to be carried out in areas where motorway chippings form the
hardstanding, this will act as a natural soakaway for excess water.
water spray to be provided to suppress affects of dust ect.
all litter to be picked up where and when it occurs
machinery on permanently on site are 1 mini digger & 1 loading shovel
No crushing or screeding to be carried out on site
Max. 2m the height of any externally stored materials
DUST
a dust suppression system, incorporating a misting and sprinkler system to be
installed, implemented and maintained throughout the working life of the site.
LITTER
an action plan is to be implemented whereas in the event of any stray litter
occurring on site, this will be patrolled and picked up on a regular basis
throughout the day and disposed of appropriately.
at no time will any waste material be burnt on site
NOISE
efficient silencers shall be fitted to, used & maintained in accordance with m
instructions, on all vehicles, plant and machinery used on site.
save for the purposes of maintenance no machinery shall operate with the
covers open or removed

PROPOSED C/U TO BUILDERS
YARD & SKIP HIRE
BEEVOR ST. IND. EST.
BEEVOR ST. BARNESLEY

1:500 OCT. 08 Rev E

Peter Thompson
"Linwood"
Barnsley Road
Dodworth
Barnsley S75 3JR
e-mail peter-thompson@hotmail.co.uk


M.C.I.A.T.

tel. 01226 201391
m. 07973251730

