Proposed Trees							
Abb	Name	Form	Girth	Height	Clr/stem	Root	Qty
BpD	Betula pendula 'Dalecarlica'	Standard (Selected)	10-12cm	300-350cm	175-200cm	RB	1
ScE	Sorbus commixta 'Embley'	Standard (Selected)	10-12cm	300-350cm	175-200cm	RB	4
							5

Proposed Shrubs						
Abb	Name	Height/Spread	Root	Cntr	M2	Qty
Bt	Berberis thunbergii	20-30cm	C	2L	4.00	49
CBM	Ceanothus 'Blue Mound'	20-30cm (D)	C	2L	4.00	18
CtR	Ceanothus thyrsiflorus 'Repens'	20-30cm	C	2L	4.00	8
EtEG	Euonymus fortunei 'Emerald 'n' Gold'	20-30cm (D)	C	3L	4.00	7
EtSQ	Euonymus fortunei 'Silver Queen'	20-30cm	C	2L	4.00	25
EpM	Elaeagnus pungens 'Maculata'	40-60cm	C	5L	4.00	8
HMW	Hebe 'Mrs Winder'	20-30cm	C	2L	4.00	38
HRE	Hebe albicans 'Red Edge'	20-30cm	C	2L	4.00	8
LaM	Lavandula angustifolia 'Munstead'	30-40cm	C	5L	4.00	33
LnMG	Lonicera nitida 'Maygreen'	30-40cm	C	2L	4.00	61
Lp	Lonicera pileata	40-60cm (D)	C	2L	4.00	11
PtOL	Prunus laurocerasus 'Otto Luyken'	40-60cm	C	5L	4.00	81
PSR	Pyracantha 'Saphyr Red'	60-80cm	C	5L	4.00	5
PSY	Pyracantha 'Saphyr Yellow'	60-80cm	C	5L	4.00	10
PxfRR	Photinia x fraseri 'Red Robin'	60-80cm	C	5L	4.00	49
SjRu	Skimmia japonica 'Rubella'	30-40cm	C	3L	4.00	18
VmA	Vinca minor 'Argenteovariegata'	40-60cm	C	5L	4.00	4
						434

This drawing has been prepared for the purpose of planning approval.

Planting Notes

Topsoil: shall be a minimum of 400mm depth over planting beds and graded to fall. Imported topsoil must be BS3882:2007 compliant and existing topsoil must be cultivated in accordance with BS3882:2007. No cultivation should take place in wet/ waterlogged conditions.
Herbicide and cultivation: Topsoil to be treated with two applications of herbicide prior to planting, where necessary, strictly in accordance with the Control of Pesticides Regulations 1986 (as amended 1997 or, otherwise, updated/superseded legislation) and following manufacturer's instructions by qualified staff. The topsoil shall than be cultivated to 150mm depth.
Planting: All planting and turfing shall conform to BS: 3936: 1992 and BS:4428:1989.
Trees: Standard trees to be planted in pits 800x800x450mm or dimensions of rootball, whichever is greater. Tree to be supported by 1Nr stake (1500mm long, per tree, 600mm above ground, 75mm diameter) and 1Nr bio-degradeable tie. Heavy and Extra Heavy Standard trees to be planted in pits 1000x1000x600mm or dimensions of rootball, whichever is greater. Tree to be supported by 2Nr stakes (1500mm long, 600mm above ground, 75mm diameter), cross bar (400x100x15mm) and 1Nr bio-degradeable ties. Alginure soil improver and 150g Enmag (or, equivalent) to be incorporated into the soil of all new tree pits. Trees to be planted centrally within a tree pit.
Container grown shrubs, transplants and whips: Shrubs and transplants shall be planted in pits 300x300x400mm depth), and the backfill shall include 3 litres of peat-free tree and shrub compost. Where two or more shrub species are indicated within a single bed each species shall be randomly mixed throughout the bed in groups of 3/5.
Herbicide: Spot treat with herbicide throughout the maintenance period in accordance with the manufacturer's instructions.
Mulch: Planting beds to receive 75mm depth pulverized ornamental bark mulch. Native woodland/edge plants to be planted with 800g flax fibre mulch mat pinned to soil. Native hedgerow to be planted through 800g flax fibre mulch roll, edges tucked. Ensure the top of the mulch layer is a minimum of 15mm below adjacent pavements and other surfaces, to prevent spillage.
Plant position: Final position of trees and shrubs subject to confirmation of service location and approval of statutory undertakers.
Protection to planting: Native hedgerow plants to be protected by spiral shelters. Native trees and shrubs within mixes to be protected by shelter guards as supplied by Acorn Planting Products Ltd (01508 528763), or equivalent.
Ornamental hedging: Hedges to comprise a single row of plants. 400mm wide trench excavated to take plants and topsoil cultivated to 400mm depth prior to application of fertiliser.
Grass: All turf/seeded areas to be cultivated and levelled as required removing any stones, rubble, subsoil, general construction waste.
Planting Season: Bare-root shrubs to be planted between mid-November and mid-March dependant upon the planting season.

LEGEND

- Existing tree to be retained
- Existing tree to be removed
- Proposed tree Standard (Selected)
- Proposed shrub bed
- Proposed grass

Rev A: Changed site boundary at request of Client - 07Jun18 (MP/jr)

Base: Orion Homes 'Site Layout' 9295-100-E received 17May18

Drawing No	Drawn by	Date	Project
H2 180503/1	BP	31.05.18	Saunderson Road, Penistone
Revision A	Checked by SH	Scale 1:250@A1	Client Orion Homes

Drawing
Detailed Landscape Proposals

Status
-

LANDSCAPE PLANNING PARTNERSHIP

Note: Dimensions to be checked on site. All in metres unless stated otherwise. Do not scale off drawing.