



CABIN CABIN

Existing Parking to be relocated on site.
 New automatic 4.8m rising arm security gate. With top and bottom curtain.
 Proposed WC to be connected to existing Drainage.
 New raised island formed with kerbs, with 2.4m high galvanised palisade security fence.
 Existing vehicle gate to be removed.
 Existing Parking to be relocated on site.

New security cabin to be provided on central island
 Proposed 2.4m high palisade fence to be installed. finish to be anthracite grey.
 Existing security hut to be removed.

New automatic 6m rising arm security gate. With top and bottom curtain.

Existing island to be removed, including bollards and kerbs.
 Stop road marking to be provided in white paint.

Existing vehicle gate to be removed.

Road marking to be provided in white paint, to form a turning circle for vehicles.
 Stop road marking to be provided in white paint.

Existing palisade fence to be removed.
 New 2.4m high galvanised palisade security fence.
 New 2.4m high pedestrian gate to be installed.
 Proposed 2No. turnstile access points to be installed. Material finish to be Anthracite Grey.
 Stop road marking to be provided in white paint.

2.4M PALISADE FENCE

2.4M PALISADE FENCE

Main Entrance Site Plan - As Proposed
 Scale 1:100

Revision	Description	Date
Client	BARNSELY Metropolitan Borough Council	
Project Title	Smithies Depot Entrance/Exit Smithies Lane Barnsley S71 1NL	
Drawing Title	Main Entrance Site Plan - As Proposed	
JANUS Architecture		
Gateway Studio, Unit 3A, Link 606 Business Park, Staithegate Lane, Bradford, BD6 1YA +44 (0) 1274 424 884 www.janusarchitecture.co.uk		
Drawing Status	Scales	Size
PLANNING	1:100	A1
Drawing Number	Revision	Date
1419-051	-	JUL '25