



- Equipment**
- 1 x TEK8(9)(B) Trombone End Kit 900x800mm
 - 1 x PS912
 - 1 x PS915
 - 1 x AGU(B)
 - 1 x HR15L(B)
 - 1 x HV5(B)
 - 1 x HV3R(B)
 - 4 x LBKT
 - 8 x LG5/FT
 - 8 x LAB
 - 15 x FXN
 - 1 x ACON(B)
 - 4 x SCON(B)
 - 1 x TEX-200

Semi permanent ramp specification

Handrails,
Galvanised & acrylic coated (warm touch)
Rail height = 900mm above all platforms & ramp sections
Mid-rail = 600mm above all platforms & ramp sections
Curbs = 100mm upstand to both sides of ramp system
Rail outer diameter = 42mm

Platforms & ramp sections
Galvanised steel frame
Expanded metal mesh surface
Multi direction grip

Ref : JW131

Surveyor : J Walbank

Gradient : 1:12

2men/2 days
Platform 900x1200mm
Ramp 900x2300mm

Groundworks

- 8 x 600x600 Paving
- 8 x 300x600 Paving
- 9 x 300x900 Paving
- 12 x Sharp Sand
- 2 x Cement
- 1 x Medium Skip