



| Product Information | |
|---|-----------------------|
| Ibstock Code: | 0587 |
| Type: | Wirecut |
| Facing Description: | Smooth |
| Dry Brick Weight (kg): | 2.3 |
| Pack Quantity: | 400 |
| Packaging (standard): | banded (plastic) |
| Technical Specification (to BS EN 771-1) | |
| Brick Dimensions (L x W x H mm): | 215x102x65 |
| Size Tolerances Mean & Range: | T2 R1 |
| Configuration: | Vertically Perforated |
| Voids (%): | 20-25 |
| Compressive Strength (N/mm ²): | >= 60 |
| Active Soluble Salts: | S2 |
| Water Absorption (% weight): | <= 8 |
| Durability: | F2~ |
| Gross Dry Density (Sound Insulation) (Kg/m ³): | 1630 |
| Equivalent Thermal Conductivity "K" value 5% Exposed: | 1.12 |
| Initial Rate of Absorption (Suction Rate) (Kg/m ² /min): | 0.30 |
| EAN: | 5036335031605 |