



EXISTING DRAINED AREA HATCHED IN BLUE
 ADDITIONAL DRAINED AREA HATCHED ORANGE

Linwood

EXISTING FOUL & SURFACE WATER
 (COMBINED) OUTFALL FROM SITE
 TO BE RETAINED

ALL EXISTING AND PROPOSED SURFACE WATER
 DRAINAGE TO BE TAKEN INTO ATTENUATION TANK.
 TANK CAPACITY TO BE 56CU M OF CELLULAR BLOCKS
 (BASED ON 95% VOID RATIO.
 HYDROBREAK DEVICE ON TANK OUTLET TO LIMIT DISCHARGE TO
 13.3LIT/SEC

NEW FOUL DRAINAGE

NEW S.W. DRAINAGE



OFFICE ONE,
 34 VICTORIA ROAD,
 BARNSELY,
 S70 2BU

Phone: 01226 208482

Email: info@whiteaguspartnership.co.uk
 Web: www.whiteaguspartnership.co.uk

ARCHITECTURAL SERVICES

Project:
 PROPOSED RETAIL DEVELOPMENT
 CASTLE VIEW, DODWORTH,
 BARNSELY S75 3LF

Client:
 FORD PROPERTIES LTD

Drawing
 Title:
 DRAINAGE

Date:
 OCT 2020
 Scale:
 1:200@ A3
 Ref:
 17-183
 Dwg. No.
 07
 Rev.
 A

Date	Suffix	Description	Date	Suffix	Description
17-12-20	A	OUTFALL DETAILS CLARIFIED			