SITE PLAN 1:200m.

* FW+SW DRAINS TO BE INVESTIGATED WITH + DISCUSSED WITH LOCAL BCO ON SITE.

N.

RETAIN EX BOUNDARY TREATMENT + SAND CEMENT RENDER TO EXTERNAL FACE.

HOLLY BANK.

NEW HOUSE.

THURLSTONE ROAD

24.

26.

28.

30.

25.

NEW GARAGE.

REPLACE UNSIGHTLY SELF SET HEDGE WITH SEMI-MATURE TRADITIONAL "CARPINUS" (HORNBEAM) HEDGING.

*NOTE - EX HEDGING WAS CHOKED WITH TREE IVY — CONSISTED OF SELF SET SYCAMORE + HAWTHORNE.

2 NO PARKING BAYS FOR QUARRY HOUSE 2.5M x 5.5M (TOTAL).

* NEW HEDGING TO BE MAINTAINED @ 1.8M WHEN MATURED *

DARK STAINED PALE BD PANELS

FENCE THRO D-E-F-G-H. CONC. POSTS + GRAVEL BOARDS

WALLS THRO A-B-C. MATCHING BLK

1.8M.

1.1M.