



EVA-07S-SE / EVA-07S-SE RFID
32amp VEHICLE CHARGING POINT

100MM DIA DUCT TO BE PROVIDED FROM HIGHWAY INTO EACH DWELLING FOR INSTALLATION OF HIGH SPEED FULL FIBRE BROADBAND. INSTALLATION OF THE ASSOCIATED CABLE/EQUIPMENT TO BE AGREED WITH PROVIDER INCLUDING TIMESCALE.

BOUNDARY TREATMENTS,SUBJECT TO AGREEMENT WITH ADJACENT OWNERS TO BE AS FOLLOWS:
POINT A TO B- EXISTING FENCE RETAINED OR NEW 1800MM HIGH FENCE TYPE A
POINTS B TO C - WALLS AND FENCES TO DETAILS
POINTS C TO D -EXISTING FENCE RETAINED OR NEW 1800MM HIGH FENCE TYPE A
POINTS D TO A- EXISTING NETWORK RAIL FENCE TO BE RETAINED. NEW 1800MM HIGH FENCE TYPE A TO BE CONSTRUCTED ALONGSIDE EXISTING FENCE.

-SIDE BOUNDARIES TO NEW DWELLINGS TO BE FENCE TYPE A
-NO BOUNDARY TREATMENTS PROPOSED TO PLOT FRONTAGES ALONG PRIVATE DRIVES.

2.0M HIGH ACOUSTIC BARRIERS BE CONSTRUCTED BETWEEN THE PROPOSED PRIVATE AMENITY SPACES AND STATION ROAD. THE ACOUSTIC BARRIERS TO BE AS SHOWN WITH CLOSE-BOARDED WEATHER-TREATED TIMBER FENCES (MIN18-20MM THICK) WITH COVER STRIPS OVER THE GAPS BETWEEN PANELS AND GRAVEL BOARDS TO SEAL THE GAP AT THE BASE AND MASONRY WALLS AS SHOWN



LOCATION PLAN

SCALE 1:1250

White Agus PARTNERSHIP
ARCHITECTURAL SERVICES
OFFICE ONE,
34 VICTORIA ROAD,
BARNSLEY.
S70 2BU
Phone: 01226 208482
Email: info@whiteaguspartnership.co.uk
Web: www.whiteaguspartnership.co.uk

Project. RESIDENTIAL DEVELOPMENT ON LAND AT STATION ROAD, DARTON BARNSLEY	Client. DEVELOPMENTS BY BOUTIQUE
Drawing Title. SITE PLAN	Date. SEPT 2021 / Scale. 1:500@ A3
	Ref. 20–100 / Dwg. No. 01 / Rev. D

Date	Suffix	Description	Date	Suffix	Description
14–09–21	A	REVISED TO CLIENTS REQUIREMENTS			
22–10–21	B	REVISED TO CLIENTS REQUIREMENTS			
25–10–21	C	PLOT 6 REVISED TO CLIENTS REQUIREMENTS			
18–12–21	D	REVISED TO HIGHWAY REQUIREMENTS			