

## **The Seam – Litter Bins**

1. Manufacturer: Wybone
  - 1.1. Product reference: MLB/224R Dual Steel Recycling Bin
2. Material: Galvanised steel
  - 2.1. Finish: Powder coated
  - 2.2. Colour: Silver

## **The Seam – ‘Timber’ Benches**

1. Manufacturer: Wybone
  - 1.1. Product reference: Wyatt Bench
2. Material: Specialist Plastic Slats & Galvanized Steel Frame
3. Size: 1900x620 mm H 920 mm
4. Method of fixing: Concrete fixings or RAWL bolts for ground fixing.
5. Finish: Specialist Timber Slats to give the aesthetic of wood as per the rest of Barnsley Town Centre.

## **The Seam – Metal Benches**

1. Manufacturer: METALCO
  - 1.1. Product reference: Libre benches collection LP200
2. Material: Stainless steel
  - 2.1. Finish: Powder coated
3. Size: 2000x584 mm H 451 mm (+ 300 mm)
4. Accessories/ Special requirements: Ground fixing kit  
Aluminum armrests
5. Method of fixing: Freestanding with pedestals or Installation with threaded bars

## **The Seam – Fixed Bollards**

1. Manufacturer: Frontier Pitts Ltd
  - 1.1. Product reference: PAS 68 HVM Static Terra Jupiter Bollard – 7.5t at 50 mph
2. Finishes
  - 2.1. Finish: Stainless Steel Sleeve
  - 2.2. Colour: Silver
3. Reflective banding: Recessed, Single
4. Dimensions
  - 4.1. Size and profile: Ø273 mm.
  - 4.2. Height: 1000 mm.
  - 4.3. Length below ground: 750 mm.2000x584 mm H 451 mm (+ 300 mm)

## **The Seam – Automatic Bollards**

1. Manufacturer: Frontier Pitts Ltd
  - 1.1. Product reference: IWA 14 Terra Universal Bollard 7.2t @ 80kph
2. Material: Carbon steel
  - 2.1. Finish: Stainless Steel Sleeve
  - 2.2. Colour: Silver
3. Special features: Red reflective band, 150 mm high at top of bollard
4. Dimensions

4.1. Size and profile:  $\varnothing$ 245 mm.

4.2. Height: 1000 mm.