

Trees adjacent existing footpath	No	Girth	Root	Code
Carpinus betulus 'Fastigiata'	5	14-16cm	RB	TR1
Copse area A	No	Girth/Height	Root/Pot size	Density
Alnus glutinosa	2	10-12cm	RB	-
Tilia cordata	1	12-14cm	RB	-
Cornus sanguinea	14	60-90cm	BR	0.75m ctrs
Corylus avellana	10	60-90cm	1+1	0.75m ctrs
Crataegus monogyna	7	60-90cm	1+1	0.75m ctrs
Prunus spinosa	10	60-90cm	1+1	0.75m ctrs
Rosa canina	3	40-60cm	BR	0.75m ctrs
Salix caprea	10	60-90cm	BR	0.75m ctrs
Viburnum opulus	14	40-60cm	1+1	0.75m ctrs
Copse area B	No	Height	Root/Pot size	Density
Acer campestre	2	10-12cm	RB	-
Sorbus aucuparia	2	10-12cm	RB	-
Cornus sanguinea	24	60-90cm	BR	0.75m ctrs
Corylus avellana	18	60-90cm	1+1	0.75m ctrs
Crataegus monogyna	12	60-90cm	1+1	0.75m ctrs
Prunus spinosa	18	60-90cm	1+1	0.75m ctrs
Rosa canina	6	40-60cm	BR	0.75m ctrs
Salix caprea	18	60-90cm	BR	0.75m ctrs
Viburnum opulus	24	40-60cm	1+1	0.75m ctrs
Copse area C	No	Height	Root/Pot size	Density
Alnus glutinosa	2	10-12cm	RB	-
Tilia cordata	1	12-14cm	RB	-
Cornus sanguinea	15	60-90cm	BR	0.75m ctrs
Corylus avellana	11	60-90cm	1+1	0.75m ctrs
Crataegus monogyna	8	60-90cm	1+1	0.75m ctrs
Prunus spinosa	11	60-90cm	1+1	0.75m ctrs
Rosa canina	4	40-60cm	BR	0.75m ctrs
Salix caprea	11	60-90cm	BR	0.75m ctrs
Viburnum opulus	15	40-60cm	1+1	0.75m ctrs
Pond perimeter	No	Height	Root/Pot size	Density
Cornus sanguinea 'Midwinter Fire'	11	40-60cm	3L	3/sq.m.
Corylus avellana	15	40-60cm	1+1	3/sq.m.
Fragaria vesca	15	20-30cm	2L	6/sq.m.
Rubus fruticosus	25	60-90cm(D)	2L	5/sq.m.
Salix cinerea	7	60-90cm	BR	3/sq.m.
Salix caprea	8	60-90cm	BR	3/sq.m.
Viburnum tinus	15	30-40cm	3L	4/sq.m.

PLANTING NOTES

Subsoil: Should be ripped and free draining

Topsoli: Planted areas to be cultivated to an approximate depth of 150mm prior to planting (any existing weedgrowth to be treated with a Glyphosate based herbicide no less than 14 days prior to cultivation).

Trees: To be planted in pits exceeding dimensions of root system by 100mm in each direction. Bottom of pit to be broken up to aid drainage. Peat free compost to be incorporated into the backfill. Trees to be secured using 75mm diameter pressure treated timber stake and tied at low level. Trees should not be planted within 5m of a building. Root barrier to be installed where trees planted adjacent services.

Shrubs: To be planted in pits exceeding dimensions of root system by 50mm in each direction. Peat free compost to be incorporated into the backfill.

Bark mulch: Planted areas to be dressed with bark mulch to a settled depth of 50mm.

General: All planting material to be true to type and size and in accordance with BS 3936 part 1. Plant stock to be watered to field capacity on completion of works and watered regularly especially during periods of warm/ dry weather.

 PHOENIX LANDSCAPE SERVICES LTD Unit 22 New Meadows, 53 Mowbray Street, Sheffield S3 8BN Tel: 0114 400 082 / 07403 65578 info@phoenixls.co.uk / www.phoenixls.co.uk		Client Mr and Mrs A. Oliver	
		Project Field Works, Moorend Lane, Silkstone Common, Barnsley S75 4RW	
		Title Soft Landscape Proposals Planting Schedule	
Layout number OLIV/MOOR/004	Rev	Drawn by AM	Date 24/10/22