

Burns Totara Burnsley
 Claycliff Island
 Burnsley
 575 215.

Area Landscaped As Per
 Specification Enclosed From
 Hudson Horticultural Ltd.

SECONDARY ENTRANCE TO
 COMPOUND WITH TARMAC
 FINISHED AND RIGGED WITH
 KERR STONES. 3x DROP DOWN
 SECURITY BOLLARDS AT 1m CENTRES.

2.4m PALISADE FENCE
 IN GALVANIZED STEEL
 SPEC SHEET ENCLOSED

NEW VEHICLE STORAGE
 COMPOUND

6.4m HIGH CCTV POLE
 WITH DOLBY CAMERA
 AND 4x 400WATT
 SONIUM FLOODLIGHT

EXISTING VEHICLE
 STORAGE COMPOUND

EXISTING BOUNDARY
 FENCE TO BE REMOVED.

LANDSCAPED SOIL SCREENED

2.4m PALISADE FENCE
 FINISHED IN GREEN
 WITH POSTS AT 2m
 CENTRES.

NEW VEHICLE STORAGE COMPOUND

EXISTING LAND TO BE SCARPED LEVEL AND SOIL PUSHED
 TO THE REAR TO FORM SOIL SCREENING MOUND APPROX
 2m HIGH PLANTED AS PER SPECIFICATION ENCLOSED FROM
 HUDSON HORTICULTURAL LTD. 150mm CRUSHED CONCRETE BASE
 TOPPED WITH 75mm TARMAC SCALPING ALL LEVELS AND
 ROLLED TO FORM POROUS HANDSTANDING BASE.

EXISTING VEHICLE STORAGE COMPOUND

EXISTING HANDLING BASE TO BE REPAIRED AND LEVELLED AND
 TOPPED WITH 75mm OF TARMAC SCALPING ROLLED AND
 LEVELLED TO FORM POROUS HANDSTANDING BASE.

DATE: 26th JANUARY 2013

APPLICATION NO: 2013/0061

SCALE 1:500