

Wavin Stormwater Management



CONNECT TO BETTER

Other Unit(s)

The following unit(s) can also be used with, or in place of the recommended unit.

Drainage Details

Area	200m ²
Catchment Type	Roof + Hardstanding
Area Reduction Factor	0.9
Soil Type	Over consolidated clay

Allowable Discharge	3 ltr/sec
Climate Change	40%
Effective Area	252m ²
Factor of Safety	1

Rainfall Data

R Value	0.36
M5-60	19

Storm Return Period	1 in 30 years
County	South Yorkshire - Barnsley

Time	Z1 Value	y mm	Z2 Value	p mm	Inflow	Outflow	Storage Volume
5min	0.36	6.84	1.43	9.78	2.46	0.9	1.56
10min	0.51	9.69	1.46	14.15	3.57	1.8	1.77
15min	0.62	11.78	1.47	17.32	4.36	2.7	1.66
30min	0.79	15.01	1.51	22.67	5.71	5.4	0.31
1hr	1	19	1.51	28.69	7.23	10.8	-3.57
2hr	1.21	22.99	1.52	34.94	8.81	21.6	-12.79
4hr	1.5	28.5	1.51	43.04	10.84	43.2	-32.36
6hr	1.7	32.3	1.49	48.13	12.13	64.8	-52.67
10hr	1.9	36.1	1.49	53.79	13.55	108	-94.45
24hr	2.4	45.6	1.45	66.12	16.66	259.2	-242.54
48hr	2.9	55.1	1.41	77.69	19.58	518.4	-498.82

Critical storm duration (hrs)	10min
Required Storage Height	1.77m
Volume from Dimensions	2.28m ³

Area Sales Manager

If you would like to find out how to purchase, please contact your Area Sales Manager

Name	Michelle Amesbury
Phone Number	07970 511099

Aquacell Disclaimer

- All information generated by this tool is supplied in good faith and without charge to enable reasonable assessment of the practical performance of Wavin products.
- Wavin offers a program of continuous improvement and reserves the right to modify the specification of products without notice.
- All information in this publication is believed to be correct at time of preparation. However, no responsibility can be accepted for any errors or omissions. Final determination of the suitability of information or material for the use contemplated and the manner of the use is the sole responsibility of the user
- Calculations are based upon relevant industry standards in accordance with the Wallingford Procedure, and should be verified by a qualified engineer.