Peak District National Park

Approximate location of existing wooden pylon and electric meter shed. To be removed as part of other works

Proposed metal fence to tie into existing

Existing grass area

Amenity area including open grass space for flexible use

Proposed benches and picnic tables (including accessible tables) within grassed amenity area

Relocated Tour de France artwork sculpture

Existing stone wall and pillar to be retained and modified (length reduced) to allow a wider entrance

Proposed horse hitching rails

Flush kerb

Horsebox parking area

New amenity area (325sqm)

Relocated and refurbished TPT information board (*note: preferred location for relocation of informal memorial is to be confirmed*)

Relocated and refurbished railway 'trolley'

Existing TPT entry sign to be retained and refurbished

Relocated and refurbished TPT sign

Proposed feature gate location

New car park area (2390sqm including tarmac surface, parking bays, and horsebox parking)

Proposed speed hump

Proposed speed hump

Relocated parish notice board, new litter bin and dog waste bin near bus stop

Existing stone wall and pillar to be retained

Bus parking area proposed to be delineated with white road marking paint

BUS ONLY

Drop kerb

Proposed tree planting in this area reflects tree planting as proposed in main VIP Peak District East Project

292.00
291.75
291.50
291.25
1:30
291.00
290.75
290.50
290.25

Proposed new accessible link (compliant with British Standard 8300-1 Design of an Accessible and Inclusive Built Environment). Requested by members of the VIP Peak District East Project Stakeholder Reference Group. Groundworks and minor regrading will be required to achieve this path.

290.10

Existing National Grid access road

Grass area and planting to be implemented as per main VIP Peak East Project

290.50

Proposed wildflower grassland in this area is to be implemented as per main VIP Peak District East Project

Low growing shrub planting fringing footpath to bus stop

Existing stone wall to be retained

Peak District National Park millstone boundary marker to be retained

Existing National Grid gate to be retained

291.75
292.00
292.25
1:35

Existing Stone Boundary Wall

KEY

- EXISTING PATH — TAR SPRAY & CHIP
- PROPOSED CAR PARK (H1) — MID GREY ULTICOLOUR TARMAC
- PROPOSED PATH SURFACING (H2) — TAR SPRAY & CHIP TO MATCH EXISTING TPT SURFACE
- EXISTING GRASS
- PROPOSED CAR BAYS (S1) — REINFORCED GRASS
- PROPOSED ACCESSIBLE CAR BAYS (S1) — REINFORCED GRASS
- PROPOSED AMENITY GRASSLAND (S2)
- PROPOSED WILDFLOWER GRASSLAND (S3)
- PROPOSED NATIVE TREES (S4) — BETULA PENDULA IN CAR PARK, AND OTHER SPECIES INCLUDING ACER CAMPESTRE AND SORBUS AUCUPARIA
- PROPOSED LOW GROWING NATIVE SHRUB PLANTING (S5)
- PROPOSED BENCH (H3)
- PROPOSED PICNIC TABLE (H4) — INCLUDING ACCESSIBLE TABLES
- PROPOSED LITTER BIN (H5)
- PROPOSED BOLLARDS (H6)
- PROPOSED KERB (H7) — 125mm HEIGHT. PRE CAST CONCRETE
- EXISTING METAL FENCE TO BE RESTORED (H8)
- PROPOSED METAL FENCE TO MATCH EXISTING (H8)
- PROPOSED CAR PARK CONCRETE WHEEL STOP (H9)
- EXISTING STONE WALL WITH STONE POSTS (H10)
- EXISTING TREE GROUPS/ VEGETATION RETAINED (S)
- RELOCATED AND REFURBISHED SIGNAGE / ELEMENTS
- PLANNING APPLICATION RED LINE BOUNDARY
- PEAK DISTRICT NATIONAL PARK BOUNDARY
- MIXED NATIVE WOODLAND PROPOSED AS PART OF MAIN VIP PEAK DISTRICT EAST PROJECT
- PROPOSED MIXED LOW GROWING NATIVE SCRUB PROPOSED AS PART OF MAIN VIP PEAK DISTRICT EAST PROJECT

rev	details	by	date
00	FIRST ISSUE	AG	12.06.19
01	REVISIONS MADE FOLLOWING STAKEHOLDER COMMENTS	KH	03.10.19
02	MINOR REVISIONS	KH	31.10.19
03	MINOR COMMENTS	KH	12/11/2019
04	MINOR COMMENTS	RG	13/11/2019
05	FOR PLANNING	KH	18/11/2019
06	MINOR REVISIONS - FOR PLANNING	RG	19/11/2019
07	MINOR REVISIONS - FOR PLANNING	RG	20/11/2019

rev	details	by	date

Notes

1. Do not scale from drawing, use figured dimensions only.
2. All dimensions to be checked onsite.
3. This drawing to be read in conjunction with all other Gillespies drawings and specifications.

Ordnance Information shown is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationary Office @ Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Licence No. 1000 17362

N

Project title
Visual Impact Provision (VIP)
Peak District East
Dunford Bridge Car Park Redesign

Drawing title
General Arrangement Plan

Drawing number P10727 -00-002-10107

Revision

Drawing Status
FOR PLANNING

Date	Scale	Drawn	Checked
20.05.19	1:200 @A1	AD	AG

© copyright GILLESPIES LLP, all rights reserved

Client
nationalgrid
Name here
Address line 1
Address Line 2
P: ***** *** *** F: ***** *** ***

GILLESPIES
5th Floor, Phoenix House, 3 South Parade, Leeds, LS1 5QX
P: 0113 247 0500 F: 0113 247 0660 E: design.leeds@gillespies.co.uk