

BARNSELY HOSPITAL NHS FOUNDATION TRUST

Application for planning permission and consent to display advertisements(s)

Town and Country Planning Act 1990

Town and Country Planning (Control of Advertisements) (England) Regulations 2007

Identification of specification of signs proposed and location of signs – ATTACHMENT "B"

1. Specification of display signs

All signs are modelled upon the NHS signage which appears on site.

a) Type A (larger single)

Signs to be made from 2 x 80mm diameter aluminium poles. Maximum length 3.5 metres (including advertisement panel) with flat 3mm cap fixing. Integrated aluminium panel - 1500 x 800mm. Advertisement area 1500 x 600mm, with NHS branding to top & bottom @1500 x 100mm. All signs to be pantone 300 NHS blue to correspond with existing on site signage. Poles to be fixed to a depth of 600-800mm depending on ground conditions. Poles will be cut to desired length on site to enable advertisement panel to be viewed above boundary wall level.

Hand dug holes in case of Cables/Pipes etc. Poles will be concreted in place and ground made good, grass and plants restored. Depending on location, the advertisement may appear on both sides of the panel

Details required for section 28 parts (a)(b)(c) and (d) of planning application form

(a) Absolute maximum is 2 metre where installed behind wall or other obstruction.

(b) 1500 x 600mm

(c) Not known as no advertisements yet identified but logically within the height of the advertisement area shown in (b) say 400mm

(d) Not known as no advertisements yet identified. Any unused background will be pantone 300 NHS blue

b) Type A Variant (larger - twin aspect)

As for Type A (larger single) but two panels side by side at approximately 30 degrees to each other to facilitate viewing from two angles. These may be used at locations **BE 5** (entrance to hospital car park off Pogmoor Road), **BE 9** (junction of Gawber Road and Pogmoor Road) **BE 2** (junction of Pogmoor Road and Summer Lane), **BE 10** and **BE 11** (main entrance to Hospital off Gawber Road). Depending on location, the advertisement may appear on both sides of the panels

Details required for section 28 parts (a)(b)(c) and (d) of planning application form

(a) Absolute maximum is 2 metre where installed behind wall or other obstruction.

- (b) 1500 x 600mm**
- (c) Not known as no advertisements yet identified but logically within the height of the advertisement area shown in (b) say 400mm**
- (d) Not known as no advertisements yet identified. Any unused background will be pantone 300 NHS blue**

c) Type B (Smaller)

Signs to be made from 2 x 80mm diameter aluminium poles. Maximum length 2 metres (including advertisement panel) with flat 3mm cap fixing. Integrated aluminium panel. Advertisement area 1000 x 560mm. All sign to be pantone 300 NHS blue to correspond with existing on site signage. Poles to be fixed to a depth of 600-800mm depending on ground conditions. Poles will be cut to desired length on site. Hand dug holes in case of Cables/Pipes etc. Poles will be concreted in place and ground made good, grass and plants restored. Depending on location, the advertisement may appear on both sides of the panel

Details required for section 28 parts (a)(b)(c) and (d) of planning application form

- (a) Absolute maximum is 650mm.**
- (b) 1000 x 560mm**
- (c) Not known as no advertisements yet identified but logically within the height of the advertisement area shown in (b) maximum say 350mm**
- (d) Not known as no advertisements yet identified. Any unused background will be pantone 300 NHS blue**

d) All signs

All signs will carry the Logo and branding of the Barnsley Hospital NHS Foundation Trust and the NHS above and below the advertisement respectively

2. Location of signs

Please refer to the filed plan "A". On that plan the locations of signs are indicated by the designation "BE" followed by a number, e.g. BE 1, BE 2 etc. Each of those locations will, if used, be the location of a sign of either Type A, Type A Variant or Type B design.

Details of the locations and Type A, Type A Variant or Type B signs which may be used are as follows:

Location	Type A	Type B	Note
BE 1	Yes		Taller sign design used to enable sign to be seen above retaining wall
BE 1A		Yes	
BE 2	Yes		Taller sign design used to enable sign to be seen above boundary fence.

			Possible site of sign Type A Variant
BE 3		Yes	
BE 4	Yes		Taller sign design used to enable sign to be seen above retaining wall
BE 5	Yes		Taller sign design used to enable sign to be seen above retaining wall. Possible site of sign Type A Variant
BE 6	Yes		Taller sign design used to enable sign to be seen above retaining wall
BE 7A		Yes	
BE 7B		Yes	
BE 8	Yes		Taller sign design used to enable sign to be seen above retaining wall
BE 9	Yes		Taller sign design used to enable sign to be seen above retaining wall. Possible site of sign Type A Variant
BE 10	Yes		Taller sign design used to enable sign to be seen above retaining wall. Possible site of sign Type A Variant
BE 10A	Yes		Taller sign design used to enable sign to be seen above retaining wall
BE 11	Yes		Taller sign design used to enable sign to be seen above retaining wall. Possible site of sign Type A Variant
BE 13		Yes	
BE 14		Yes	Taller sign design used to enable sign to be seen above retaining wall

Note: There is no Sign numbered 12.