



- n. PLANTING
  - Planting shall take place between November and March.
  - Planting areas shall be weeded to be weed free prior to planting.
  - Planting areas cultivated 300 mm deep and stone picked of any material greater than 50mm in any direction.
  - Approved planting compost and slow release fertiliser shall be incorporated into the topsoil during planting.
  - Planting beds shall be mulched with 75mm depth density grade bark mulch on completion.
  - Planting areas shall be watered to field capacity on completion.

B = Bare root (bagged).  
C = Container (or pot) grown, followed by size of the container (or pot).  
FORM = Shape of tree as supplied by the nursery.  
RB = Rootballed (balled and wrapped).  
SIZE = Height or Spread of juvenile plant.  
STD = (clear stem) Standard.  
STOCK = Root condition/protection method eg Bare root.  
Trans = Transplant (or undercut seedling).  
- Refer to specification for further information.  
- All plants to be completely hardened off  
- Substitutions to be agreed with Landscape Architect.  
Plant Schedule generated by "Oscap" software 05/07/2024

Project - Organisation - Volume/System - Level - Type - Role - Number  
**2763-URB-LS-00-DR-L-208150**